



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
EDISON, NEW JERSEY 08837

2 8

0382

36621

September 18, 1987

MEMORANDUM

SUBJECT: SAAD Waste Oil Geotechnical Investigation Draft Report

FROM: George R. Prince, Environmental Scientist  
Environmental Impact Section  
Environmental Response Branch

A handwritten signature in black ink, appearing to read "George R. Prince".

TO: Greg Powell, OSC  
EPA, Region IV

I have attached a copy of a draft report from our EERU contractor covering the drilling program we conducted at the SAAD waste oil site in Nashville, TN. This report will probably remain in draft form as our current contract has expired.


We garnered a significant amount of information from our investigations at the SAAD site. Most of this information is included in this report, but may further require some explanation. We should get together at your convenience to discuss our past efforts and evaluate future needs for removal actions at this site.


Call me if you have any questions at FTS 340-6649.

Attachment

call on 3/29/88

~~3rd~~ week of April - maybe  
4th





**Figure 2**  
**Saad Waste Oil**  
**Tank and Boring Locations**  
**Scale 1" = 52.5'**

TOTAL VOC'S = 12

280384

**TABLE 7**  
**VOLATILE ORGANICS AND PESTICIDES/PCB'S IN WATER**  
**Concentrations Reported In ug/L**

Parameter	Borehole No./Date									
	B-1 3/23/87	B-2 3/23/87	B-4 3/23/87	B-5 3/23/87	B-6 3/23/87	B-7 3/26/87	B-14 3/26/87	B-17 3/23/87	B-19 3/23/87	B-21 3/25/87
Lab Sample No.	5710	5709	5707	5705	5706	5715	5714	5708	5711	5713
Methylene Chloride				200*		53*	2500			1*
Trans-1,2-Dichloroethane	63		420	1200	1900	1800	4100	270	560	14
Chloroethane										13
Toluene	88	4000	1100	7500	360	210	4100			
Total xylenes	1900	880	1500	1100*	150*		310			9
Acetone										68
Chloroform										
Ethyl benzene	220	120*	180				110*			
2 Butanone										9*
4 Methyl-2-pentanone							210*			
Benzene	7*	55*								
1,1 Dichloroethane	78		55	120*	67*	81*	110*	14	39*	33
1,1,1-Trichloroethane										8
Trichloroethene							5000			.
Vinyl chloride	64		120		280	350		22	140	18
Carbon disulfide				110*						
Pesticides/PCB's	ND	ND		ND	ND	ND	ND	ND	ND	ND
4,4 - DDT			.56							

ND - None Detected

\*Denotes a value below the limit of quantification that is considered approximate





Figure 2  
Saad Waste Oil  
Tank and Boring Locations  
Scale 1" = 52.5'

TOTAL VOC'S N/A

0386



**VOLATILE ORGANICS AND PESTICIDE PCB'S IN SOIL**  
**Concentrations Reported In ug/kg**

Parameter	Borehole/Depth										SSS1 (Oil) (ug/g)
	B-2 6.0'-7.5'	B-4 4.0'-5.0'	B-6 10.0'-13.0'	B-10 4.5'-6.0'	B-11 12.5'	B-11 14.0'	B-11 16.0'	B-14 3.0'-4.1'	B-18 6.5'-8.5'	B-18 6.5'-8.5' Duplicate	
Lab Sample No.	B-2, 5-5	B-4, 4'-5'	B-8,R-1,10-13	B-13,4,5-6	B-16,R-1,2,5	B-16,R-1,14	B-16,R-2,80B	B-20,3-4.1	B-24, R-1, 6.5'-8.5'	B-24,R-1 6.5'-8.5'	7334
Methylene Chloride			16	950					38*		670
Trans-1,2-Dichloroethane	2*		8*	13,000							
2-Hexanone			23*						270		
Toluene			54	29,000	53,000	100	3*	3,900			1300
Total xylenes	330	590	120	9,800		23		3,700			
Acetone	22			1,200*	1,100*	340	800	810*			
Chlorobenzene											
Ethyl benzene	95	110		2,200*	4,600	7*		610*	380		230
2 Butanone						71	96				
4 Methyl-2-pentanone	33			530*		38	49				
Benzene	5*										
1,1 Dichloroethane				18,000						19*	130
1,1,1-Trichloroethane				28,000							1700
Trichloroethene				930							4800
Tetrochloroethene				3,200							4800
Vinyl chloride											290
Trans-1,2-dichloroethylene											4200
Pesticides/PCB's (ug/g)	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Aroclor 1242 (ug/l)											36
Aroclor 1260 (ug/l)											17

ND - None Detected

\*Denotes a value below the limit of quantification that is considered approximate


**TABLE 8  
OFF-SITE GROUNDWATER**

Parameter	Sample									
	Croft Spring	Croft Spring	Croft Spring	Saad Monitoring Well	Saad Monitoring Well 9/87	Well #1 9/87	Well #2	Well #2 9/87	Well #3	Well #3 9/87
Lab Sample No.	SS-S-7-W	SS-CF-SP	7333	SS-SS-MW7	3334	7331	SS-CF-MG2	7332	SS-CF-MW3	7353
Sampling Program			3/87		3/87	3/87		3/87		3/87
1,1 Dichloroethane	2J	ND	ND	1,100	1,700		ND	ND	ND	ND
Chloroform	0.5J			11						
Chlorobenzene	2J									
Vinyl Chloride				6,600	9,800					
Methylene Chloride				19,000	5,500					
1,1 Dichloroethene				690						
Chloroethane				240						
Trans-1,2-Dichloroethane				95,000	52,000					
1,2 Dichloroethane				31						
1,1,1-Trichloroethane				15,000	6,300					
Trichloroethene				69,000	30,000	<5				
Benzene				67						
Tetrachloroethene				49,000	9,600					
Toluene				3,900	4,600					
Chlorobenzene				87						
Ethyl benzene				310	500					

ND - No VOA's detected in analysis

J - Estimated Value





0390






Figure 5  
Potentiometric  
Groundwater Surface  
Scale 1" = 52.5' Contour Interval 1'

2 8 0341





Scale 1:24,000  
Source: U.S.G.S. Oak Hill and Antioch,  
Tenn. topographic Quadrangles  
7.5 Minute Series

Figure 1  
Site Location Map  
Saad Waste Oil Site

**DRAFT**

**SAAD WASTE OIL**  
**Geotechnical Investigation**

**8/20/87**

## SUMMARY

**DRAFT**

The US EPA Emergency Response Branch (ERB) and contract support group (Environmental Emergency Response Unit [EERU]) were tasked by Region IV EPA to perform a three part investigation of the Saad Waste Oil Site, Nashville TN. (Figure 1). The three sections of this investigation include:

- 1) Assess quality and quantities of fluids stored in above and underground storage tanks at the Saad Waste Oil site.
- 2) Determine volume and extent of oil contaminated soil.
- 3) Evaluate shallow groundwater contamination and potential migration from the site.

The tank investigation identified 16,876 gallons of fluid in three phases. Pumping and batching fluids is suggested, followed by a sludge removal program.

The soil boring and sampling program identified 9,378 yd<sup>3</sup> of oil contaminated soil. The majority of this soil is on the Saad site, but there is migration to the southeast. Removal is unrealistic due to extent, volume and the water table in the oil contaminated soil. Remedial options include capping and a slurry wall/cutoff trench or in-situ stabilization. The latter is the most feasible due to the lack of perimeter space for a slurry wall or cutoff trench.

An examination of site groundwater demonstrated contaminant migration southeast and possibly a secondary northeast pathway. There was no correlation observed between the site and Croft Spring.

# TABLE OF CONTENTS

<u>Section and Title</u>	<u>Page No.</u>
LIST OF TABLES	iii
LIST OF FIGURES	iv
LIST OF APPENDICES	v
1.0 INTRODUCTION	1-1
2.0 FIELD INVESTIGATION	2-1
2.1 <u>Tank Investigation Program</u>	2-1
2.2 <u>Soil Boring and Sampling Program</u>	2-5
2.3 <u>Groundwater</u>	2-14
2.3.1 Site Groundwater	2-14
2.3.2 Off-Site Groundwater	2-19
3.0 CONCLUSIONS	3-1
3.1 <u>Tank Investigation Program</u>	3-1
3.2 <u>Soil Boring and Sampling Program</u>	3-1
3.3 <u>On-Site Groundwater</u>	3-2
3.4 <u>Off-Site Groundwater</u>	3-2

## LIST OF TABLES

<u>Table No.</u>	<u>Title</u>	<u>Page No.</u>
1	Tank Fluid Volume Estimates	2-2
2	Tank Samples, Key to Laboratory Analysis	2-3
3	Tank Samples, Laboratory Analysis Summary	2-4
4	Samples Collected and Analyzed	2-6
5	Physical Borehole Information	2-7
6	Volatile Organics and Pesticide/PCB's in Soil	2-8
7	Volatile Organics and Pesticides/PCB's in Water	2-15
8	Off-Site Groundwater	2-20



**LIST OF FIGURES**

<u>Figure No.</u>	<u>Title</u>	<u>Page No.</u>
1	Site Location Map Saad Waste Oil Site	1-2
2	Saad Waste Oil Tank and Boring Locations	1-3
3	Isopach of Oil Contaminated Soils	2-9
4	Bedrock Contours	2-11
5	Potentiometric Groundwater Surface	2-16
6	Concentrations of Prevalent Groundwater Constituents	2-17

## LIST OF APPENDICES

<u>Appendix</u>	<u>Title</u>	<u>Page No.</u>
A	ANALYTICAL RESULTS, TANK SAMPLING, SITE SOIL AND SITE GROUNDWATER	A-1
B	SOIL BORING LOGS	B-1
C	9/86 SAMPLING PROGRAM LAB RESULTS	C-1
D	MONITORING WELL INSTALLATION DETAILS	D-1
E	SINGLE WELL PUMPING TEST	E-1
F	PRIOR GROUNDWATER ANALYSIS	F-1
G	DAILY CHRONOLOGY OF FIELD ACTIVITIES	G-1



## 1.0 INTRODUCTION

Saad Waste Oil is the former John P. Saad Oil Company on Trousdale Blvd., Nashville TN (Figure 1). The operation began in 1970 and gained notoriety in 1978 when a pond at the west end of the site was found to contain waste solvents. Drums suspected of containing hazardous waste were found on the site in 1979.

The site, underlain by the Bigby-Cannon limestone and the Hermitage formations, exhibits karstic development. The suspect pond was rumored in a sinkhole that was partially on John P. Saad Oil Company and CSX Railroad property. Waste oil migration through the karstic formations to a major spring (Croft Spring), potentially downgradient of the site is a potential impact from the site. The spring discharges in a planned wildlife area of the Cumberland Museum. Prior investigations concentrated on the Croft Spring, attempting to identify a hydrologic connection between Croft Spring and CSX Railroad and/or Saad Waste Oil.

An electrical resistivity study (4/82) by Ecology and Environment (E&E) identified potential solution cavities that could direct flow from Saad Waste Oil and/or CSX to the Croft Spring. Seven monitoring wells were installed to confirm the electrical resistivity survey. Five monitoring wells were installed on the Croft Farm (Cumberland Museum property) and one each on Saad and CSX properties. A sampling program was conducted by NUS Corporation during 8/82 and 9/82.


ERB/EERU initially conducted surface and groundwater sampling program at the Croft Farm, Saad Waste Oil, and CSX Railyard (6/87). A soil boring, monitoring well installation, and sampling program concentrating on the Saad Waste Oil site was performed during 3/87 (Figure 2).



Saad Waste Oil Site

Scale 1:24,000  
Source: U.S.G.S. Oak Hill and Antioch,  
Tenn. topographic Quadrangles  
7.5 Minute Series

Figure 1  
Site Location Map  
Saad Waste Oil Site



**Figure 2**  
**Saad Waste Oil**  
**Tank and Boring Locations**  
**Scale 1" = 52.5'**

## 2.0 FIELD INVESTIGATION

The Saad Waste Oil field investigation program was designed to provide: information for removal of liquids stored on site in tanks, extent and volume of waste oil contaminated soils, and assessment of groundwater contaminant migration from the site.

### 2.1 Tank Investigation Program

The tank investigation program was designed to provide tank fluid volumes and chemistry, to be used in a removal program (Figure 2). Three visual classifications of tank fluid phases were used: water, oil water emulsion, and oil (Table 1). Fluid volume calculations were based on the these classifications (Table 1). Several samples were composited to reduce laboratory costs and simulate removal batching (Table 2 and 3, Appendix A).

A composite sample from Tanks 1, 4, 6, 11 and Truck Tank 16 (Lab Sample No's. 5719 and 5720, Table 3) sent for laboratory analysis, represented: 2,678 gallons of oil, 170 gallons of oil/water emulsion, and 2,557 gallons of water. Fluid removal should isolate Tank 1 (completely oil) and Tank 4 (water and oil/water emulsion). Tanks 6, 11, and Truck Tank 16 should be pumped with a two phase recovery system or passed through an oil water separator.

Tank 15 (Sample 1258) contains 161 gallons of oil and 2,713 gallons of water. Recovery could be similar to Tanks 6, 11, and Truck Tank 16. Batching the oil and water samples separately from the composite of Tanks 1, 4, 6, 11, 15 and Truck Tank 16 should be relatively simple with questionable recoverability of 161 gallons of oil from Tank 15 as a separate phase. This batching would produce 2,839 gallons of oil and 5,270 gallons of water.

**TABLE 1**  
**TANK FLUID VOLUME ESTIMATES**

<u>Tank Number</u>	<u>Phase</u>	<u>Fluid Volume (gallons)</u>	<u>Corresp. Lab Sample Number</u>	<u>Comments</u>
1	Oil	2,596	5719	Entire Volume Oil
2	----	----	----	Empty
3	----	----	----	Collapsed - No Access
4	Oil/Water Emulsion	45	5719	5% Oil Water-Emulsion
	Water	856	5719	95% Amber Liquid
6	Water	23	5719	100% Amber liquid
10	Oil/Water Emulsion	4,270	1260	Leaking @2.5'
11	Oil	82	5719	5% Oil
	Water	1,553	5719	95% Amber Liquid
12	Water	840	----	Not Sampled
13	----	----	----	Empty
14	----	----	----	Empty
15	Oil	161	1258	Oil Layer 0.3' Thick
	Water	2,713		
16	Oil/Water Emulsion	125	5720	50% Oil Water Emulsion
	Water	125	5720	50% Water
Oil Water Separator	Water	3,200	1261	
	Sludge	287		

TABLE 2

## TANK SAMPLES, KEY TO LABORATORY ANALYSIS

<u>Lab/Chain of Custody No.</u>	<u>Description of Tanks Sampled</u>	<u>Sample Date</u>
5719	Composite of Tanks: 1, 4, 6, 11 and Truck Tank 16	3/20/87
5720	Duplicate Composite of Tanks: 1, 4, 6, 11 and Truck Tank 16	3/20/87
1258	Tank 15	3/17/87
1260	Tank 10	3/18/87
1261	Oil/Water Separater Pit - Eastern Tank	3/18/87



TABLE 3

## TANK SAMPLES, LABORATORY ANALYSIS SUMMARY

Sample Parameter	Sample Number (Concentrations in ug/g unless noted)					
	Method Blank	5719	5720	1258	1260	1261
Acetone	32			1300		
2-Butanone	31		12	2900		
Methylene Chloride		13	19	6	220	
1,1-Dichloroethane		3*	4*			
1,1,1-Trichloroethane		22	24		9	
Trichloroethene		20	32	43	98	
Toluene		33	32	8	170	
Ethyl benzene		5*	5*			
Total xylenes		9	9		11	
4-Methyl-2-pentanone				68	15	
Tetrachloroethene		2*				
Pesticides/PCB's in Oil		ND	ND	ND	ND	ND
bis (2-Ethylhexyl) phthalate				1.1	474	3.9
Phenanthrene		21				0.11
Napthalene		44				
2-Methylnaphthalene		110				
Flourene		15				
<u>Detection Limit</u>						
Antimony	2.0	ND	ND	ND	ND	ND
Arsenic	1.0	ND	ND	ND	4.9	ND
Beryllium	0.1	ND	ND	ND	ND	ND
Cadmium	0.5	0.84	0.81	0.82	0.64	0.66
Chromium	0.4	7.58	7.86	20.6	76.6	14.1
Copper	0.5	28.4	27.3	33.5	3.3	13.7
Lead	3.5	574	728	549	25.8	136
Mercury	0.1	0.28	ND	ND	ND	ND
Nickel	0.75	3.3	2.6	1.4	4.3	2.9
Selenium	0.5	ND	ND	ND	ND	ND
Silver	0.25	ND	ND	ND	ND	ND
Thallium(2)		ND	ND	ND	ND	ND
Zinc	0.15	304	315	218	63.6	147
Flashpoint	°F	<7	<70	<72	<70	<70
% Ash		0.31	0.23	0.25	0.81	0.03
BTU/pound		9,350	8,500	0	15,300	500
Total Organic Halogens (1)		0.20	0.26	0.09	0.55	0.09

notes a value below the limit of quantification that is considered approximate

(1) TOX values are reported as % chlorine

(2) Detection Limits for thallium varied due to background corrections for matrix effects

ID None Detected

Tank 10 was sampled separately (Sample 1260) containing 4,270 gallons of oil/water emulsion and should be treated as a separate batch. Recovery could be through simple transfer pumping with the possibility of an oil/water separator.

The site oil/water separators contain 3,200 gallons of water and 39 cubic feet of sludge. The water phase can be easily pumped, with undetermined pumpability of the sludge. Passing the discharge through an oil/water separator is advisable.

Total tank fluid volumes include: 2,839 gallons of oil, 4,440 gallons of oil/water emulsion, and 8,470 gallons of water. After tank fluid removal is complete, the remaining material should be mainly sludges. A clean up program should be developed based on consistency of material encountered. Pressurized steam cleaning and pumping is an alternative to manually scraping the tanks.

## 2.2 Soil Boring and Sampling Program

The soil boring and sampling program was designed to identify the horizontal and vertical extent, chemical constituents, and volume of waste oil contaminated soil. There were 103 soil samples collected from 21 borings (Table 4). Nine soil samples, representative of the site, were collected for Volatile organic and Pesticide/PCB laboratory analysis (Tables 4, 5, 6, and Appendix A). The horizontal extent of visible oil contamination is outlined by the 2' contour on the Isopach of Oil Contaminated Soil (Figure 3). Vertical extent of contamination is identified on the soil boring logs in Appendix B. Thickness of contamination is identified by the isopach of oil contaminated soil.

Initially, the extent of contamination was estimated in the waste oil lagoon encompassing Borings B10, B11 (Monitoring Well 11) and Well SSS1 (Figure 3). Review of an earlier field program in the Franklin Brick Yard identified potential oil contaminated soil. The soil boring plan was designed to isolate brick yard contami-

**TABLE 5**  
**PHYSICAL BOREHOLE INFORMATION**

Original Numbering System	Modified Numbering System	Borehole Depth Below GS	Presence of Oil in Boring	Depth to Water Table Below GS	Ground Surface (MSL)	Bedrock Surface (MSL)
B-1	B-1	13.5'	Yes	7.57	581.7	568.20
B-2	B-2	17.5'	No	15.17	580.3	563.10
B-3	B-3	5'4"	No	- (1)	581.3	
B-4	B-4	9'1'	Yes	5.58	580.1	571.02
B-6	B-5	19.5'	Yes	7.22	581.5	562.0
B-8	B-6	20'2"	Yes	6.20	581.7	561.53
B-9	B-7	10.0'	Yes	6.62'	582.1	562.10
B-10	B-8	4.5'	Yes	- (1)	-	
B-11	B-9	5.25'	Yes	- (2)	581.5	
B-13	B-10	6'4"	Yes	- (2)	582.0	
B-16	B-11	17'8"	Yes	6.65'	582.2	564.53
B-18	B-12	10.5'	Yes	6.68'	581.8	
B-19	B-13	20'1"	Yes	-		
B-20	B-14	20.0'	No	2.31	581.4	561.40
B-21	B-15	2.25'	No	- (1)	581.8	579.55
B-22	B-16	3.5'	No	- (1)	581.4	577.90
B-23	B-17	14.25'	No	3.46'	578.7	564.95
B-24	B-18	8.5'	Yes	6.13'	581.8	573.30
B-25	B-19	18.0'	No	17.24	580.3	563.80
B-26	B-20	15.0'	No	4.44	581.1	566.10
B-27	B-21	18.0'	No	6.77'		

- (1) Borehole completed above Water Table.  
(2) Borehole collapse above Water Table.

2 8 0408

**TABLE 6**  
**VOLATILE ORGANICS AND PESTICIDE PCB'S IN SOIL**  
**Concentrations Reported In ug/kg**

Parameter	Borehole/Depth										
	B-2 6.0'-7.5'	B-4 4.0'-5.0'	B-6 10.0'-13.0'	B-10 4.5'-6.0'	B-11 12.5'	B-11 14.0'	B-11 16.0'	B-14 3.0'-4.1'	B-18 6.5'-8.5'	B-18 6.5'-8.5' Duplicate	SSS1 (Oil) (ug/g)
<b>Lab Sample No.</b>	<b>B-2, 5-5</b>	<b>B-4, 4'-5'</b>	<b>B-8,R-1,10-13</b>	<b>B-13,4,5-6</b>	<b>B-16,R-1,2,5</b>	<b>B-16,R-1,14</b>	<b>B-16,R-2,BOB</b>	<b>B-20,3-4.1</b>	<b>B-24, R-1, 6.5'-8.5'</b>	<b>B-24,R-1 6.5'-8.5'</b>	<b>7334</b>
Methylene Chloride			16	950					38*		670
Trans-1,2-Dichloroethane	2*		8*	13,000							
2-Hexanone			23*						270		
Toluene			54	29,000	53,000	100	3*	3,900			1300
Total xylenes	330	590	120	9,800		23		3,700			
Acetone	22			1,200*	1,100*	340	800	810*			
Chlorobenzene											
Ethyl benzene	95	110		2,200*	4,600	7*		610*	380		230
2 Butanone						71	96				
4 Methyl-2-pentanone	33			530*		38	49				
Benzene	5*										
1,1 Dichloroethane				18,000						19*	130
1,1,1-Trichloroethane				28,000							1700
Trichloroethene				930							4800
Tetrochloroethene				3,200							4800
Vinyl chloride											290
Trans-1,2-dichloroethylene											4200
Pesticides/PCB's (ug/g)	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Aroclor 1242 (ug/l)											36
Aroclor 1260 (ug/l)											17

ND - None Detected


\*Denotes a value below the limit of quantification that is considered approximate


nation or connect it to oil migrating from the site. The soil boring program identified oil contaminated soil from the site, thinning southeast to the brick yard area. (Figure 3).

Clean areas (borings with no visible oil contamination) north and east are delineated by boreholes 17, 19, 20, and 21. Clean areas to the south and west are identified by boreholes 2, 14, 15, and 16. Rail lines prohibited definition of the western and southeastern boundaries of oil contaminated soil. These clean classifications are based on visual examination of soil samples. Questionable boundaries exist at the Franklin Brick Co. office and shop building and the Klein Coach Co. building.

An isopach (Figure 3) was developed to calculate oil contaminated soil volumes. Sources for the oil contaminated soil thickness are the soil boring logs in Appendix B. The total estimate of oil contaminated soil is 9,378 yd<sup>3</sup>. This estimate does not include clean soil overlying the contaminated material. Volumes were calculated using Figure 3 and a compensating polar planimeter. The majority of waste oil contaminated soil is within site property boundaries.

Bedrock topography and waste oil contaminated soil were compared to identify possible oil migration correlations with bedrock configuration (Figure 4). Sources for the Bedrock Contour maps were boring logs in Appendix B, summarized in Table 5. Bedrock contours approximately reflect waste oil migration on the site and to the southeast. The bedrock high at boring B18 southeast of the site does not correlate with the oil migration at the soil rock interface. Boreholes 1 and 4 represent additional oil contaminated soil areas that are upgradient of the site based on bedrock topography. There is no information available west of the site.





**Figure 4**  
**Bedrock Contours**  
Scale 1" = 52.5' Contour Interval 2'

28 0412

Samples for soil chemistry analysis (Table 6, Appendix B & C) were collected with split barrel or continuous tube samplers, represented on boring logs by S and R designations, respectively. Equipment was pressure steam cleaned between samples. Split barrel samples were more reliable in obtaining a sample. However, when the continuous tube sampler worked, samples were larger and appeared less disturbed.

Volatile organic concentrations were higher in the lagoon area, represented by soil samples B-10, B-11 and oil sample SSS1. There are three compounds that may be considered markers for the site: Toluene, Total xylenes, and Ethyl benzene. Concentrations indicate migration to the southeast decreasing with distance from the proposed lagoon (B-6, 4, 2, and 18 in increasing distance from the lagoon). There were no Pesticide/PCB's identified in any soil samples, just in the soil sample from Well SSS1.

Vertical attenuation of concentrations is represented by samples collected from borehole B-11 at 12.5', 14.0', and 16.0'. Visual oil concentrations that decreased with depth were supported by laboratory analysis (Table 6).

Examination of the log for borehole 14 does not identify oil migration to the south, although volatile organic concentrations in the soil are considerable. A possible explanation is the auger refusal prohibiting sampling of borehole 14 below 4.1' or water phase contaminant transport.

An Auto Skimmer was installed in existing wells SSS-1 and MW11 during the March, 1987 drilling program. The purpose of the Auto Skimmer was to determine passive recoverability of product from the Saad Site. Passive product recoverability does not use a watertable depressing pump to increase the hydraulic gradient to the well. The advantage of a passive system is no discharge from a depressant pump to be disposed of or injected back to the formation.



The Auto Skimmer is a top filling bailer that is lowered to the water table where the buoyancy of the bailer triggers an incremental lowering of the bailer. When the bailer begins filling, the buoyancy changes and the lowering process stops. After filling, the bailer is raised to the surface and emptied through an oil/water separator.

Both wells are located in the area of the reclaimed waste oil lagoon. Well SSS1 is cased through the unconsolidated zone with an open borehole in rock. Well MW11 is screened from approximately two feet above the water table to the soil/rock interface.

The first skimmer test was performed on Well SSS1. There was free product in the well, but an accurate thickness measurement could not be obtained. Water level paste and an EMTEC interface probe were coated by the oil and did not identify the water level. Approximately two gallons of oil were skimmed from the well during the initial cycles of the unit. After the initial recovery, there was no product recharge to the well during a six hour test period. All recovered product was casing storage based on initial water level measurements and displacement of two gallons of product in a 4-inch well. A possible explanation of product storage in the casing could be a seasonally fluctuating water table forcing product into the casing. There was no product recovery from a second test of similar duration.

The Auto Skimmer was installed on monitoring well MW11 immediately after installation. There was an immeasurable product layer noted in the well prior to well installation. The unit operated for several hours with no product recovery.

An auto skimmer was installed in monitoring wells to experiment with passive (no drawdown pump) product recovery. There was no product recharge in the monitoring wells, eliminating passive recovery as a remedial alternative.

## 2.3 Groundwater

### 2.3.1 Site Groundwater

Boreholes from the soil boring and sampling program were used to sample and monitor site groundwater levels. If the water table was encountered, temporary screens and casing were installed in boreholes. Monitoring wells were installed in three boreholes, B14, 11, and 18 (Appendix D). All screens were placed above the water table. There were ten water samples collected for volatile organics and pesticide/PCB analysis (Table 7). Sampling equipment was decontaminated with successive detergent, distilled water, methanol, and distilled water rinses between samples. Groundwater levels were measured with a Slope Indicator electrical tape and an EMTEC product/water measuring device. The Slope Indicator worked consistently, although the EMTEC device performed sporadically. Borehole locations and elevations were surveyed using Well SSS1 for vertical control and existing structures for horizontal control.

Groundwater flow direction and gradient was determined by creating a potentiometric groundwater surface map (Figure 5). A groundwater "trough" runs northwest to southeast through the northeast section of the site. The potentiometric map combined with the isopach of oil contaminated soil (Figure 3) correlate southeast contaminant migration. There is a possible second migration path to the northwest.


Laboratory analysis identified 5 prevalent volatile organics; 1,1 dichloroethane, trans-1,2-Dichloroethane, toluene, ethyl benzene and total xylenes (Table 7). Concentrations of each constituent are presented on Figure 6. Total xylene and ethyl benzene concentrations, two components found in gasoline, are concentrated around Trousdale Road and Franklin Brick Yard, with the exception of B-14 (W-14). Proximity to the road and an


**TABLE 7**  
**VOLATILE ORGANICS AND PESTICIDES/PCB'S IN WATER**  
**Concentrations Reported In ug/L**

Parameter	Borehole No./Date									
	B-1 3/23/87	B-2 3/23/87	B-4 3/23/87	B-5 3/23/87	B-6 3/23/87	B-7 3/26/87	B-14 3/26/87	B-17 3/23/87	B-19 3/23/87	B-21 3/25/87
Lab Sample No.	5710	5709	5707	5705	5706	5715	5714	5708	5711	5713
Methylene Chloride				200*		53*	2500			1*
Trans-1,2-Dichloroethane	63		420	1200	1900	1800	4100	270	560	14
Chloroethane										13
Toluene	88	4000	1100	7500	360	210	4100			
Total xylenes	1900	880	1500	1100*	150*		310			9
Acetone										68
Chloroform										
Ethyl benzene	220	120*	180				110*			
2 Butanone										9*
4 Methyl-2-pentanone							210*			
Benzene	7*	55*								
1,1 Dichloroethane	78		55	120*	67*	81*	110*	14	39*	33
1,1,1-Trichloroethane										8
Trichloroethene							5000			
Vinyl chloride	64		120		280	350		22	140	18
Carbon disulfide				110*						
Pesticides/PCB's	ND	ND		ND	ND	ND	ND	ND	ND	ND
4,4 - DDT			.56							

ND - None Detected

\*Denotes a value below the limit of quantification that is considered approximate





underground storage tank in the brick yard may be alternate contaminant sources to the Saad site. However, these constituents were identified in on site soils analysis.

All samples have concentrations of 1,1-Dichloroethane, and trans-1,2-Dichloroethane, two common solvents. Borings B-17 and 19 are upgradient of the site, indicating possible additional sources of groundwater contamination. Toluene is found in all borings except upgradient boreholes 17 and 19, and borehole 21. Concentrations attenuate to the southeast with increased distance from the site. Toluene concentrations in boreholes 6 and 7 are lower than borehole 5, indicating a potential secondary migration path to the northeast. The toluene concentrations correlate with a buried "shot rock" site drain identified by local workers.

The potentiometric groundwater surface and water chemistry analysis indicate southeast and possibly northeast contaminant migration. Additional contaminant sources may exist based on results from boreholes 17 and 19, and the ethyl benzene/total xylene concentrations in samples near the Franklin Brick yard.

Hydraulic properties of the unconsolidated water table aquifer were determined by performing a single well pumping test in borehole B-6 (Appendix E). Drawdown was minimal at maximum pump capacity. Recovery occurred before any measurements could be made, limiting calculations to drawdown data. Transmissivity was 28,448 GPD/ft and hydraulic conductivity was  $6.27 \times 10^{-1}$  cm/sec. A potential explanation for these hydraulic conditions is the gravel and boulder zones encountered in the boring program. These hydraulic conditions may be representative of a limited area with highly transmissive conditions. A higher pumping rate for an extended period of time is needed to identify these potential boundary conditions.

### 2.3.2 Off-Site Groundwater

A potential hydraulic connection between Saad Waste Oil and/or the CSX Railyard and the Croft Spring may be possible based on waste oil contaminated soil, site groundwater chemistry, and potentiometric water levels directed to the southeast toward Croft Spring. However, distance and the karstic nature of the bedrock prohibit any positive correlations between site contaminant migration and Croft Spring.

Examination of Croft Spring and monitoring well Volatile organic chemistry analysis (Table 8, Appendices A, C & F) do not reveal a connection between the site and Croft Spring. Base Neutral/Acid Extractable analysis reveal similar results.

The lack of corresponding laboratory results do not prove or disprove a hydraulic connection between the site and Croft Spring. The karstic nature of this bedrock aquifer offers a multitude of possible discharge mechanisms that may not have occurred during sampling periods.

**TABLE 8**  
**OFF-SITE GROUNDWATER**

Parameter	Sample									
	Croft Spring	Croft Spring	Croft Spring	Saad Monitoring Well	Saad Monitoring Well 9/87	Well #1 9/87	Well #2	Well #2 9/87	Well #3	Well #3 9/87
Lab Sample No.	SS-S-7-W	SS-CF-SP	7333	SS-SS-MW7	3334	7331	SS-CF-MG2	7332	SS-CF-MW3	7353
Sampling Program			3/87		3/87	3/87		3/87		3/87
1,1 Dichloroethane	2J	ND	ND	1,100	1,700		ND	ND	ND	ND
Chloroform	0.5J			11						
Chlorobenzene	2J									
Vinyl Chloride				6,600	9,800					
Methylene Chloride				19,000	5,500					
1,1 Dichloroethene				690						
Chloroethane				240						
Trans-1,2-Dichloroethane				95,000	52,000					
1,2 Dichloroethane				31						
1,1,1-Trichloroethane				15,000	6,300					
Trichloroethene				69,000	30,000	<5				
Benzene				67						
Tetrachloroethene				49,000	9,600					
Toluene				3,900	4,600					
Chlorobenzene				87						
Ethyl benzene				310	500					

ND - No VOA's detected in analysis

J - Estimated Value



### 3.0 CONCLUSIONS

#### 3.1 Tank Investigation Program

The tank investigation identified 16,876 gallons of mixed; oil, oil/water emulsion, and water phase fluids stored at the site. Batching recommendations provide a simple removal scheme. Batching may be simplified if an onsite oil/water separator is used. Removal of sludges remaining after pumping is possible by pressure cleaning and/or scraping (shoveling the sludge).

#### 3.2 Soil Boring and Sampling Program

The soil boring and sampling program identified oil contaminated soil in a much broader area than the reclaimed waste oil lagoon. The entire site is underlain by oil contaminated soil with southeast oil migration to the Franklin Brick Company property. The majority of the estimated 9,378 yd<sup>3</sup> of oil contaminated soil is on Saad Waste Oil property.

Volume and extent of contamination make soil removal difficult. Extensive overburden off site and a groundwater table above the bottom of waste throughout make removal unrealistic.

There are two remedial methods (or combinations) that prohibit further waste oil migrations. The first alternative could be capping the site with an impermeable material to prevent infiltration (asphalt). The water table in contaminated soils necessitates a slurry wall or cutoff trench to inhibit off-site contaminant migration from groundwater flow through the site. Spatial limitations virtually eliminate slurry wall or cutoff trench construction. A second alternative could be in-situ stabilization of oil contaminated soil using pressure grouting techniques.

### 3.3 On Site Groundwater

- The groundwater potentiometric surface and laboratory analysis indicate flow primarily to the southeast and possibly to the northwest. High transmissivity of the oil contaminated zones (gravel layers) could provide a rapid contaminant transport system if not for the low groundwater gradient and inconsistency of materials encountered.

Remedial alternatives discussed in the Soil Boring section could effectively inhibit leaching and migration of contaminants by groundwater. When choosing a remedial alternative, downward vertical contaminant migration on and off site should be considered.

### 3.4 Off-Site Groundwater

The soil boring and on-site groundwater monitoring program identify contaminant migration to the southeast, the direction of Croft Spring. However, offsite groundwater samples including Croft Spring do not identify contaminant transport. This does not eliminate site contamination of Croft Spring, but requires further investigation into contaminant pathways. Injection of tracers to determine flow paths is premature until there is a better understanding of contaminant transport.

APPENDIX A

ANALYTICAL RESULTS, TANK SAMPLINGS,  
SITE SOIL, AND SITE GROUNDWATER

ENVIRESPONSE, INC.  
GSA RARITAN DEPOT, BLDG. 209, BAY F  
EDISON, NJ 08837  
201-548-9660

SAAD WASTE OIL SITE  
Nashville, TN  
Project No. 37069190499  
July 29, 1987

Submitted to: G. Prince-USEPA-ERT

Submitted by:  
Enviresponse, Inc.

M.D. Garber 7/28/87  
M.D. Garber  
EI-EERU Project Manager

Analysis by:  
Versar Laboratory

J.B. Bortis 7/28/87  
J.B. Bortis  
EI-EERU S&A Section Chief

Reviewed by:  
J. Cullinane

J. Giga 7/28/87  
J. Giga, Ph.D.  
EI-EERU QA/QC Officer

## TABLE OF CONTENTS

## SECTION I

Introduction

Analytical Procedures

Sample Results:

Volatile Organics in Water.....	Table 1
Pesticides/PCBs in Water.....	Table 2
Volatile Organics in Soil.....	Table 3
Pesticides/PCBs in Soil.....	Table 4
Volatile Organics in Oil.....	Table 5
Pesticides/PCBs in Oil.....	Table 6
Base Neutral/Acids in Oil.....	Table 7
Metals in Oil.....	Table 8
Incineration Parameters for Oil.....	Table 9

## SECTION II

QA/QC Procedures

QA/QC Results:

Surrogate Standard Recoveries for Volatile Organics in Water, Soil and Oil.....	Table 10
Matrix Spike Duplicate Recoveries for Volatile Organics in Water.....	Table 11
Matrix Spike Duplicate Recoveries for Volatile Organics in Soil .....	Table 12
Matrix Spike Duplicate Recoveries for Volatile Organics in Oil .....	Table 13
Surrogate Standard Recoveries for Pesticides/PCBs in Water, Soil, and Oil.....	Table 14
Matrix Spike Duplicate Recoveries for Pesticides in Water .....	Table 15
Matrix Spike Duplicate Recoveries for Pesticides in Soil .....	Table 16
Matrix Spike Duplicate Recoveries for Pesticides in Oil .....	Table 17
Surrogate Standard Recoveries for Base Neutral Extractables in Oil.....	Table 18A
Surrogate Standard Recoveries for Acid Extractables in Oil.....	Table 18B
Matrix Spike Duplicate Recoveries for Base Neutral/Acid Extractables in Oil.....	Table 19
Duplicate Metals in Oil Analyses.....	Table 20
Matrix Spike Duplicate Recoveries for Metals.....	Table 21
Duplicate Incineration Parameters Analyses.....	Table 22

## SECTION III

GC/MS Data for Volatile Organics in Water

## SECTION IV

GC/MS Data for Volatile Organics in Soil

## SECTION V

GC/MS Data for Volatile Organics in Oil

## SECTION VI

GC Data for Pesticides/PCBs in Water

## SECTION VII

GC Data for Pesticides/PCBs in Soil

## SECTION VIII

GC Data for Pesticides/PCBs in Oil

## SECTION IX

GC/MS Data for Base Neutral/Acid Extractables in Oil

## SECTION X

Data for Metals in Oil

## SECTION XI

Data for Incineration Parameters

## SECTION XII

Interlaboratory Correspondence

## SECTION XIII

Chain of Custody Records

## INTRODUCTION

On March 20, 1987, five oil samples were sent to Versar Laboratory in Virginia from the Saad Waste Oil Site in Nashville, Tennessee. Priority pollutant volatile organics, PCBs, pesticides, base-neutral/acid extractables, and metals plus, incineration parameters (TOX, BTU, ash, and ignitability) analyses were performed. On March 23, seven water samples and ten soil samples were submitted to Versar for priority pollutant volatile organics and pesticides/PCBs analyses. Sample No. E-16, R-2 BOB is erroneously listed on the chain of custody records as a water sample; it is in fact a soil sample.

## ANALYTICAL PROCEDURES

### WATER

**Volatile Organics:** The volatile organics analyses were conducted according to Contract Laboratory Program (CLP) protocols. Most samples required dilution due to high concentrations of the parameters of interest. The method blanks for these analyses contained methylene chloride and acetone. The background for these compounds was subtracted from samples showing a positive response. Results are presented in Table 1. CLP criteria for calibration linearity were met for all compounds. Instrument detection limits were also acceptable. Detection limits varied for these samples due to the dilutions. Detection limits for each sample can be located in Section III. They are provided in the form of CLP sample reporting data sheets. Also included in this section are the listings of tentatively identified compounds. These compounds do not meet CLP criteria for identification and should be used with discretion.

**Pesticides/PCBs:** The pesticides/PCB analyses were conducted according to EPA Method 608 of the Federal Register. Results are presented in Table 2. All samples were analyzed as low level and met all detection limit criteria established by CLP. PCBs were undetected in all samples. 4,4'-DDT was found in sample 5707 but the chromatography was poor on both columns and Versar strongly suggests that this may be a false positive. In addition, since the linearity of DDT exceeded CLP limits, this result is somewhat questionable. No results are reported for sample 5708. The original analysis of the water samples indicated "overactivated" sorbent was used to clean the sample extracts and the extraction and analysis of the samples were repeated. Sample 5708 was expended during the initial analysis. The holding times for the extraction of the samples was exceeded.

### SOILS

**Volatile Organics:** These analyses were conducted according to CLP

protocols. The soils contained various levels of volatile compounds and detection limits varied accordingly. The detection limits for each sample are provided in Section IV in the form of CLP data sheets. Also included in this section are listings of tentatively identified compounds. These compounds do not meet CLP criteria for identification and should be used with discretion. All compounds met CLP standards for calibration linearity and detection limits. The results are presented in Table 3.

**Pesticides/PBCs:** Samples were prepared and analyzed according to EPA Method 8080. Pesticides and PCBs were undetected in these samples. Results are presented in Table 4.

## OILS

**Volatile Organics:** Samples were prepared by diluting one gram of oil in one milliliter of methanol. Sample extracts were analyzed by direct injection of a 1 ul aliquot onto the column to the GC/MS. The methanol blank contained acetone and 2-butanone. This background was subtracted from any sample hits for these compounds. Calibration range linearity was within CLP limits for all compounds except acetone and 2-butanone, probably due to the presence of these compounds in the methanol. In addition, the concentration of acetone and 2-butanone in Sample 1258 exceeded the linear calibration range and should be considered approximate. Redilution of this sample was not possible since only a small oil layer was present in the sample container and it was expended during the initial dilution. Results are presented in Table 5. Section V contains a listing of tentatively identified compounds. These compounds do not meet CLP criteria for identification and should be used with discretion.

**Pesticides/PCBs:** The samples were prepared and analyzed according to EPA Method 8080. Pesticides and PCBs were undetected in these samples as shown in Table 6. Linearity criteria as established by CLP were not met for alpha-BHC, delta-BHC, gamma-BHC, aldrin, 4,4'-DDT and methoxychlor. All other parameters were within the CLP limits. Detection limits were also met. Results are presented in Table 6.

**Base Neutral/Acid Extractables:** The samples were prepared according to EPA Method 8270. Sample analyses were conducted according to CLP protocol. All detection limit and linearity criteria were met with the exception of benzoic acid. Linearity for this compound exceeded the 35% relative standard deviation limit. Results are presented in Table 7. Section IX contains a list of tentatively identified compounds. These compounds did not meet CLP criteria for identification and should be considered as marginally accurate. Sample 1261 was analyzed in triplicate. Phenanthrene was detected in one of the three analyses. Bis(2-ethylhexyl)phthalate was detected in two of the three analyses. The analysis of one 1261 sample did not confirm the presence of either compound but GC/MS data for tentatively confirmed compounds indicate that they may be present. The analysis of these samples was complicated due to high



concentrations of numerous hydrocarbons which created background interferences.

Metals: Samples were analyzed according to EPA Methods 6010, 7060, 7470, and 7740 for priority pollutant metals. All calibration and linearity criteria were met. Results are presented in Table 8.

The results of the incineration parameter testing are presented in Table 9.

Table 1. Volatile Organics in Water  
Concentrations reported in ug/L

Sample No.	Parameter	Concentration
5705 (Diluted 100x)	Methylene chloride	200.*
	Carbon disulfide	110.*
	1,1-Dichloroethane	120.*
	trans-1,2-Dichloroethene	1200.
	Toluene	7500.
	Ethyl benzene	250.*
	Total xylenes	1100.*
5706 (Diluted 20x)	Vinyl chloride	280.
	1,1-Dichloroethane	67.*
	trans-1,2-Dichloroethene	1900.
	Toluene	360.
	Total xylenes	150.*
5707 (Diluted 10x)	Vinyl chloride	120.
	1,1-Dichloroethane	55.
	trans-1,2-Dichloroethene	420.
	Toluene	1100.
	Ethyl benzene	180.
	Total xylenes	1500.
5708 (Diluted 2x)	Vinyl chloride	22.
	1,1-Dichloroethane	14.
	trans-1,2-Dichloroethene	270.
5709 (Diluted 50x)	Benzene	55.*
	Toluene	4000.
	Ethyl benzene	120.*
	Total xylenes	880.
5710 (Diluted 5x)	Vinyl chloride	64.
	1,1-Dichloroethane	78.
	trans-1,2-Dichloroethene	63.
	Benzene	7.*
	Toluene	88.
	Ethyl benzene	220.
	Total xylenes	1900.

\*denotes a value below the limit of quantification that is considered approximate.

Table 1. Volatile Organics in Water (Cont'd)

Concentrations reported in ug/L

Sample No.	Parameter	Concentration
5711 (Diluted 10x)	Vinyl chloride	140.
	1,1-Dichloroethane	39.*
	trans-1,2-Dichloroethene	560.
5712	Methylene chloride	1.*
	Chloroform	2.*
	1,1,1-Trichloroethane	2.*
	Trichloroethene	2.*
5713	Vinyl chloride	18.
	Chloroethane	13.
	Methylene chloride	1.*
	Acetone	68.
	1,1-Dichloroethane	33.
	trans-1,2-Dichloroethene	14.
	2-Butanone	9.*
	1,1,1-Trichloroethane	8.
	Total xylenes	9.
5714 (Diluted 50x)	Methylene chloride	2500.
	1,1-Dichloroethane	110.*
	trans-1,2-Dichloroethene	4100.
	Trichloroethene	5000.
	4-Methyl-2-pentanone	210.*
	Toluene	4100.
	Ethyl benzene	110.*
	Total xylenes	310.
5715 (Diluted 25x)	Vinyl chloride	350.
	Methylene chloride	53.*
	1,1-Dichloroethane	81.*
	trans-1,2-Dichloroethene	1800.
	Toluene	210.

\*denotes a value below the limit of quantification that is considered approximate.

Table 2. Results of Pesticides/PCBs in Water

Concentrations reported in ug/L

Sample No.	Parameter	Concentration
Method Blank	None detected	--
5705	None detected	--
5706	None detected	--
5707	4,4'-DDT	.56
5708	None detected	--
5709	None detected	--
5710	None detected	--
5711	None detected	--
5712	None detected	--
5713	None detected	--
5714	None detected	--
5715	None detected	--

Table 3. Volatile Organics in Soil

Concentrations reported in ug/kg

Sample No.	Parameter	Concentration
B-8 R1 10-13 (Diluted 2x)	Methylene chloride	16.
	trans-1,2-Dichloroethene	8.*
	2-Hexanone	23.*
	Toluene	54.
	Total xylenes	120.
B-20 3-4.1 (Diluted 100x)	Acetone	810.*
	Toluene	3900.
	Ethyl Benzene	610.*
	Total Xylenes	3700.
B-16 R1-14 (Diluted 2x)	Acetone	340.
	2-Butanone	71.
	4-Methyl-2-pentanone	38.
	Toluene	100.
	Ethyl benzene	7.*
	Total xylenes	23.
B-16 R2 B08	Acetone	800.
	2-Butanone	96.
	4-Methyl-2-pentanone	49.
	Toluene	3.*
B-2 S-5	Acetone	22.
	trans-1,2-Dichloroethene	2.*
	Benzene	5.*
	4-Methyl-2-pentanone	33.
	Ethyl benzene	95.
	Total Xylenes	330.
B-4 4'-5' (Diluted 2x)	Ethyl benzene	110.
	Total xylenes	590.
B-16 R1 2.5 (Diluted 250x)	Acetone	1100.*
	Toluene	53000.
	Ethyl benzene	4600.

\*denotes a value below the limit of quantification that is considered approximate.

Table 3. Volatile Organics in Soil (Cont'd)

Concentrations reported in ug/kg

Sample No.	Parameter	Concentration
B-35 S-2 6.5-8.5 (Diluted 10x)	1,1-Dichloroethane	19.*
B-24 R1 6.5-8.5 (Diluted 10x)	Methylene chloride	38.*
	2-Hexanone	270.
	Ethyl benzene	380.
B-13 4.5-6 (Diluted 100x)	Methylene chloride	950.
	Acetone	1200.*
	1,1-Dichloroethane	18000.
	trans-1,2-Dichloroethene	13000.
	1,1,1-Trichloroethane	28000.
	Trichloroethene	930.
	4-Methyl-2-pentanone	530.*
	Tetrachloroethene	3200.
	Toluene	29000.
	Ethyl benzene	2200.*
	Total xylenes	9800.

\*denotes a value below the limit of quantification that is considered approximate.

Table 4. Pesticides/PCBs in Soil  
Concentrations reported in ug/g

Sample No.	Parameter	Concentration
B-2 S-5	None detected	--
B-4 4-5	None detected	--
B-8 R-1 10-13	None detected	--
B-13 4.5-6	None detected	--
B-16 R-1 2.5	None detected	--
B-16 R-2 B08	None detected	--
B-16 R-1 14	None detected	--
B-20 3-4.1	None detected	--
B-24 R-1 6.5-8.5	None detected	--
B-35 S-2 6.5-8.5	None detected	--

Table 5. Volatile Organics in Oil  
Concentrations reported in ug/g

Sample No.	Parameter	Concentration
Method Blank	Acetone	32.
	2-Butanone	31.
5719	Methylene chloride	13.
	1,1-Dichloroethane	3.*
	1,1,1-Trichloroethane	22.
	Trichloroethene	20.
	Tetrachloroethene	2.*
	Toluene	33.
	Ethyl benzene	5.*
	Total xylenes	9.
5720	Methylene chloride	19.
	1,1-Dichloroethane	4.*
	2-Butanone	12.
	1,1,1-Trichloroethane	24.
	Trichloroethene	32.
	Toluene	32.
	Ethyl benzene	5.*
	Total xylenes	9.
1258	Methylene chloride	6.
	Acetone	1200.
	2-Butanone	2900.
	Trichloroethene	43.
	4-Methyl-2-pentanone	68.
	Toluene	8.
1260	Methylene chloride	220.
	1,1,1,-Trichloroethane	9.
	Trichloroethene	98.
	4-Methyl-2-pentanone	15.
	Toluene	170.
	Total xylenes	11.
1261	None detected	--

\*denotes a value below the limit of quantification that is considered approximate.



Table 6. Results of Pesticides/PCBs in Oil

Concentrations in ug/g

Sample No.	Parameter	Concentration
1258	None detected	--
1258 (Duplicate)	None detected	--
1260	None detected	--
1261	None detected	--
5719	None detected	--
5720	None detected	--

Table 7. Results of Base Neutral/Acid Extractables in Oils

Concentrations reported in ug/g

Sample No.	Parameter	Concentration
Method Blank	None detected	--
1258	None detected	--
1260	bis(2-Ethylhexyl)phthalate	474.
1261	bis(2-Ethylhexyl)phthalate	1.1
1261 (Duplicate 1)	None detected	--
1261 (Duplicate 2)	Phenanthrene	0.11*
	bis(2-Ethylhexyl)phthalate	3.9
5719	Naphthalene	44.
	2-Methylnaphthalene	110
	Phenanthrene	21.
	Fluorene	15.
5720	None detected	--

\* denotes a response that is below the limit of quantification and considered approximate.

Table 8. Results of Metals in Oil Analysis

Concentrations reported in ug/g

Parameter		Concentration				
	Detection Limit	5719	5720	1258	1260	1261
Antimony	2.0	ND	ND	ND	ND	ND
Arsenic	1.0	ND	ND	ND	4.9	ND
Beryllium	0.1	ND	ND	ND	ND	ND
Cadmium	0.5	0.84	0.81	0.82	0.64	0.66
Chromium	0.4	7.58	7.86	20.6	76.6	14.1
Copper	0.5	28.4	27.3	33.5	3.3	13.7
Lead	3.5	574.	728.	549.	25.8	136.
Mercury	0.1	0.28	ND	ND	ND	ND
Nickel	0.75	3.3	2.6	1.4	4.3	2.9
Selenium	0.5	ND	ND	ND	ND	ND
Silver	0.25	ND	ND	ND	ND	ND
Thallium	*	ND	ND	ND	ND	ND
Zinc	0.15	304.	315.	218.	63.6	147.

ND denotes not detected.

\*Detection limits for thallium varied due to background corrections for matrix effects.

Table 9. Incineration Testing for Oil

Sample No.	Flashpoint oF	% Ash	BTU/ pound	Total organic Halogens*
5719	<70	0.31	9350.	0.20
5720	<70	0.23	8500.	0.26
1258	<72	0.25	0	0.09
1260	<70	0.81	15300.	0.55
1261	<72	0.03	500.	0.09

\*TOX values reported as % chlorine.

## QA/QC PROCEDURES

**Volatile Organics:** All water, soil and oil samples were spiked with three surrogate standards. In the case of water and soil samples, these surrogate standards were used to assure the efficiency of the purge and trap unit. For the oil samples, the surrogates were used to establish the extraction efficiency. The surrogate standard recoveries are presented in QA/QC Table 10. All recoveries were within CLP advisory limits.

Two water samples were spiked in duplicate with a five component volatile organics mixture to determine the presence of any matrix interferences. All compounds were within the advisory limits established by CLP. Results are presented in QA/QC Table 11.

One soil sample and one oil sample were spiked with a five component volatile organics mixture. All recoveries were within CLP advisory limits. Results are presented in QA/QC Table 12 for the soil sample and QA/QC Table 13 for the oil.

**Pesticides/PCBs:** All water, soil and oil samples were spiked with a surrogate standard, dibutylchlorodate, to assure extraction efficiency. These results are presented in QA/QC Table 14. One water sample, 5706, showed a low recovery of 23%. The laboratory provided no possible cause. The soil samples showed recoveries in excess of 150% for 9 out of 12 analyses. The analysis of the soil samples for volatile organics by GC/MS indicated elevated concentrations of hydrocarbons which are the most likely reason for the high surrogate recoveries for the pesticides. The oil samples also showed high recoveries for samples 1260, 1261, 5719, and 5720.

Two water samples, 5712 and 5709, were spiked in duplicate with a three component mixture of pesticides. Five of six recoveries for these compounds in sample 5712 exceeded the CLP advisory limits. Six of six recoveries for sample 5709 exceeded 200%. The laboratory suggested that this sample may have been "double spiked". These results are presented in QA/QC Table 15.

One soil sample, B-16 R-2 BOB, was spiked with a six component pesticide mixture. All recoveries were within the CLP advisory limits except 4,4'-DDT which had a 155% recovery. The linearity of the 4,4'-DDT was unacceptable throughout these analyses. The results are presented in QA/QC Table 16.

One oil sample, 1258, was spiked with a six component pesticide mixture. Again, all recoveries, except 4,4'-DDT, were within CLP advisory limits. The results are reported in QA/QC Table 17.

No PCB matrix spikes were performed.

**Base Neutral/Acid Extractables:** The oil samples were spiked with three base neutral surrogate standards and three acid surrogate standards. The recoveries were within CLP advisory limits for all surrogates in all samples except sample 5719. Sample 5719 showed elevated recoveries for all but one surrogate. These results are presented in QA/QC Tables 18A and 18B.

**Metals:** One oil sample, 1261, was analyzed in duplicate to determine matrix homogeneity. The relative percent differences for all detected metals were less than 10 as presented in QA/QC Table 20.

Sample 5720 was spiked with 1.0 ug/g mercury to determine any matrix effects. The recovery was 50% possibly due to complexing of the mercury with chlorides during sample digestion. The volatile organics analysis for this oil sample confirmed the presence of organochlorine compounds (See Table 5 of Section I, Results). Sample 5719 was spiked with arsenic and selenium and showed recoveries of 104% and 114%, respectively. Sample 1260 was spiked with a mixture of the ten remaining priority pollutant metals. All recoveries were within a range of 60%-125% except silver which had a recovery of 53%. This sample contained high concentrations of organochlorine compounds, possibly resulting in complexing of the silver and chlorine during digestion with subsequent precipitation. The results of these matrix spikes are presented in QA/QC Table 21.

QA/QC Table 22 presents the results of duplicate incineration parameters analyses. The relative percent differences did not exceed 15. The flashpoint testing was not performed in duplicate.

QA/QC Table 10. Surrogate Standard Recoveries for Volatile Organics in Water, Soil, and Oil

Sample No.	% Recovery Toluene-DB	% Recovery Bromofluorobenzene	% Recovery 1,2-Dichloroethane-D4
Water:			
5705	101	104	92
5706	101	101	96
5707	98	98	93
5708	98	102	87
5708 (MS)	96	99	89
5708 (MSD)	93	100	91
5709	98	99	88
5710	98	100	90
5711	98	103	92
5712	101	107	92
5713	102	108	92
5713 (MS)	98	101	94
5713 (MSD)	97	99	96
5714	99	98	88
5715	97	98	91
Soil:			
B-2 S-5	100	89	96
B-4 4-5	108	100	108
B-8 R-1 10-13	99	107	95
B-13 4.5-6	102	102	122
B-16 R-1 2.5	104	98	89
B-16 R-2 BOB (Dil 5X)	101	97	94
B-16 R-2 BOB	103	100	101
B-16 R-1 14	103	102	111
B-20 3-4.1	105	103	119
B-24 R-1	101	134	115
B-35 S-2	102	109	92
B-2 S-5 (MS)	96	93	80
B-2 S-5 (MSD)	99	94	81
Oil:			
1258	95	107	105
1260	95	106	106
1261	92	105	109
5719	101	100	109
5719 (MS)	98	103	108
5719 (MSD)	98	106	106
5720	95	106	106

QA/QC Table 11. Matrix Spike/Matrix Spike Duplicate Recoveries for Volatile Organics in Water

Concentrations reported in ug/L

All parameters spiked at 50 ug/L

Parameter	Sample	Recovered		% Recovery		RPD
		MS	MSD	MS	MSD	
-----						
Sample No. 5708						
1,1-Dichloroethene	ND	33	32	66	64	3.1
Trichloroethene	ND	47	44	94	88	6.6
Chlorobenzene	ND	44	43	88	86	2.3
Toluene	ND	44	42	88	84	4.6
Benzene	ND	43	39	86	78	9.8

## Sample No. 5713

1,1-Dichloroethene	ND	49	49	98	98	0
Trichloroethene	ND	50	50	100	100	0
Chlorobenzene	ND	49	48	98	96	2.0
Toluene	ND	50	50	100	100	0
Benzene	ND	48	48	96	96	0

MS denotes matrix spike. MSD denotes matrix spike duplicate.

RPD denotes relative percent difference.

ND denotes not detected.



QA/QC Table 12. Matrix Spike/Matrix Spike Duplicate Recoveries for  
Volatile Organics in Soils

Concentrations reported in ug/kg

All parameters spiked at 50 ug/kg

Parameter	Sample Conc.	Recovered Conc.		% Recovery		RPD
		MS	MSD	MS	MSD	
Sample B-2 S-5						
1,1-Dichloroethene	ND	65.	67.	130	134	3.0
Trichloroethene	ND	53.	55.	106	110.	3.7
Chlorobenzene	ND	45.	52.	90.	104	14.
Toluene	ND	45.	49.	90.	98.	8.5
Benzene	5.*	44.	48.	78.	86.	11.

MS denotes matrix spike. MSD denotes matrix spike duplicate.

RPD denotes relative percent difference.

ND denotes not detected.

\* denotes a value that is below the limit of quantification and  
considered approximate.

QA/QC Table 13. Matrix Spike/Matrix Spike Duplicate Recoveries for Volatile Organics in Oil

Concentrations reported in ug/g

All parameters spiked at 100 ug/g

Parameter	Sample Conc.	Recovered Conc.		% Recovery		RPD
		MS	MSD	MS	MSD	
Sample No. 5719						
1,1-Dichloroethene	ND	112	116	112	116	3.5
Trichloroethene	20.	118	129	98	109	11.
Chlorobenzene	ND	98	98	98	98	0
Toluene	33.	125	133	92	100	8.3
Benzene	ND	97.	100.	97.	100	3.0

MS denotes matrix spike, MSD denotes matrix spike duplicate.

RPD denotes relative percent difference.

ND denotes not detected.

QA/QC Table 14. Surrogate Standard Recoveries for Pesticides/PCBs in Water, Soil and Oil

Sample No.	Matrix	% Recovery Dibutylchloroendate
5705	Water	31.
5706	Water	23.
5707	Water	120
5709	Water	70
5709 MS	Water	120
5709 MSD	Water	129
5710	Water	46
5711	Water	20
5712	Water	100
5712 MS	Water	100
5712 MSD	Water	100
5713	Water	30
5714	Water	70
5715	Water	50
B-2 S-5	Soil	190
B-4 4-5	Soil	560
B-8 R-1 10-13	Soil	320
R-13 4.5-6	Soil	300
B-16 R-1 2.5	Soil	110
B-16 R-2 BOB	Soil	110
B-16 R-1 14	Soil	170
B-20 3-4.1	Soil	350
B-24 R-1 6.5-8.5	Soil	930
B-35 S-2 6.5-8.5	Soil	1380
B-16 R-2 BOB (MS)	Soil	130
B-16 R-2 BOB (DUP)	Soil	230
1258	Oil	100
1258 Duplicate	Oil	110
1258 MS	Oil	100
1260	Oil	320
1261	Oil	550
5719	Oil	270
5720	Oil	1330

MS denotes matrix spike, MSD denotes matrix spike duplicate.  
DUP denotes duplicate.

QA/QC Table 15. Matrix Spike/Matrix Spike Duplicate Recoveries for Pesticides in Water

Concentrations reported in ug

All parameters spiked with .5 ug

Parameter	Sample Conc.	Recovered Conc.		% Recovery		RPD
		MS	MSD	MS	MSD	
Sample No. 5712						
Dieldrin	ND	.62	.63	124	126	3.2
Endrin	ND	.74	.78	148	156	5.3
4,4'-DDT	ND	.93	.79	186	158	16.3
Sample No. 5709						
Dieldrin	ND	1.1	1.2	220	240	9.0
Endrin	ND	1.3	1.4	260	280	7.0
4,4'-DDT	ND	1.2	1.2	240	240	0

MS denotes matrix spike, MSD denotes matrix spike duplicate.  
RPD denotes relative percent difference.  
ND denotes not detected.

QA/QC Table 16. Matrix Spike Recoveries for Pesticides in Soil  
Concentrations reported in ug

Parameter	Sample Conc.	Spike Conc.	Recovered Conc.	% Recovery
Sample No. B-16 R-2 BOB				
gamma-BHC	ND	0.80	0.78	98.
Heptachlor	ND	0.80	0.78	98.
Aldrin	ND	0.80	0.78	98.
Dieldrin	ND	2.0	2.0	100.
Endrin	ND	2.0	2.2	110.
4,4'-DDT	ND	2.0	3.1	155.

ND denotes not detected.

## QA/QC Table 17. Matrix Spike Recoveries for Pesticides in Oil

Concentrations reported in total ug

Parameter	Sample Conc.	Spike Conc.	Recovered Conc.	% Recovery
-----------	-----------------	----------------	--------------------	------------

Sample No. 1258

Lindane	ND	2.0	2.2	110
Heptachlor	ND	2.0	1.9	95
Aldrin	ND	2.0	2.3	115
Dieldrin	ND	5.0	6.1	122
Endrin	ND	5.0	6.2	124
4,4'-DDT	ND	5.0	7.6	154

ND denotes not detected.

QA/QC Table 18A. Surrogate Standard Recoveries for Base Neutral Extractables

Sample No.	% Recovery Nitrobenzene-D4	% Recovery 2-Fluorobiphenyl	% Recovery p-Terphenyl-D14
1258	88.	60	78
1260	83	59	68
1261	89	69	65
1261 Dup	95	90	64
1261 MS	92	84	56
5719	316	180	220
5720	94	63	82

MS denotes matrix spike.

QA/QC Table 18B. Surrogate Standard Recoveries for Acid Extractables

Sample No.	% Recovery 2-Fluorophenol	% Recovery Phenol-D5	% Recovery 2,4,6-Tribromophenol
1258	79.	80.	86
1260	79.	79.	81
1261	87.	85.	96
1261 Dup	80.	78	95
1261 MS	90.	81.	102.
5719	148.	208.	122.
5720	89.	89.	84.

MS denotes matrix spike.

QA/QC Table 19. Matrix Spike Recoveries for Base Neutral/Acid  
Extractables in Oil

Concentrations reported in ug/ml

Parameter	Sample Conc.	Spike Conc.	Recovered Conc.	%Recovery
Sample 1261				
1,2,4-Trichlorobenzene	ND	100.	80.	80.
Acenaphthene	ND	100.	77.	77.
2,4-Dinitrotoluene	ND	100.	97.	97.
Pyrene	ND	100.	55.	55.
N-nitrosodi-n-propylamine	ND	100.	68.	68.
1,4-Dichlorobenzene	ND	100.	61.	61.
Pentachlorophenol	ND	200.	192	96.
Phenol	ND	200.	131	66.
2-Chlorophenol	ND	200.	132	66.
4-Chloro-3-methylphenol	ND	200.	161	80.
4-Nitrophenol	ND	200.	162	81.

ND denotes not detected.



## QA/QC Table 20. Duplicate Metals in Oil Analyses

Concentrations reported in ug/g

Parameter	Run 1	Run 2	RPD
Sample No. 1261			
Antimony	ND	ND	--
Beryllium	ND	ND	--
Cadmium	0.66	0.66	0
Chromium	14.1	15.	6.2
Copper	13.7	14.	2.2
Lead	136.	134.	1.5
Nickel	2.9	2.7	7.1
Silver	ND	ND	--
Thallium	ND	ND	--
Zinc	147.	146.	0.7

RPD denotes relative percent difference.

ND denotes not detected.

QA/QC Table 21. Matrix Spike Recoveries for Metals in Oil

Concentrations in ug/g

Parameter	Sample Conc.	Spike Conc.	Recovered Conc.	% Recovery
Sample No. 1260				
Antimony	ND	100.	67.8	67.8
Beryllium	ND	50.	46.7	93.4
Cadmium	0.64	50.	37.5	73.7
Chromium	76.6	50.	139	125
Copper	3.3	100.	91.1	87.8
Lead	25.8	100.	89.4	63.6
Nickel	4.3	100.	84.7	80.4
Silver	ND	50.	26.6	53.2
Thallium	ND	100.	73.4	73.4
Zinc	63.6	100.	158.	94.4
Sample No. 5719				
Arsenic	ND	2.5	2.6	104
Selenium	ND	5.0	5.7	114
Sample No. 5720				
Mercury	ND	1.0	.3	50.
ND denotes not detected.				

QA/QC Table 22. Duplicate Analyses for Incineration Parameters

Parameter	Sample No.	Run 1	Run 2	Difference	RPD
% Ash	1258	0.27	0.24	0.03	12.
TOX (% as Cl)	1260	0.55	0.57	0.02	3.6
BTU/pound	1260	15,300	15,300	0.0	0.0

RPD denotes relative percent difference.

## ENVIRESPONSE, INC.

## CHAIN OF CUSTODY RECORD

PROJECT NAME Saad Oil Site  
 PROJECT NO. 370 69 190499

SAMPLER(S) SIGNATURE

*Catherine Burchette*  
*Steve K. Jones*

SAMPLE IDENTIFICATION	SAMPLING LOCATION	DATE SAMPLED	SAMPLE TYPE				COMP	GRAB	VOLUME TO BE COLLECTED	NO OF CONTAINERS	TIME COLLECTION BEGAN	INITIAL	TIME COLLECTION COMPLETED	INITIAL	COMMENTS
			WATER	SOLID	AIR	OIL									
B24	6.5'-8.5'	3/20/87		✓				✓	1x80c	1	-		-		VOA, PESTICIDES/PCB, PD ANALYZE CONTAMINATED PORTION
B13	4.5'-6'	3/20/87		✓				✓	1x80c	1	-		-		↓
B35	6.5'-8.5'	3/20/87		✓				✓	1x80c	1	-		-		
05705	B6	3/23/87	✓					✓	2x1L	2	-		-		VOA
05705	B6	3/23/87	✓					✓	3x40mL	3	-		-		PP, PESTICIDE/PCB
05706	B8	3/23/87	✓					✓	2x1L	2	-		-		VOA
05706	B8	3/23/87	✓					✓	3x40mL	3	-		-		PP, PESTICIDE/PCB
05707	B4	3/23/87	✓					✓	2x1L	2	-		-		VOA
05707	B4	3/23/87	✓					✓	3x40mL	3	-		-		PP, PESTICIDE/PCB
05708	B23	3/23/87	✓					✓	2x1L	2	-		-		VOA
05708	B23	3/23/87	✓					✓	3x40mL	3	-		-		PP, PESTICIDE/PCB

RELINQUISHED BY NAME *Catherine Burchette* DATE/TIME 3/23/87 1445

RELINQUISHED BY NAME \_\_\_\_\_ DATE/TIME \_\_\_\_\_

RELINQUISHED BY NAME \_\_\_\_\_ DATE/TIME \_\_\_\_\_

AUTHORIZATION FOR DISPOSAL \_\_\_\_\_ DATE/TIME \_\_\_\_\_

RECEIVED BY NAME *D. J. F.* DATE/TIME 3/24/87 0806

RECEIVED BY NAME \_\_\_\_\_ DATE/TIME \_\_\_\_\_

RECEIVED BY NAME \_\_\_\_\_ DATE/TIME \_\_\_\_\_

DISPOSED BY: \_\_\_\_\_ DATE/TIME \_\_\_\_\_

### CHAIN OF CUSTODY RECORD

**SAMPLER(S) SIGNATURE**

PROJECT NO. 370 69190499

[illegible]

RELINQUISHED BY: NAME J. Burchette DATE/TIME 3/29/87 1400  
RELINQUISHED BY: NAME \_\_\_\_\_ DATE/TIME \_\_\_\_\_  
RELINQUISHED BY: NAME \_\_\_\_\_ DATE/TIME \_\_\_\_\_  
AUTHORIZATION FOR DISPOSAL \_\_\_\_\_ DATE/TIME \_\_\_\_\_

RECEIVED BY NAME D-9/11-1 DATE/TIME 3-21-87/0546  
RECEIVED BY NAME \_\_\_\_\_ DATE/TIME \_\_\_\_\_  
RECEIVED BY NAME \_\_\_\_\_ DATE/TIME \_\_\_\_\_  
DISPOSED BY: \_\_\_\_\_ DATE/TIME \_\_\_\_\_

MRJ 5-13-87

289458

# ENVIRESPONSE, INC.

## CHAIN OF CUSTODY RECORD

PROJECT NAME Seed Oil Site  
PROJECT NO 32069190499

SAMPLER(S) SIGNATURE Cynthia Bourdette  
Seed Oil Site

SAMPLE IDENTIFICATION	SAMPLING LOCATION	DATE SAMPLED	SAMPLE TYPE			COMP	GRAV	VOLUME TO BE COLLECTED	NO OF CONTAINERS	TIME COLLECTION BEGAN	INITIAL	TIME COLLECTION COMPLETED	INITIAL	COMMENTS
			WATER	SOIL	AIR									
05711	B25	3/23/87	✓				✓	2X1L	2	1400	UB	1415	UB	PP, PESTICIDES/PCB
05711	B25	3/23/87	✓				✓	3X40mL	3	1400	UB	1415	UB	VOA
05710	B1	3/23/87	✓				✓	2X1L	2	1350	UB	1400	UB	PP, PEST./PCB.
05710	B1	3/23/87	✓				✓	3X40mL	3	1350	UB	1400	UB	VOA
05709	B2	3/23/87	✓				✓	2X1L	2	1310	UB	1320	UB	PP, PESTICIDE/PCB
05709	B2	3/23/87	✓				✓	3X40mL	3	1310	UB	1320	UB	VOA
B1b	<del>B25</del> 12.5'	3/20/87	✓				✓	1X800L	1	—	UB	—	UB	VOA, PESTICIDES/PCB, PP ANALYZE CONTAMINATED
B1b	14'	3/20/87	✓				✓	1X800L	1	—	UB	—	UB	
B1b	B08	3/20/87	✓				✓	1X800L	1	—	UB	—	UB	
B20	3'	3/20/87	✓				✓	1X800L	1	—		—		
B8	10'-13'	3/20/87	✓				✓	1X800L	1	—		—		
B4	4'-5'	3/20/87	✓				✓	1X800L	1	—		—		
B2	35	3/20/87	✓				✓	1X800L	1	—		—		✓



# FIELD DATA SHEET

2 8 0400

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

Location: Saad Site

Collectors: Paul Karmazinsky

Lab Number (Consec.#'s)

01258

Date Collected

013 7 17 87

Time (24 hr)

1730

## SOIL

## LAND

## VEGETATION

## GROUNDWATER

### Device

Auger  
Core  
Split Spoon  
Cylinder Cup  
Spade

### Soil Type

Rock  
Gravel  
Sand  
Clay  
Silt  
Muck  
Loam  
Peat

### Depth

Ft.  
or  
In.

Color: \_\_\_\_\_

Upland-Dry  
Lowland-Dry  
Floodplain  
Wetland  
Gully

Slope > 15°  
< 15°

Old Field  
Wooded  
Farmland  
Residential  
Industrial  
Commercial

Herbaceous \_\_\_\_\_ %  
Shrubs \_\_\_\_\_ %  
Trees \_\_\_\_\_ %

DBH

In.

Water Table Depth

Ft.

Sample Depth

Ft.

Color: \_\_\_\_\_

Odor: \_\_\_\_\_

Oil: \_\_\_\_\_

Device: \_\_\_\_\_

## SURFACE WATER

## SAMPLE PREPARATION

Color: \_\_\_\_\_ Temp \_\_\_\_\_  
Odor: \_\_\_\_\_ pH \_\_\_\_\_

STREAM Width      Ft.

Depth      Ft.  
or  
In.

Velocity      Ft/Sec

FLOW DIRECTION \_\_\_\_\_

Pools \_\_\_\_\_ % Riffles \_\_\_\_\_ %

### Device

Kemmerer  
Petersen  
Surber  
Manual  
Net  
Seine  
Trawl  
Bucket

### Surface

Clean  
Oil  
Garbage  
Trash  
Bubbles  
Dead Fish  
Sewage  
Ind. Waste  
Float. Solids

### Bottom %

Ooze  
Sand  
Gravel  
Clay  
Rubble  
Rock  
Shell  
Organic

### Container

Glass Jar  
Plastic Jar  
Metal  
Acetate Core  
Paper Cap  
Teflon Cap  
Foil Cap

### Storage

Wet Ice  
Ambient  
Dry Ice

### Cleaning Procedure

Low → High Concentration  
Detergent Wash  
Water Rinse  
Acetone Rinse  
Hexane Rinse  
Other Solvent Rinse  
Specify: \_\_\_\_\_

## TRANSECT INFORMATION

Letter Station #

T 115

Compass Direction

Distance Between Stations

to

is

Ft

Remarks and Site Description

TANK #15



## FIELD DATA SHEET

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

Location: Sead SiteCollectors: George Prince

Lab Number (Consec.#'s)

01260

Date Collected

Mo 03 Day 18 Yr 87

Time (24 hr)

1530

## SOIL

## LAND

## VEGETATION

## GROUNDWATER

## Device

## Soil Type

Auger  
Core  
Split Spoon  
Cylinder Cup  
Spade

Rock  
Gravel  
Sand  
Clay  
Silt  
Muck  
Loam  
Peat

## Depth

Ft.  
or  
In.

Color: \_\_\_\_\_

Upland-Dry  
Lowland-Dry  
Floodplain  
Wetland  
Gully

Slope > 15°  
< 15°

Old Field Residential  
Wooded Industrial  
Farmland Commercial

Herbaceous \_\_\_\_\_ %  
Shrubs \_\_\_\_\_ %  
Trees \_\_\_\_\_ %

DBH

In.

Water Table Depth

Ft.

Sample Depth

Ft.

Color: \_\_\_\_\_

Odor: \_\_\_\_\_

Oil: \_\_\_\_\_

Device: \_\_\_\_\_

## SURFACE WATER

## SAMPLE PREPARATION

Color: \_\_\_\_\_ Temp \_\_\_\_\_  
Odor: \_\_\_\_\_ pH \_\_\_\_\_

Width \_\_\_\_\_ Ft.

Depth \_\_\_\_\_ Ft.  
or  
In.

Velocity \_\_\_\_\_ Ft/Sec

FLOW DIRECTION \_\_\_\_\_

Pools \_\_\_\_\_ % Riffles \_\_\_\_\_ %

## Device

Kemmerer  
Petersen  
Surber  
Manual  
Net  
Seine  
Trawl  
Bucket

## Surface

Clean  
Oil  
Garbage  
Trash  
Bubbles  
Dead Fish  
Sewage  
Ind. Waste  
Float. Solids

## Bottom %

Ooze  
Sand  
Gravel  
Clay  
Rubble  
Rock  
Shell  
Organic

## Container

Glass Jar  
Plastic Jar  
Metal  
Acetate Core  
Paper Cap  
Teflon Cap  
Foil Cap

## Storage

Wet Ice  
Ambient  
Dry Ice

## Cleaning Procedure

Low → High Concentration  
Detergent Wash  
Water Rinse  
Acetone Rinse  
Hexane Rinse  
Other Solvent Rinse  
Specify: \_\_\_\_\_

## TRANSECT INFORMATION

Compass Direction \_\_\_\_\_

Distance Between Stations

Letter Station #  
7 10

\_\_\_\_\_ to \_\_\_\_\_ is \_\_\_\_\_ Ft.

Remarks and Site Description

TANK # 10





## FIELD DATA SHEET

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

Location: Saad Site  
Collectors: George Prince

Lab Number (Consec.#'s)

01261

Date Collected

Mo 03 Day 18 Yr 87

Time (24 hr)

1 5 50

## SOIL

## LAND

## VEGETATION

## GROUNDWATER

## Device

Auger  
Core  
Split Spoon  
Cylinder Cup  
Spade

## Soil Type

Rock  
Gravel  
Sand  
Clay  
Silt  
Muck  
Loam  
Peat

## Depth

Ft.  
or  
In.

Color: \_\_\_\_\_

Upland-Dry  
Lowland-Dry  
Floodplain  
Wetland  
Gully

Slope > 15°  
< 15°

Old Field  
Wooded  
Farmland  
Residential  
Industrial  
Commercial

Herbaceous \_\_\_\_\_ %  
Shrubs \_\_\_\_\_ %  
Trees \_\_\_\_\_ %

DBH    In.

Water Table Depth

    Ft.

Sample Depth

    Ft.

Color: \_\_\_\_\_

Odor: \_\_\_\_\_

Oil: \_\_\_\_\_

Device: \_\_\_\_\_

## SURFACE WATER

## SAMPLE PREPARATION

Color: \_\_\_\_\_ Temp \_\_\_\_\_  
Odor: \_\_\_\_\_ pH \_\_\_\_\_

Stream Width     Ft.Depth     Ft. or In.Velocity     Ft/Sec

FLOW DIRECTION \_\_\_\_\_

Pools \_\_\_\_\_ % Riffles \_\_\_\_\_ %

## Device

Kemmerer  
Petersen  
Surber  
Manual  
Net  
Seine  
Trawl  
Bucket

## Surface

Clean  
Oil  
Garbage  
Trash  
Bubbles  
Dead Fish  
Sewage  
Ind. Waste  
Float. Solids

## Bottom %

Ooze  
Sand  
Gravel  
Clay  
Rubble  
Rock  
Shell  
Organic

## Container

Glass Jar  
Plastic Jar  
Metal  
Acetate Core  
Paper Cap  
Teflon Cap  
Foil Cap

## Storage

Wet Ice  
Ambient  
Dry Ice

## Cleaning Procedure

Low → High Concentration  
Detergent Wash  
Water Rinse  
Acetone Rinse  
Hexane Rinse  
Other Solvent Rinse  
Specify: \_\_\_\_\_

## TRANSECT INFORMATION

Compass Direction \_\_\_\_\_

Distance Between Stations

Letter	Station #
T	17

to    is     Ft.

Remarks and Site Description

T17 Oil/Water Separator Pit - Eastern Tank



## FIELD DATA SHEET

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

Location: Saad SiteCollectors: GP & CB

Lab Number (Consec.#'s)

No 5705

Date Collected

Mo 013 Day 213 Yr 817

Time (24 hr)

0910

SOIL		LAND	VEGETATION		GROUNDWATER	
Device	Soil Type	Upland-Dry Lowland-Dry Floodplain Wetland Gully	Old Field Wooded Farmland	Residential Industrial Commercial	Water Table Depth	Ft.
Auger Core Split Spoon Cylinder Cup Spade	Rock Gravel Sand Clay Silt Muck Loam Peat	Slope > 15° < 15°	Herbaceous _____ % Shrubs _____ % Trees _____ %		Sample Depth	Ft.
Depth	Color: _____		DBH		Color: _____ Odor: _____ Oil: _____ Device: _____	
<div><div></div><div></div><div></div><div></div></div> Ft. or In.						

SURFACE WATER				SAMPLE PREPARATION		
Color: _____	Temp _____	Device	Surface	Bottom %	Container	Cleaning Procedure
C _____	pH _____	Kemmerer Peterson Surber Manual Net Seine Trawl Bucket	Clean Oil Garbage Trash Bubbles Dead Fish Sewage Ind. Waste Float. Solids	Ooze Sand Gravel Clay Rubble Rock Shell Organic	Glass Jar Plastic Jar Metal Acetate Core Paper Cap <u>Teflon Cap</u> Foil Cap	Low → High Concentration Detergent Wash Water Rinse Acetone Rinse Hexane Rinse Other Solvent Rinse Specify: _____
STREAM Width	Ft.				Storage	
Depth	Ft. or In.				<u>Wet Ice</u> Ambient Dry Ice	
Velocity	Ft/Sec					
FLOW DIRECTION _____						
Pools _____ %	Riffles _____ %					

## TRANSECT INFORMATION

Letter	Station #
<u>B</u>	<u>06</u>

Compass Direction

Distance Between Stations

 to  is  Ft

Remarks and Site Description

Borehole #6

3 - 40mils

2 - 1 liter

1 hour after bailing 55 gal.

Oil present



# FIELD DATA SHEET

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

2 8 0464

Location: Saad Site

Collectors: GP

Lab Number (Consec.#'s)  
No 5706

Date Collected  
Mo 013 Day 213 Yr 817

Time (24 hr)  
0925

SOIL		LAND	VEGETATION		GROUNDWATER	
Device Auger Core Split Spoon Cylinder Cup Spade  Depth <div><div></div><div></div><div></div><div></div></div> Ft. or In.	Soil Type Rock Gravel Sand Clay Silt Muck Loam Peat Color: _____	Upland-Dry Lowland-Dry Floodplain Wetland Gully  Slope $> 15^\circ$ $< 15^\circ$	Old Field Wooded Farmland  Herbaceous _____ % Shrubs _____ % Trees _____ % DBH <div><div></div><div></div><div></div></div> In.	Residential Industrial Commercial	Water Table Depth <div><div></div><div></div><div></div><div></div></div> Ft. Sample Depth <div><div></div><div></div><div></div><div></div></div> Ft. Color: _____ Odor: _____ Oil: _____ Device: _____	

SURFACE WATER				SAMPLE PREPARATION	
Color: _____ Odor: _____ Temp _____ pH _____	Device Kemmerer Peterson Surber Manual Net Seine Trawl Bucket	Surface Clean Oil Garbage Trash Bubbles Dead Fish Sewage Ind. Waste Float. Solids	Bottom % Ooze Sand Gravel Clay Rubble Rock Shell Organic	Container <u>Glass Jar</u> Plastic Jar Metal Acetate Core Paper Cap <u>Teflon Cap</u> Foil Cap Storage Wet Ice Ambient Dry Ice	Cleaning Procedure Low $\rightarrow$ High Concentration Detergent Wash Water Rinse Acetone Rinse Hexane Rinse Other Solvent Rinse Specify: _____
Stream Width <div><div></div><div></div><div></div><div></div></div> Ft. Depth <div><div></div><div></div><div></div><div></div></div> Ft. or In. Velocity <div><div></div><div></div><div></div><div></div></div> Ft/Sec FLOW DIRECTION _____ Pools _____ % Riffles _____ %					

## TRANSECT INFORMATION

Letter	Station #
<u>B</u>	<u>08</u>

Compass Direction \_\_\_\_\_

Distance Between Stations

to  is  Ft

## Remarks and Site Description

Borehole 8  
1 hr after bailing 55 gal  
oil present  
3 - 40 mils  
2 - 1 L



# FIELD DATA SHEET

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

2 8 0465

Location: Seed Oil Site

Collectors: A. Prince / C. Burchette

Lab Number (Consec. #'s)

NO 5707

Date Collected

Mo 9 Day 3 Yr 87

Time (24 hr)

1115

## SOIL

## LAND

## VEGETATION

## GROUNDWATER

<b>Device</b> Auger Core Split Spoon Cylinder Cup Spade  <b>Depth</b> <table border="1"><tr><td></td><td></td><td></td><td></td></tr></table> Ft. or In.					<b>Soil Type</b> Rock Gravel Sand Clay Silt Muck Loam Peat Color: _____	<b>Upland-Dry</b> <b>Lowland-Dry</b> <b>Floodplain</b> <b>Wetland</b> <b>Gully</b>  Slope $\geq 15^\circ$ $< 15^\circ$	<b>Old Field</b> <b>Wooded</b> <b>Farmland</b> <b>Residential</b> <b>Industrial</b> <b>Commercial</b>  <b>Herbaceous</b> _____ % <b>Shrubs</b> _____ % <b>Trees</b> _____ %  <b>DBH</b> <table border="1"><tr><td></td><td></td><td></td></tr></table> In.				<b>Water Table Depth</b> <table border="1"><tr><td></td><td></td><td></td><td></td></tr></table> Ft. <b>Sample Depth</b> <table border="1"><tr><td></td><td></td><td></td><td></td></tr></table> Ft.  <b>Color:</b> _____ <b>Odor:</b> _____ <b>Oil:</b> _____ <b>Device:</b> _____								

## SURFACE WATER

## SAMPLE PREPARATION

<b>Color:</b> _____ <b>Temp</b> _____ <b>Odor:</b> _____ <b>pH</b> _____  <b>EAM Width</b> <table border="1"><tr><td></td><td></td><td></td><td></td><td></td></tr></table> Ft.  <b>Depth</b> <table border="1"><tr><td></td><td></td><td></td><td></td></tr></table> Ft. or In.  <b>Velocity</b> <table border="1"><tr><td></td><td></td><td></td><td></td></tr></table> Ft/Sec  <b>FLOW DIRECTION</b> _____ <b>Pools</b> _____ % <b>Riffles</b> _____ %														<b>Device</b> Kemmerer Peterson Surber Manual Net Seine Trawl Bucket	<b>Surface</b> Clean Oil Garbage Trash Bubbles Dead Fish Sewage Ind. Waste Float. Solids	<b>Bottom %</b> Ooze Sand Gravel Clay Rubble Rock Shell Organic	<b>Container</b> Glass Jar Plastic Jar Metal Acetate Core Paper Cap Teflon Cap Foil Cap  <b>Storage</b> Wet Ice Ambient Dry Ice	<b>Cleaning Procedure</b> Low $\rightarrow$ High Concentration Detergent Wash Water Rinse Acetone Rinse Hexane Rinse Other Solvent Rinse Specify: _____

## TRANSECT INFORMATION

Compass Direction

Distance Between Stations

Letter B Station # 04

--	--	--

 to 

--	--	--

 is 

--	--	--	--

 Ft

Remarks and Site Description

Borehole 4  
3 - 40 mils  
2 - 1 liter  
1 hr after bailing  
oil present



## FIELD DATA SHEET

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-8880

Location: Saad SiteCollectors: G Prince C Burchetto

Lab Number (Consec.#'s)

NO 5708

Date Collected

Mo 013 Day 213 Yr 817

Time (24 hr)

1135

## SOIL

Device	Soil Type
Auger	Rock
Core	Gravel
Split Spoon	Sand
Cylinder Cup	Clay
Spade	Silt
	Muck
	Loam
	Peat
Depth	Color: _____
<input type="text"/> <input type="text"/> <input type="text"/> <input type="text"/>	
Ft. or In.	

## LAND

Upland-Dry  
Lowland-Dry  
Floodplain  
Wetland  
Gully

Slope  $> 15^\circ$   
 $< 15^\circ$

## VEGETATION

Old Field  
Wooded  
Farmland  
Residential  
Industrial  
Commercial

Herbaceous \_\_\_\_\_ %  
Shrubs \_\_\_\_\_ %  
Trees \_\_\_\_\_ %

DBH    in.

## GROUNDWATER

Water Table Depth     Ft.Sample Depth     Ft.

Color: \_\_\_\_\_

Odor: \_\_\_\_\_

Oil: \_\_\_\_\_

Device: \_\_\_\_\_

## SURFACE WATER

Color: \_\_\_\_\_ Temp \_\_\_\_\_  
Odor: \_\_\_\_\_ pH \_\_\_\_\_

Stream Width      Ft.

Depth      Ft. or In.

Velocity      Ft/Sec

FLOW DIRECTION \_\_\_\_\_

Pools \_\_\_\_\_ % Riffles \_\_\_\_\_ %

Device	Surface	Bottom %
Kemmerer	Clean	Ooze
Petersen	Oil	Sand
Surber	Garbage	Gravel
Manual	Trash	Clay
Net	Bubbles	Rubble
Seine	Dead Fish	Rock
Trawl	Sewage	Shell
Bucket	Ind. Waste	Organic
	Float. Solids	

## SAMPLE PREPARATION

Container	Cleaning Procedure
Glass Jar	Low $\rightarrow$ High Concentration
Plastic Jar	Detergent Wash
Metal	Water Rinse
Acetate Core	Acetone Rinse
Paper Cap	Hexane Rinse
Teflon Cap	Other Solvent Rinse
Foil Cap	Specify: _____
Storage	
Wet Ice	
Ambient	
Dry Ice	

## TRANSECT INFORMATION

Letter	Station #
B	23

B-17

Compass Direction

Distance Between Stations

   to    is     Ft

Remarks and Site Description

Developed by driller  
oil present

3-40 miles  
2-1 liter



# FIELD DATA SHEET

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

28 0467

Location: Saad Oil Site

Collectors: G Prince C Barchetto

Lab Number (Consec.#'s)

No 5709

Date Collected

Mo 01 Day 13 Yr 81

Time (24 hr)

1 2 1 0

SOIL		LAND	VEGETATION		GROUNDWATER	
Device	Soil Type	Upland-Dry Lowland-Dry Floodplain Wetland Gully	Old Field Wooded Farmland	Residential Industrial Commercial	Water Table Depth	Ft.
Auger	Rock					
Core	Gravel					
Split Spoon	Sand				Sample Depth	Ft.
Cylinder Cup	Clay		Herbaceous	%		
Spade	Silt		Shrubs	%		
Depth	Muck	Slope > 15° < 15°	Trees	%	Color:	
	Loam		DBH	In.	Odor:	
	Peat				Oil:	
	Color:				Device:	

SURFACE WATER				SAMPLE PREPARATION	
Color:	Temp	Device	Surface	Bottom %	Container
Odor:	pH	Kemmerer	Clean	Ooze	Glass Jar
		Petersen	Oil	Sand	Plastic Jar
Stream Width	Ft.	Surber	Garbage	Gravel	Metal
		Manual	Trash	Clay	Acetate Core
Depth	Ft or In.	Net	Bubbles	Rubble	Paper Cap
		Seine	Dead Fish	Rock	Teflon Cap
Velocity	Ft/Sec	Trawl	Sewage	Shell	Foil Cap
		Bucket	Ind. Waste	Organic	Storage
FLOW DIRECTION			Float. Solids		Wet Ice
Pools %	Riffles %				Ambient
					Dry Ice

## TRANSECT INFORMATION

Letter	Station #
B	02

B-2

Compass Direction

Distance Between Stations

         to          is          Ft

Remarks and Site Description

3-40 miles  
Bailed 30 minutes previous 2-1 liter  
oil present  
chemical odor



## FIELD DATA SHEET

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

Location: Saad Oil SiteCollectors: G. Prince, C. Burchette

Lab Number (Consec.#'s)

No 5710

Date Collected

Mo 01 Day 13 Yr 81

Time (24 hr)

1 35 0

## SOIL

## LAND

## VEGETATION

## GROUNDWATER

Device

Soil Type

Auger  
Core  
Split Spoon  
Cylinder Cup  
Spade

Rock  
Gravel  
Sand  
Clay  
Silt  
Muck  
Loam  
Peat

Depth

            Ft.  
or  
In.

Color:   

Upland-Dry  
Lowland-Dry  
Floodplain  
Wetland  
Gully

Slope  $> 15^\circ$   
 $< 15^\circ$

Old Field    Residential  
Wooded      Industrial  
Farmland    Commercial

Herbaceous    %  
Shrubs    %  
Trees    %

DBH          In.Water Table Depth             Ft.Sample Depth             Ft.Color:   Odor:   Oil:   Device:   

## SURFACE WATER

## SAMPLE PREPARATION

Color:    Temp   Odor:    pH   STREAM Width             Ft.Depth             Ft. or In.Velocity             Ft/SecFLOW DIRECTION   Pools    % Riffles    %

Device

Kemmerer  
Petersen  
Surber  
Manual  
Net  
Seine  
Trawl  
Bucket

Surface

Clean  
Oil  
Garbage  
Trash  
Bubbles  
Dead Fish  
Sewage  
Ind. Waste  
Float. Solids

Bottom %

Ooze  
Sand  
Gravel  
Clay  
Rubble  
Rock  
Shell  
Organic

Container

Glass Jar  
Plastic Jar  
Metal  
Acetate Core  
Paper Cap  
Teflon Cap  
Foil Cap

Storage

Wet Ice  
Ambient  
Dry Ice

Cleaning Procedure

Low  $\rightarrow$  High Concentration  
Detergent Wash  
Water Rinse  
Acetone Rinse  
Hexane Rinse  
Other Solvent Rinse  
Specify:   

## TRANSECT INFORMATION

Letter B Station # 01 BL

Compass Direction         

Distance Between Stations

         to          is             Ft.

Remarks and Site Description

purged 15 minutes until dry

3-40 miles  
2-1 liter



## FIELD DATA SHEET

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

Location: Saad Oil SiteCollectors: G Prince C Burchetto

Lab Number (Consec. #'s)

No 5711

Date Collected

Mo 013 Day 213 Yr 817

Time (24 hr)

1400

## SOIL

## LAND

## VEGETATION

## GROUNDWATER

## Device

Auger  
Core  
Split Spoon  
Cylinder Cup  
Spade

## Soil Type

Rock  
Gravel  
Sand  
Clay  
Silt  
Muck  
Loam  
Peat

Color: \_\_\_\_\_

## Depth

                    Ft.  
or  
In.

Upland-Dry  
Lowland-Dry  
Floodplain  
Wetland  
Gully

Slope  $> 15^\circ$   
 $< 15^\circ$

Old Field  
Wooded  
Farmland  
Residential  
Industrial  
Commercial

Herbaceous \_\_\_\_\_ %  
Shrubs \_\_\_\_\_ %  
Trees \_\_\_\_\_ %

DBH

               In.

Water Table Depth

                    Ft.

Sample Depth

                    Ft.

Color: \_\_\_\_\_

Odor: \_\_\_\_\_

Oil: \_\_\_\_\_

Device: \_\_\_\_\_

## SURFACE WATER

## SAMPLE PREPARATION

Color: \_\_\_\_\_ Temp \_\_\_\_\_  
Odor: \_\_\_\_\_ pH \_\_\_\_\_

STREAM Width                     Ft.Depth                     Ft.  
or  
In.Velocity                     Ft/Sec

FLOW DIRECTION \_\_\_\_\_

Pools \_\_\_\_\_ % Riffles \_\_\_\_\_ %

## Device

Kemmerer  
Petersen  
Surber  
Manual  
Net  
Seine  
Trawl  
Bucket

## Surface

Clean  
Oil  
Garbage  
Trash  
Bubbles  
Dead Fish  
Sewage  
Ind. Waste  
Float. Solids

## Bottom %

Ooze  
Sand  
Gravel  
Clay  
Rubble  
Rock  
Shell  
Organic

## Container

Glass Jar  
Plastic Jar  
Metal  
Acetate Core  
Paper Cap  
Teflon Cap  
Foil Cap

## Storage

Wet Ice  
Ambient  
Dry Ice

## Cleaning Procedure

Low  $\rightarrow$  High Concentration  
Detergent Wash  
Water Rinse  
Acetone Rinse  
Hexane Rinse  
Other Solvent Rinse  
Specify: \_\_\_\_\_

## TRANSECT INFORMATION

Compass Direction \_\_\_\_\_

Distance Between Stations

Letter	Station #
B	25519

               to

               is

                    Ft.

Remarks and Site Description

*purged for 30 minutes  
presence of oil*

*3-40 miles  
2-1 liter*





## FIELD DATA SHEET

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

Location: Seed Oil

Collectors: A. Prince / C. Burchette

Lab Number (Consec.#'s)  
NO 5719

Date Collected  
Mo 03 Day 210 Yr 87

Time (24 hr)  
              

SOIL		LAND	VEGETATION		GROUNDWATER	
<b>Device</b> Auger Core Split Spoon Cylinder Cup Spade  <b>Depth</b> <u>    </u> <u>    </u> <u>    </u> <u>    </u> Ft. or In.	<b>Soil Type</b> Rock Gravel Sand Clay Silt Muck Loam Peat Color: <u>    </u>	Upland-Dry Lowland-Dry Floodplain Wetland Gully  Slope $> 15^\circ$ $< 15^\circ$	Old Field Wooded Farmland  Herbaceous <u>    </u> % Shrubs <u>    </u> % Trees <u>    </u> % DBH <u>    </u> <u>    </u> <u>    </u> In.	Residential Industrial Commercial	<b>Water Table Depth</b> <u>    </u> <u>    </u> <u>    </u> <u>    </u> Ft. <b>Sample Depth</b> <u>    </u> <u>    </u> <u>    </u> <u>    </u> Ft. Color: <u>    </u> Odor: <u>    </u> Oil: <u>    </u> Device: <u>    </u>	

## SURFACE WATER

## SAMPLE PREPARATION

SURFACE WATER		Device	Surface	Bottom %	Container	Cleaning Procedure
Color: <u>    </u> Odor: <u>    </u> Temp <u>    </u> pH <u>    </u> SAM Width <u>    </u> <u>    </u> <u>    </u> <u>    </u> Ft. Depth <u>    </u> <u>    </u> <u>    </u> <u>    </u> Ft. or In. Velocity <u>    </u> <u>    </u> <u>    </u> <u>    </u> Ft/Sec FLOW DIRECTION <u>    </u> Pools <u>    </u> % Riffles <u>    </u> %	Kemmerer Petersen Surber Manual Net Seine Trawl Bucket	Clean Oil Garbage Trash Bubbles Dead Fish Sewage Ind. Waste Float. Solids	Ooze Sand Gravel Clay Rubble Rock Shell Organic	Glass Jar Plastic Jar Metal Acetate Core Paper Cap Teflon Cap Foil Cap  <b>Storage</b> Wet Ice Ambient Dry Ice	Low $\rightarrow$ High Concentration Detergent Wash Water Rinse Acetone Rinse Hexane Rinse Other Solvent Rinse Specify: <u>    </u>	

## TRANSECT INFORMATION

Letter	Station #
<u>    </u>	<u>    </u>

Compass Direction     

Distance Between Stations

               to                is                     Ft.

Remarks and Site Description

Composite of Tank #1  
 Tank #4  
 Tank #11  
 Tank #6  
 Truck Tank #16



## FIELD DATA SHEET

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6880

Location: Saad Oil

Collectors: H. Preiner / C. Burchette

Lab Number (Consec. #'s)

NO 5720

Date Collected

Mo 013 Day 20 Yr 87

Time (24 hr)

## SOIL

## LAND

## VEGETATION

## GROUNDWATER

<b>Device</b> Auger Core Split Spoon Cylinder Cup Spade  <b>Depth</b> <u>  </u> <u>  </u> <u>  </u> <u>  </u> Ft. or In.		<b>Soil Type</b> Rock Gravel Sand Clay Silt Muck Loam Peat Color: <u>      </u>	<b>Upland-Dry</b> <b>Lowland-Dry</b> <b>Floodplain</b> <b>Wetland</b> <b>Gully</b>  Slope $> 15^\circ$ $< 15^\circ$	<b>Old Field</b> <b>Wooded</b> <b>Farmland</b> <b>Residential</b> <b>Industrial</b> <b>Commercial</b>  Herbaceous <u>      </u> % Shrubs <u>      </u> % Trees <u>      </u> % DBH <u>  </u> <u>  </u> <u>  </u> In.	<b>Water Table Depth</b> <u>  </u> <u>  </u> <u>  </u> <u>  </u> Ft.  <b>Sample Depth</b> <u>  </u> <u>  </u> <u>  </u> <u>  </u> Ft.  Color: <u>      </u> Odor: <u>      </u> Oil: <u>      </u> Device: <u>      </u>
--	--	--	--	--	---

## SURFACE WATER

## SAMPLE PREPARATION

Color: <u>      </u> Temp <u>      </u> Odor: <u>      </u> pH <u>      </u>  <b>Stream</b> Width <u>  </u> <u>  </u> <u>  </u> <u>  </u> Ft. Depth <u>  </u> <u>  </u> <u>  </u> <u>  </u> Ft. or In. Velocity <u>  </u> <u>  </u> <u>  </u> <u>  </u> Ft/Sec  FLOW DIRECTION <u>      </u> Pools <u>      </u> % Riffles <u>      </u> %	<b>Device</b> Kemmerer Petersen Surber Manual Net Seine Trawl Bucket	<b>Surface</b> Clean Oil Garbage Trash Bubbles Dead Fish Sewage Ind. Waste Float. Solids	<b>Bottom %</b> Ooze Sand Gravel Clay Rubble Rock Shell Organic	<b>Container</b> Glass Jar Plastic Jar Metal Acetate Core Paper Cap Teflon Cap Foil Cap  <b>Storage</b> Wet Ice Ambient Dry Ice	<b>Cleaning Procedure</b> Low $\rightarrow$ High Concentration Detergent Wash Water Rinse Acetone Rinse Hexane Rinse Other Solvent Rinse Specify: <u>      </u>
--	--	---	---	---	--

## TRANSECT INFORMATION

Letter	Station #
<u>  </u>	<u>  </u>

Compass Direction

Distance Between Stations

         to          is             Ft.

Remarks and Site Description

Composite duplicate of:  
 Tank #1  
 Tank #4  
 Tank #11  
 Tank #6  
 Truck Tank #16



PROJECT Saad Waste Oil 28 0472  
 PROJECT NO. 37069190499 BORING B-1  
 ELEVATION 581.7 DATE 3/19/87  
 FIELD GEOLOGIST Karmazinski

Sample No., Type, and Depth (FT.)	Blows/ Six Inches or RQD (%)	Material Moisture and Water Depth (FT.)	Soil Density/ Consistency or Rock Hardness	LITHOLOGY	DESCRIPTION
0.0' - 7"	26/50/1"	Dry	V. Dense		0.0'-2.5' Dark Gray Gravel Fill, Some Reddish Brown Sand and Clay
S-2	19				
1.5' - 3.0'	12/17		M. Dense		2.5'-3.0' Oil Impregnated Gravel, Sand & Clay with Wood Particles (Organic Odor)
S-3	10/12	Moist			3.0'-5.0' Oil Impregnated Dark Gray-Black Gravel, Clay, Sand
4.5' - 6.0'	36/10		Dense		5.0'-6.0' Brown Clay & Gravel; Trace Silt & Sand
S-4	10/30		Hard		6.0'-6.5' Oil Impregnated Clay & Gravel; Trace Silt & Sand
6.0' - 7.5'	20/45		Hard		6.5'-7.5' Brown Clay & Gravel, Trace Silt & Sand
S-5	19/10	Wet			7.5'-8.0' Gravel
7.5' - 9.0'	6/7		Stiff		8.0'-9.0' Lt. Brown Silty Clay & Coarse Sand Slightly Impregnated @ 8.9'
R-1					9.0'-13.0' No Recovery
9.0' - 13.0'					
R-2					13.0'-13.5' Gray to Blue-Green Clay; Trace Gravel
13.0' - 13.5'					
					BOB 13.5'
					Rock 13.5'

REMARKS Drilling Method - Auger BORING B-1  
Casing - Temporary  
 PAGE 1 OF 1

PROJECT Saad Waste Oil  
 PROJECT NO. 37069190499 BORING B-2  
 ELEVATION 580.3 DATE 3/19/87  
 FIELD GEOLOGIST Karmazinski

2804/3

	Sample No., Type, and Depth (FT.)	Blows/ Six Inches or RQD (%)	Material Moisture and Water Depth (FT.)	Soil Density/ Consistency or Rock Hardness	LITHOLOGY	DESCRIPTION
0.0'	S-1 0.0'-1.5'	23/25 7/5	Moist	Dense		0.0'-1.0' Dark Gray Gravel Fill
	S-2 1.5'-3.0'	4/9		Stiff		1.0'-2.5' Dk. Gray Gravel Fill & Brown Sandy Clay, Mottled
	S-3 3.0'-4.5'	8/6		Stiff		2.5'-3.0' Gray Silty Clay - Slight Odor
	S-4 4.5'-6.0'	8/3				3.0'-5.0' Greenish Brown Clayey Silt with Rotted Wood Debris
5.0'	S-5 6.0'-7.5'	3/5		M. Stiff		5.0'-15.2' Dk. Gray Clayey Silt - Some Sand, Slight Oily texture, Distinct Odor 6.0' to BOB, 7.4'-7.5' Clay Lense 7.5'-15.2' Increased Sand Concentration Downward with Sand Lenses
	S-6 7.5'-9.0'	2/2		M. Stiff		
	R-1 9.0'-14.0'	4/1				
		1/1	V. Soft			
10.0'			Wet			15.2'-17.2' Lt. Gray Silty Clay with Some Well Graded Sand
						17.2'-17.5' Lt. Gray Weathered Sandstone
15.0'	R-2 14.0'-17.5'					

REMARKS

Drilling Method - Auger



Casing - Temporary

BORING B-2

PAGE 1 OF 1

2 8 0474

PROJECT Saad Waste Oil  
 PROJECT NO. 37069190499 BORING B-3  
 ELEVATION 581.3 DATE 3/19/87  
 FIELD GEOLOGIST Karmazinski

Sample No., Type, and Depth (FT.)	Blows/ Six Inches or RQD (%)	Material Moisture and Water Depth (FT.)	Soil Density/ Consistency or Rock Hardness	LITHOLOGY	DESCRIPTION
0.0' S-1 0.0'-1.5'	9/15	Dry	M.Dense		0.0'-1.5' Dark Gray Gravel, Some Reddish Brown Sand & Clay Fill, 1.4'-1.5' Oil Impregnated
S-2 1.5'-3.0'	14/9				1.5'-3.0' Gray Gravel & Brown Sand, Slight Oil Stain, (Slight Odor)
1.5'-3.0' S-3 3.0'-4.5'	22/39	Moist	V.Dense		3.0'-4.5' Dk. Gray Gravel and Brown Sand
4.5'-5.4" S-4 4.5'-5.7"	7/3		V.Dense		4.5'-5.4" Dk. Gray Gravel and Reddish Brown Sandy Clay
	46/50/1"				
					Auger Refusal 5'4" (Not on Rock)






0475

**FIELD GEOLOGIST** Karmazinski

**PAGE 1 OF 1**

PROJECT Saad Waste Oil  
 PROJECT NO. 37069190499 BORING B-5  
 ELEVATION 581.5 DATE 3/20/87  
 FIELD GEOLOGIST Karmazinski

280476

Sample No., Type, and Depth (FT.)	Blows/ Six Inches or RQD (%)	Material Moisture and Water Depth (FT.)	Soil Density/ Consistency or Rock Hardness	LITHOLOGY	DESCRIPTION
0.0' S-1 0.0'-5"	50/5"/	Dry	V. Dense		0.0'-4.0' Dark Gray Gravel
S-2 1.5'-1'10"	/50/4"				
S-3 3.0'-4.5'	40/34		V. Dense		
S-4 4.5'-6.0'	25/15				4.0'-6.0' Dark Gray Gravel, Brown Clayey Silt and Sand
S-5 6.0'-7.5'	4/3	Moist	M. Dense		6.0'-7.5' Brown Sandy Clay - Odor Present
S-6 7.5'-9.0'	5/2		Stiff		7.5'-10.5' Oil Impregnated Sandy Clay and Gravel Grading to Oil Laden Gravel, Clay and Sand @ 8.0'
S-7 9.0'-10.5'	4/7	Wet	Stiff		
	6/5				
	15/		V. Stiff		10.5'-14.5' No Recovery
10.5'-14.5'					
14.5'-19.5'					
R-2 14.5'-19.5'					14.5'-15.0' Oil Laden Gravel
					15.0'-17.5' Brown Clayey Silt, Some Sand and Gravel
					17.5'-19.0' Brown Sandy Silt and Gravel
					19.0'-19.5' Brown Clayey Silt and Sand
					Auger Refusal 19.5'
					BOB 19.5'

REMARKS Drilling Method - Auger BORING B-5  
Casing - Temporary  
 PAGE 1 OF 1

280477

0.0.

50'

100

**PAGE 1 OF 1**



PROJECT Saad Waste Oil  
PROJECT NO. 37069190499 BORING B-8  
ELEVATION \_\_\_\_\_ DATE 3/21/87  
FIELD GEOLOGIST Karmazinski

[illegible]


**REMARKS** Drilling Method - Auger  
Casing - None Installed

**BORING** B-8

**PAGE** 1 **OF** 1

PROJECT Saad Waste Oil  
 PROJECT NO. 37069190499 BORING B-9  
 ELEVATION 581.5 DATE 3/21/87  
 FIELD GEOLOGIST Karmazinski

280479

Sample No., Type, and Depth (FT.)	Blows/ Six Inches or RQD (%)	Material Moisture and Water Depth (FT.)	Soil Density/ Consistency or Rock Hardness	LITHOLOGY	DESCRIPTION
0.0'- S-1	15/18	Moist	Dense		0.0'-0.5' Dark Gray Gravel Fill
0.5'- S-2	19/8				0.5'-5.25' Dark Gray Gravel and Sand Fill with Oil Stain
1.5'- S-3	30/12		Dense		
3.0'- S-4	30/14		M. Dense		3.0'-5.25' Red Paint or Dye on Split Barrel, Mixed with Oil
4.5'- S-4	16/7	Wet			Auger Refusal and BOB 5.25'
4.5'- 5.25'	50/3"/				

REMARKS Drilling Method - Auger BORING B-9  
Casing - None Installed  
 PAGE 1 OF 1

280430

00.















5.0'

100

**PAGE 1 OF 1**

PROJECT Saad Waste Oil  
 PROJECT NO. 37069190499 BORING B-11  
 ELEVATION 582.2 DATE 3/22/87  
 FIELD GEOLOGIST Karmazinski

280481

Sample No., Type, and Depth (FT.)	Blows/ Six Inches or RQD (%)	Material Moisture and Water Depth (FT.)	Soil Density/ Consistency or Rock Hardness	LITHOLOGY	DESCRIPTION
0.0' S-1 0.0'-1.5'	16/29	Moist	Dense		0.0'-4.5' Dark Gray Gravel Fill and Clayey Silt, Some Sand, Dry Oil Impregnated
S-2 1.5'-1'11"	10/50/5"				
S-3 3.0'-4.5'	39/6		V. Dense		
S-4 4.5'-6.0'	8/5		M. Dense		
5.0' S-5 6.0'-6.5'	3/5	Wet	Loose		4.5'-7.5' No Recovery
S-6 6.5'-7.5'	2/50/0"				
R-1 9.0'-14.0'			V. Dense		
		Wet			7.5'-8.7' Oil Laden Clayey Silt
10.0' R-2 14.0'-17.8'		Wet			8.7'-9.0' Oil Laden Sand 9.0'-12.5' Oil Laden Clayey Silt and Gravel, Some Sand Bottom of Oil Laden Zone 12.5'
		Wet			12.5'-17'8" Brown Clayey Silt with Sand Lenses, Some Oil Stain
		Wet			12.5'-17'8" Brown Clayey Silt with Sand Lenses, Some Oil Stain
		Wet			Rock 17'8" BOB 17'8"
		Wet			Rock 17'8" BOB 17'8"
		Wet			Rock 17'8" BOB 17'8"
		Wet			Rock 17'8" BOB 17'8"
		Wet			Rock 17'8" BOB 17'8"
		Wet			Rock 17'8" BOB 17'8"
		Wet			Rock 17'8" BOB 17'8"
		Wet			Rock 17'8" BOB 17'8"

REMARKS Drilling Method - Auger BORING B-11  
Casing - Well Installed  
 PAGE 1 OF 1

28 C462

0.0'

5.0'

10.0'

15.0'

**PAGE 1 OF 1**

280483

0.0.

50'

100'



150

200

**PAGE 1 OF 1**




PROJECT Saad Waste Oil  
 PROJECT NO. 37069190499 BORING B-15  
 ELEVATION 581.8 DATE 3/18/87  
 FIELD GEOLOGIST Karmazinski

Sample No., Type, and Depth (FT.)	Blows/ Six Inches or RQD (%)	Material Moisture and Water Depth (FT.)	Soil Density/ Consistency or Rock Hardness	LITHOLOGY	2 8 0485
					DESCRIPTION
S-1 0.0'- 1'11"	7/12	Dry	V. Dense		0.0'-1.0' Dark Gray Gravel
S-2 1.5'- 1.75'	50/5" / 50/3"		V. Dense		1.0'-2.25' Dark Gray Gravel and Reddish Brown Sand and Clay
					BOB 2.25' Rock 2.25'



PROJECT Saad Waste Oil  
 PROJECT NO. 37069190499 BORING B-16  
 ELEVATION 581.4 DATE 3/18/87  
 FIELD GEOLOGIST Karmazinski

28  
0466




Sample No., Type, and Depth (FT.)	Blows/ Six Inches or RQD (%)	Material Moisture and Water Depth (FT.)	Soil Density/ Consistency or Rock Hardness	LITHOLOGY	DESCRIPTION
S-1 0.0'- 1.25'	12/14	Dry	V.Dense		0.0'-3.5' Dark Gray Gravel
S-2 1.5'- 1'10"	50/3" / 50/4"		V.Dense		
S-3 3.5'	/50/0"				
					BOB 3.5' Rock 3.5'

280467

**PAGE 1 OF 1**

PROJECT Saad Waste Oil  
 PROJECT NO. 37069190499 BORING B-18  
 ELEVATION 581.8 DATE 3/19/87  
 FIELD GEOLOGIST Karmazinski

2  
8  
0468

Sample No., Type, and Depth (FT.)	Blows/ Six Inches or RQD (%)	Material Moisture and Water Depth (FT.)	Soil Density/ Consistency or Rock Hardness	LITHOLOGY	DESCRIPTION
0.0'	S-1 0.0'-1.5'	9/12	M. Dense		0.0'-3.0' Dark Gray Gravel Fill and Reddish Brown Silty Clay, Some Sand
	S-2 1.5'-3.0'	9/12			
		13/14	M. Dense		
	S-3 3.0'-4.5'	1/4	M. Dense		3.0'-5.0' Reddish Brown Sandy Silt; Some Clay and Trace Med. Gray Gravel
5.0'	S-4 4.5'-6.0'	8/8			5.0'-6.5' Debris-Wood and Reddish Brown Silty Clay, Some Oil Staining and Odor
	R-1 6.0'-8.5'	10/12	M. Dense		6.5'-8.5' Gravel and Sand, Trace Silt and Clay, Oil
		▽			
		Wet			
10.0'					BOB 8.5' Rock 8.5'

REMARKS Drilling Method - Auger BORING B-18  
Casing - Well Installed  
 PAGE 1 OF 1

280469

**PAGE 1 OF 1**

PROJECT Saad Waste Oil  
PROJECT NO. 37069190499 BORING B-20  
ELEVATION 581.1 DATE 3/20/87  
FIELD GEOLOGIST Karmazinski

28 0490

[illegible]

**REMARKS** Drilling Methods - Auger to 6.0', Air Rotary to 15.0'  
Casing - Temporary

**BORING** B-20

**PAGE** 1 **OF** 1

280491

0.0'

5.0'

100'

150

20.0

**PAGE 1 OF 1**

APPENDIX C

9/86 SAMPLING PROGRAM LAB RESULTS

**ENVIRESPONSE, INC.**

ENVIRONMENTAL EMERGENCY RESPONSE UNIT

GSA RARITAN DEPOT, WOODBRIDGE AVENUE, BUILDING 209, BAY F. EDISON, N.J. 08837  
(201) 548-9660**WATER ANALYSIS FOR SAAD WASTE OIL SITE****Nashville, TN****Project No. 3-70-69190499****October 23, 1986**

Submitted to: G. Prince  
USEPA-RCB  
Edison, NJ

Submitted by:

Enviresponse, Inc.

*J. P. Michalowicz* 10/23/86  
J. P. Michalowicz  
EI-EERU Project Manager

*D. D. Chen* 10/23/86  
D. D. Chen, Ph.D.  
EI-EERU S&A Section Chief

*J. Giga* 10/23/86  
J. Giga, Ph.D.  
EI-EERU QA/QC Officer

Analysis by:

Clayton  
Environmental  
Consultants

Reviewed by:

Janet Cullinane



## TABLE OF CONTENTS

SECTION I

## Introduction

## Procedures

## Sample Results

Detection Limits for Volatile Organics Analysis. . . . .	Table 1
Results of Volatile Organics Analysis. . . . .	Table 2
Detection Limits for PCB/Pesticides Analysis . . . . .	Table 3
Results of PCB/Pesticides Analysis . . . . .	Table 4
Detection Limits for Base Neutral/Acid Extractables. . . . .	Table 5
Results of Base Neutral/Acid Extractables. . . . .	Table 6
Detection Limits for Metals Analysis . . . . .	Table 7
Results of Total Metals Analysis . . . . .	Table 8
Results of Dissolved Metals Analysis . . . . .	Table 9
Results of Chlorides and Bromides Analysis . . . . .	Table 10
Results of Oil Fingerprinting. . . . .	Table 11

SECTION II

## QA/QC Procedures

## QA/QC Results

Surrogate Standard Recoveries for	
Volatile Organics Analysis. . . . .	QA/QC Table 12
Results of Duplicate Volatile Organics Analysis. . . . .	QA/QC Table 13
Results of Volatile Organics Analysis Matrix Spike . . . . .	QA/QC Table 14
Surrogate Standard Recoveries for PCB/Pesticides . . . . .	QA/QC Table 15
Results of Duplicate PCB/Pesticides Analysis . . . . .	QA/QC Table 16
Results of PCB/Pesticides Matrix Spike Analysis. . . . .	QA/QC Table 17
Surrogate Standard Recoveries for BNAs . . . . .	QA/QC Table 18
Results of Duplicate BNA Analysis. . . . .	QA/QC Table 19
Results of BNA Matrix Spike Analysis . . . . .	QA/QC Table 20
Results of Duplicate Metals Analysis . . . . .	QA/QC Table 21
Results of Metals Matrix Spike Analysis. . . . .	QA/QC Table 22
Results of Duplicate Chlorides and Bromides Analysis . . . . .	QA/QC Table 23
Results of Chlorides and Bromides Matrix Spikes. . . . .	QA/QC Table 24

SECTION III

## Data for Volatile Organics Analysis

SECTION IV

## Data for PCB/Pesticides Analysis

SECTION V

Data for Base Neutral/Acid Extractables Analysis

SECTION VI

Data for Chlorides and Bromides Analysis

SECTION VII

Oil Fingerprinting Chromatograms

SECTION VIII

Service Laboratory Correspondence

SECTION IX

Chain of Custody Records

# INTRODUCTION

On September 13, 1986, 10 water samples and one oil sample from the Saad Waste Oil Site in Nashville, Tennessee were received by Enviresponse, Inc. They were submitted to Clayton Environmental Consultants for priority pollutant volatile organics, PCB/Pesticides, and Base Neutral/Acid Extractables analyses plus chlorides, bromides, and 15 metals. In addition, oil fingerprinting analyses were performed.

## PROCEDURES

All priority pollutant organics and metals analyses were conducted in accordance with Contract Lab Program (CLP) protocols. Method blank results for all priority pollutant parameters were below the required limit of detection.

Volatile Organics Analysis: All water samples were analyzed by purge and trap-GC/MS. The oil sample was dissolved in methanol and a portion of the methanol was injected into water for purge and trap-GC/MS analysis.

PCB/Pesticides Analysis: Water samples were serially extracted with methylene chloride, concentrated to a final volume of 1 ml, and solvent exchanged with iso-octane. The oil sample was dissolved in iso-octane. All samples were analyzed by electron capture detector-gas chromatography (ECD-GC). GC/MS confirmation was not performed for sample parameters which were undetected or below the method detection limit for GC/MS. Confirmation of PCBs in sample 7334, oil and water, were performed using capillary column ECD-GC.

Base Neutral/Acid Extractables: Water samples were serially extracted with methylene chloride after treatment with NaOH to raise the pH to 12. The water was then acidified to a pH less than 2 and serially extracted with methylene chloride. The extracts were combined and concentrated to a final volume of 1 ml. The oil sample was diluted with methylene chloride. Sample extracts were then analyzed by GC/MS.

Metals: The water samples were analyzed according to EPA Document 600-4-79-020, Methods for the Examination of Water and Wastewater. The oil sample was analyzed according to EPA Document SW 846, Method 3050, Test Methods for Evaluating Solid Waste.

Chlorides/Bromides: The analysis of the water samples was performed according to EPA Document 600-4-790-20, Method 300.1, Methods for the Examination of Water and Wastewater.

Oil Fingerprinting: The water samples were extracted with Freon prior to flame ionization detector-gas chromatography (FID-GC) analysis. The oil sample was diluted using Freon. No. 2 diesel fuel was diluted with Freon to various concentrations and analyzed by FID-GC. The chromatograms of the oil and water extracts were analyzed and compared to the diesel fuel chromatograms.

Results and detection limits for the above described analyses are presented in Tables 1-11.

Table 1. Detection Limits for Volatile Organics Analysis

Parameter	Detection Limit (water) ug/l	Detection Limit (oil) ug/g
Chloromethane	10	50
Bromomethane	10	50
Vinyl Chloride	10	50
Chloroethane	10	50
Methylene Chloride	5	25
Trichlorofluoromethane	1	25
1,1-Dichloroethylene	5	25
1,1-Dichloroethane	5	25
Trans-1,2-Dichloroethylene	5	25
Chloroform	1	25
1,2-Dichloroethane	5	25
1,1,1-Trichloroethane	5	25
Carbon Tetrachloride	5	25
Bromodichloromethane	5	25
1,2-Dichloropropane	7	35
Trans-1,3-Dichloropropylene	5	25
Trichloroethylene	5	25
Dibromochloromethane	5	25
1,1,2-Trichloroethane	5	25
Benzene	5	25
cis-1,3-Dichloropropene	5	25
2-Chloroethylvinyl ether	10	50
Bromoform	5	25
Tetrachloroethylene	5	25
Toluene	1	25
Chlorobenzene	5	25
Ethylbenzene	5	25
1,3-Dichlorobenzene	15	75
1,4-Dichlorobenzene	15	75
1,2-Dichlorobenzene	7	35

Table 2. Results of Volatile Organics Analysis

Sample No.	Parameter	Concentration
<u>Water</u>		(reported as ug/l)
7331	Trichloroethylene	<5
7332	None Detected	---
7333	None Detected	---
7334	Vinyl chloride	9800
	Methylene chloride	5500
	1,1-Dichloroethane	1700
	Trans-,2-dichloroethylene	52000
	1,1,1-Trichloroethane	6300
	Trichloroethylene	30000
	Tetrachloroethylene	9600
	Toluene	4600
	Ethyl benzene	500
7335	Chloroform	<1
	Toluene	<1
7341	Chloroethane	130
	Methylene chloride	6.0
	1,1-Dichloroethane	8.0
7342	None Detected	---
7344	Trans-1,2-dichloroethylene	<5
	Tetrachloroethylene	6.0
7345	Trans-1,2-dichloroethylene	<5
	Trichloroethylene	7.0
	Tetrachloroethylene	6.0
7346	Trans-1,2-dichloroethylene	<5
	Toluene	<5
7353	None Detected	---

Table 2. Results of Volatile Organics Analysis (Cont'd)

Sample No.	Parameter	Concentration
<u>011</u>		(reported as ug/g)
7334	Vinyl chloride	290.
	Methylene chloride	670.
	1,1-Dichloroethane	130
	Trans-1,2-dichloroethylene	4200.
	1,1,1-Trichloroethane	1700.
	Trichloroethylene	4800
	Tetrachloroethylene	4800.
	Toluene	1300.
	Ehtyl benzene	230.

Table 3. Detection Limits for PCB/Pesticides Analysis

Parameter	Detection Limit (water) ug/l	Detection Limit (oil) ug/kg
$\alpha$ BHC	.05	78
$\beta$ BHC	.05	78
$\gamma$ BHC	.05	78
$\delta$ BHC (Lindane)	.05	78
Heptachlor	.05	78
Aldrin	.05	78
Heptachlor Epoxide	.05	78
Endosulfan I	.05	78
Dieldrin	.10	160
4,4'-DDE	.10	160
Endrin	.10	160
Endosulfan II	.10	160
4,4'-DDD	.10	160
Endosulfan Sulfate	.10	160
4,4'-DDT	.10	160
Methoxychlor	.50	780
Endrin Ketone	.10	160
Chlordane	.50	780
Toxaphene	1.0	1600
Aroclor 1016	.50	780
Aroclor 1221	.50	780
Aroclor 1232	.50	780
Aroclor 1242	.5	780
Aroclor 1248	.5	780
Aroclor 1254	1.0	1600
Aroclor 1260	1.0	1600



Table 4. Results of PCB/Pesticides Analysis

Sample No.	Parameter	Concentration
<u>Water</u>		(reported as ug/l)
7332	None Detected	---
7333	None Detected	---
7334	Aroclor 1242 Aroclor 1260	130. 74
7335	None Detected	---
7341	None Detected	---
7342	None Detected	---
7344	None Detected	---
7346	None Detected	---
7353	None Detected	---
<u>Oil</u>		(reported as ug/g)
7334	Aroclor 1242 Aroclor 1260	36.0 17.0

Table 5. Detection Limits for Base Neutral/Acid Extractables Analysis

Parameter	Detection Limit (water) ug/l	Detection Limit (oil) ug/kg
N-nitrosodimethylamine	11	120
Phenol	10	110
bis(2-chloroethyl) ether	10	110
2-Chlorophenol	10	110
1,3-Dichlorobenzene	10	110
1,4-Dichlorobenzene	10	110
1,2-Dichlorobenzene	10	110
bis(2-Chloroisopropyl) ether	10	110
N-nitroso-di-n-propylamine	10	110
Hexachloroethane	10	110
Nitrobenzene	10	110
Isophorone	10	110
2-Nitrophenol	10	110
2,4-Dimethylphenol	10	150
bis(2-Chloroethoxy) methane	10	110
2,4-Dichlorophenol	10	110
1,2,4-Trichlorobenzene	10	110
Naphthalene	10	150
Hexachlorobutadiene	10	110
2,4,6-Trichlorophenol	10	110
2-Chloronaphthalene	10	110
Dimethyl phthalate	10	110
Acenaphthylene	10	110
Acenaphthene	10	110
2,4-Dinitrophenol	50	560
4-Nitrophenol	50	560
2,4-Dinitrotoluene	10	110
2,6-Dinitrotoluene	10	110
Diethyl phthalate	10	110
4-Chlorophenyl-phenylether	10	110
Fluorene	10	110
4,6-Dinitro-2-methylphenol	50	560
N-Nitrosodiphenylamine	10	110
4-Bromophenyl-phenylether	10	110
Hexachlorobenzene	10	110
Pentachlorophenol	50	560
Phenanthrene	10	110
Anthracene	10	110
Di-n-butyl phthalate	10	110
Fluoranthene	10	110
Benzidene	160	1800
Pyrene	10	110
Butylbenzyl phthalate	10	110
3,3'-Dichlorobenzidene	28	310

Table 5. Detection Limits for Base Neutral/Acid Extractables  
Analysis (Cont'd)

Parameter	Detection Limit (water) ug/l	Detection Limit (oil) ug/kg
Benzo(a)anthracene	10	110.
bis(2-ethylhexyl)phthalate	10	110
Chrysene	10	110.
Di-n-octylphthalate	10	110.
Benzo(b)fluoranthene	11	120.
Benzo(k)fluoranthene	10	110.
Benzo(a)pyrene	10	110.
Indeno(1,2,3-cd)pyrene	13	150.
Dibenzo(a,h)anthracene	16	180.
Benzo(g,h,i)perylene	17	190

Table 6. Results for Base Neutral/Acid Extractables Analysis

Sample No.	Parameter	Concentration
<u>Waters</u>		reported as ug/l
7332	Diethylphthalate*,** bis(2-ethylhexyl)phthalate	<10. 78.
7333	Diethylphthalate*,** Di-n-butylphthalate*,**	<10. <10.
7334	Phenol 2,4-Dimethylphenol Naphthalene** 4-Chloro-3-methylphenol** bis(2-ethyl hexyl)phthalate	1900. 4900. 150. 160. 180.
7335	None Detected	--
7341	Diethylphthalate*,** bis(2-ethylhexyl)phthalate Di-n-octylphthalate**	<10. 22. <10
7342	Diethylphthalate	<10
7344	Diethylphthalate*,** bis(2-ethylhexyl)phthalate	<10 <10
7345	Di-n-butylphthalate** bis(2-ethylhexyl)phthalate	<10 72.
7346	Diethylphthalate*,**	<10
7353	Phenol** Fluorene** Butylbenzylphthalate bis(2-ethylhexyl)phthalate Di-n-octyl phthalate	<10 <10 12. <10 <10

\* Compound was also detected in the method blank.

\*\* Value is below the limit of quantification.

Table 6. Results for Base Neutral/Acid Extractables Analysis (Cont'd)

Sample No.	Parameter	Concentration
<u>011</u>		reported as ug/g
7334	Naphthalene	150
	2,4-Dimethylphenol	150
	Hexachlorobutadiene**	20
	Fluorene**	24
	Phenanthrene**	92
	Anthracene**	11
	Fluoranthene**	18
	Pyrene**	18
	Butylbenzylphthalate**	27
	Bis(2-ethyl hexyl)phthalate	410

\*Compound was also found in the method blank.

\*\*Value is approximate due to its proximity to the detection limit.

Table 7. Detection Limits for Metals Analysis  
(Concentration reported as mg/l)

Parameter	Total Concentration	Dissolved Concentration
Arsenic	.001	NA
Aluminum	.10	.20
Barium	.03	NA
Beryllium	.003	NA
Boron	2.0	NA
Cadmium	.003	NA
Chromium	.005	NA
Copper	.005	NA
Iron	.005	.01
Lead	.02	NA
Manganese	.005	.01
Nickel	.01	NA
Selenium	.002	NA
Vanadium	.10	NA
Zinc	.005	NA

NA denotes not analyzed

Table 8. Results of Total Metals Analysis - Waters  
Concentrations reported in mg/l

Parameter	Sample No.									
	7346 (Blank)	7332	7333	7334	7335	7353	7341	7342	7344	7345
Arsenic	ND	.003	ND	.14	ND	.012	.008	.001	ND	ND
Aluminum	ND	7.8	.10	.20	.10	6.5	4.1	.40	.20	.20
Barium	.060	.11	ND	.44	ND	.10	.090	ND	ND	ND
Beryllium	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Boron	3.0	ND	ND	ND	ND	ND	ND	ND	ND	ND
Cadmium	.009	.009	.007	.026	.006	.008	.005	.005	.006	.006
Chromium	ND	.019	ND	.005	ND	.016	.030	ND	ND	ND
Copper	.010	.032	.011	.016	.010	.033	.021	.011	.010	.007
Iron	.30	7.4	.84	38.	.30	9.3	20.	1.2	.18	.35
Lead	.12	.10	.080	.080	.060	.090	.080	.060	.080	.060
Manganese	.017	1.8	1.7	31.	.019	1.4	1.9	.74	.065	.065
Nickel	.020	.080	.050	.11	.030	.050	.080	.020	.030	.030
Selenium	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Vanadium	.2	ND	ND	ND	ND	ND	ND	ND	ND	ND
Zinc	.018	.091	.025	.043	.017	6.5	4.1	.40	.20	.20

ND denotes not detected

Table 8. Results of Metals Analysis - 011

(Concentrations reported as ug/g)

Sample No. 7334

Parameter	Concentration	Detection Limit
Aluminum	1000	50.
Arsenic	8.4	.50
Barium	54.	15.
Beryllium	ND	2.0
Boron	ND	750
Cadmium	4.0	2.0
Chromium	30.	3.0
Copper	7	3.0
Iron	711	3.0
Lead	23.	10.
Manganese	78.	3.0
Nickel	5.5	5.0
Selenium	ND	1.0
Vanadium	ND	50.
Zinc	44.	3.0

ND denotes not detected



Table 9. Results of Dissolved Metals Analysis

Concentrations in mg/l

Parameter	Sample No.								
	7346 (Blank)	7332	7333	7335	7353	7341	7342	7344	7345
Aluminum	ND	.30	ND	ND	ND	ND	ND	.30	ND
Manganese	.020	.050	1.8	.030	1.3	1.8	.12	.080	.070
Iron	.20	.34	.58	.17	1.0	1.7	.27	.38	.22

ND denotes not detected

Table 10. Results of Chlorides and Bromides Analysis  
(Concentrations in mg/l)

Sample No.	Chlorides	Bromides
Method Blank	ND	ND
7332	4.0	ND
7333	11.	ND
7334	310	11.
7335	6.4	ND
7341	22.	ND
7342	64	ND
7344	11.	ND
7345	11.	ND
7346	ND	ND
7353	10.	ND

ND denotes not detected. Detection limits were .5 mg/l for chlorides and 1.0 ug/l for bromides.

Table 11. Matching of Oil Fingerprinting Analysis to Diesel Fuel No. 2

Sample No.	Results
Method Blank	Negative
7332	Negative
7333	Negative
7334 (water)	Positive
7334 (oil)	Positive
7335	Negative
7341	Negative
7342	Negative
7344	Negative
7345	Negative
7346	Negative
7353	Negative

## QA/QC PROCEDURES

Volatile Organics Analysis: Three surrogate standards were spiked into each sample prior to analysis to ensure the efficiency of the purge and trap unit. Recoveries for these standards are presented in QA/QC Table 12. The recoveries for water ranged from 85% - 106% and for the oil sample from 84% - 106%.

One water sample (7331) and the oil sample (7334) were analyzed in duplicate to determine sample homogeneity. The results are presented in QA/QC Table 13. Methylene chloride was detected in the water sample but not in the duplicate. Methylene chloride was also detected in the method blank. This is a common laboratory solvent and is often seen as contamination during sample analysis. Its presence at detection limit levels in one sample and not in a duplicate can be disregarded since the background in a laboratory can vary. The relative percent differences for the oil sample ranged from 0 to 16 indicating good sample homogeneity.

A water sample, 7346, and the oil sample, 7334, were spiked with five volatile organics to determine any matrix interferences that may be present. These results are listed in QA/QC Table 14. Recoveries ranged from 86% - 106% for the water and from 90% - 120% for the oil and were within the QA/QC limits for this laboratory.

PCB/Pesticides Analysis: All water samples and standards were spiked with dibutyl chlorodate to assure proper instrument performance. These surrogate standard results are presented in QA/QC Table 15. The recovery for two samples, 7332, its duplicate, and 7334, could not be calculated due to a contamination peak that coeluted with dibutyl chlorodate. All other recoveries were within the QA/QC limits of the laboratory. CLP protocols do not require surrogate spiking for oil matrices.

One water sample, 7332, was analyzed in duplicate to determine sample homogeneity. PCBs and pesticides were undetected in both. The oil sample, 7334, was also analyzed in duplicate. Results for the oil sample are presented in QA/QC Table 16. The relative percent difference for Aroclor 1242 and Aroclor 1260 were 2.8 and 6.1, respectively.

One water sample was spiked with six pesticides to determine the presence of matrix interferences. Results are presented in QA/QC Table 17. All compounds except 4,4'-DDT were within the laboratory's QA/QC limits.

Base Neutral/Acid Extractables Analysis: All water samples and method blanks were spiked with three surrogate standards to ensure extraction efficiency. The results are presented in QA/QC Table 18. Surrogate spiking was not required for the oil sample since the sample preparation does not include an extraction process. Recoveries for water sample 7334 could not be determined due to high levels of phenol and 2,4-dimethyl phenol which required dilution of the extract prior to analysis. All other surrogate standard recoveries were within the QA/QC limits of the laboratory.

The results of duplicate analyses of water sample 7332 and oil sample 7334 are presented in QA/QC Table 19. Relative percent difference for diethylphthalate was not calculated because its concentration was less than the method limit of quantification. Bis(2-ethylhexyl)phthalate was found at 78 ug/l in the sample but undetected in the duplicate. Reproducibility for three compounds above the limit of quantification found in the oil sample ranged from 0-6.4 relative percent difference.

Results of the matrix spike analysis for water sample 7346 and the oil sample are presented in QA/QC Table 20. All recoveries were within the QA/QC limits of the laboratory.

Metals Analysis: The results of duplicate metals analyses are presented in QA/QC Table 21. Relative percent differences for the water ranged from 0-26. For the oil sample, relative percent difference ranged from 0 to 25.

One water sample was spiked with fifteen metals to determine any matrix interferences. Results are presented in QA/QC Table 22. Recoveries ranged from 93-134%. The oil sample was also spiked with fifteen metals as shown in QA/QC Table 22. Recoveries ranged from 61 to 112% for all compounds except selenium. Recovery for selenium was 3%. Historical data for selenium in oil indicates low recoveries are usual.

Chlorides/Bromides Analysis: Duplicate chlorides and bromides results are presented in QA/QC Table 23. Water sample 7341 was analyzed in duplicate and showed no relative percent difference for chlorides. Bromides were undetected in the sample and duplicate.

Matrix spike results for chlorides and bromides are presented in QA/QC Table 24. One sample, 7341, was spiked with both analytes and two other water samples, 7344 and 7335, were spiked with chlorides and bromides, respectively. Recoveries ranged from 96-110%.

Oil Fingerprinting: Two deionized water samples were spiked with 5 ul of pure diesel fuel oil to determine extraction efficiency. Quantification of the oil was performed by selecting the twelve highest peak area responses and comparing to a diesel fuel standard. Recoveries were 110% and 114%.

QA/QC Table 12. Surrogate Standard Recoveries for  
Volatile Organic Analysis

Sample No.	% Recovery		
	Toluene-D8	4-Bromofluorobenzene	1,2-Dichloroethane-D4
<u>Water</u>			
7331	103.	106.	99.
7332	101.	98.	102.
7332 (Duplicate)	101.	100.	102.
7333	96.	100.	97.
7334 (water)	94.	100.	99.
7335	101.	98.	97.
7341	91.	106.	101.
7342	98.	100.	93.
7344	105.	101.	93.
7345	100.	102.	92.
7346	102.	99.	100.
7353	99.	102.	85.
7346 MS	99.	99.	100.
Method Blank I	98.	101.	101.
Method Blank II	100.	104.	90.
Method Blank III	101.	103.	95.
<u>011</u>			
7334	87.	98.	95.
7334 MS	97.	104.	87.
7334 (Duplicate)	102.	106.	84.
Method Blank	93.	107.	86.

QA/QC Table 13. Results of Duplicate Volatile Organics Analysis

Parameter	Run 1	Run 2	RPD
Sample No. 7331 (water) - Concentrations reported as ug/l			
Methylene chloride	<5	ND	--
Sample No. 7334 (oil) - Concentrations reported as ug/g			
Vinyl chloride	290.	300.	3.4
Methylene chloride	670.	570.	16.
1,1-Dichloroethane	130.	130.	0.
Trans-1,2-dichloroethylene	4200.	4000.	4.9
1,1,1-Trichloroethane	1700.	1700.	0
Trichloroethylene	4800.	4900.	2.1
Tetrachloroethylene	4800.	5600.	15.
Toluene	1300.	1400.	7.4
Ethyl benzene	230.	270.	16.

RPD denotes relative percent difference

QA/QC Table 14. Results of Matrix Spike Volatile Organics Analysis

Parameter	Spike Conc.	Sample Conc.	Recovered Conc.	% Recovery
Sample No. 7346 (water) - concentrations reported as ug/l				
1,1-Dichloroethane	50.	ND	43.	86.
Trichloroethylene	50.	ND	52.	104.
Chlorobenzene	50.	ND	51.	102.
Toluene	50.	.6	50.	99.
Benzene	50.	ND	53.	106.
Sample 7334 (oil) - concentrations reported as ug/g				
1,1-Dichloroethane	3100	ND	2800	90.
Trichloroethylene	3100	4800	8500	120.
Chlorobenzene	3100	ND	3300	106.
Toluene	3100	1300	4500	103.
Benzene	3100	ND	2900	94.



QA/QC Table 15. Surrogate Standard Recoveries for  
PCB/Pesticides Analysis

Sample No.	Parameter	% Recovery
7332	Dibutyl Chlorendate	*
7332 Duplicate	Dibutyl Chlorendate	*
7333	Dibutyl Chlorendate	97.0
7334	Dibutyl Chlorendate	*
7335	Dibutyl Chlorendate	88.0
7341	Dibutyl Chlorendate	53.0
7342	Dibutyl Chlorendate	86.0
7344	Dibutyl Chlorendate	91.0
7345	Dibutyl Chlorendate	90.0
7346	Dibutyl Chlorendate	102.0
7346 MS	Dibutyl Chlorendate	86.0
7353	Dibutyl Chlorendate	101.0
Method Blank	Dibutyl Chlorendate	93.0

\*Surrogate standard recovery could not be calculated due to coelution of dibutyl chlorendate with interference peak.

QA/QC Table 16. Results of Duplicate PCB/Pesticides Analysis  
Concentrations in ug/g

Parameter	Run 1	Run 2	RPD
Sample 7334 (011)			
Aroclor 1242	36.	35.	2.8
Aroclor 1260	17.	16.	1.06

RPD denotes relative percent difference

QA/QC Table 17. Results of Matrix Spike PCB/Pesticides Analysis  
Concentrations reported as ug/l

Parameter	Spike Conc.	Sample Conc.	Recovered Conc.	% Recovery
Sample No. 7332 (water)				
Lindane	.20	ND	.19	95.
Heptachlor	.20	ND	.14	70.
Aldrin	.20	ND	.12	60.
Dieldrin	.50	ND	.43	86.
Endrin	.50	ND	.44	88.
4,4'-DDT	.50	ND	.66	130.

QA/QC Table 18. Surrogate Standard Recoveries for  
Base Neutral/Acid Extractables

Sample No.	% Recovery		
	2-Fluorophenol	2-Fluorobiphenyl	2,4,6-Tribromophenol
7332	50.	63.	48.
7332 (duplicate)	51.	59.	50.
7333	58.	66.	81.
7334 (water)	*	*	*
7334 (oil)	not required	not required	not required
7335	57.	80.	65.
7341	53.	76.	71.
7342	55.	69.	68.
7344	52.	78.	58.
7345	47.	87.	62.
7346	62.	57.	96.
7346 MS	60.	65.	76.
7353	56.	66.	58.
Method Blank	59.	70.	82.

\*Surrogate standards were diluted out due to high concentrations of phenol and 2,4-dimethylphenol in sample.

QA/QC Table 19. Results of Duplicate Base Neutral/Acid Extractables Analysis

Parameter	Run 1	Run 2	RPD
Sample 7332 (water) - concentrations reported as ug/l			
Diethylphthalate	<10	<10	--
Bis(2-ethylhexyl)phthalate	78	ND	--
Sample 7334 (oil) - concentrations reported as ug/g			
2,4-Dimethylphenol	150.	160.	6.4
Naphthalene	150.	150.	0
Hexachlorobutadiene	<110.	<110.	--
Fluorene	<110.	<110.	--
Phenanthrene	<110.	<110.	--
Anthracene	<110.	<110.	--
Fluoranthene	<110.	ND	--
Pyrene	<110.	<110.	--
Butylbenzyl phthalate	<110.	<110.	--
Bis(2-ethylhexyl)phthalate	410.	400.	2.5

QA/QC Table 20. Results of Matrix Spike Base Neutral/Acid  
Extractables Analysis

Concentrations reported as ug/l

Sample 7346 water:

Parameter	Spike Conc.	Sample Conc.	Recovered Conc.	% Recovery
1,2,4-Trichlorobenzene	130	ND	69.	53.
Acenaphthene	130	ND	89.	68.
2,4-Dinitrotoluene	130	ND	120	92.
Pyrene	130	ND	150	115
N-nitroso-di-n-propylamine	130	ND	89.	68.
1,4-Dichlorobenzene	130	ND	66.	51.
Pentachlorophenol	270	ND	240	89
Phenol	270	ND	120	44.
2-Chlorophenol	270	ND	200	73.
4-Chloro-3-methylphenol	270	ND	230	85.
4-Nitrophenol	270	ND	100	37.

## QA/QC Table 21. Results of Duplicate Metals Analysis

Concentrations reported as mg/l

Parameter	Run 1	Run 2	RPD
<u>Total Metals:</u> Sample No. 7335 (water)			
Arsenic	ND	ND	--
Aluminum	.1	.1	0
Barium	ND	ND	--
Beryllium	ND	ND	--
Boron	ND	ND	--
Cadmium	.006	.006	0
Chromium	ND	ND	--
Copper	.010	.008	22.
Iron	.30	.39	26.
Lead	.06	.06	0
Manganese	.019	.017	11.
Nickel	.03	.03	0
Selenium	ND	ND	--
Vanadium	ND	ND	--
Zinc	.017	.018	5.7
<u>Dissolved Metals:</u> Sample 7341 (water)			
Manganese	1.8	1.8	0
Iron	1.7	1.7	0
Aluminum	ND	ND	--
<u>Total Metals:</u> Sample 7334 (oil) - concentrations in ug/g			
Aluminum	8.4	8.2	2.4
Barium	54.	47.	4.7
Beryllium	ND	ND	--
Boron	ND	ND	--
Cadmium	4.0	4.0	0
Chromium	30.	31.	3.3
Copper	7.0	9.0	25.
Iron	711	710	.14
Lead	23.	22.	4.4
Manganese	78	94	19.
Nickel	5.5	5.4	1.8
Selenium	ND	ND	--
Vanadium	ND	ND	--
Zinc	44.	49.	11

QA/QC Table 22. Results of Matrix Spike for Metals Analysis

Parameter	% Recovery
<u>Sample 7335 - Water</u>	
Arsenic	95.
Aluminum	106
Barium	126
Beryllium	101
Boron	93.
Cadmium	95.
Chromium	94.
Copper	93.
Iron	93.
Lead	95.
Manganese	134
Nickel	113
Selenium	95.
Vanadium	126
Zinc	123
<u>Sample 7334 - 011</u>	
Arsenic	61.
Aluminum	88.
Barium	112
Beryllium	66.
Boron	76.
Cadmium	94.
Chromium	107
Copper	100
Iron	78.
Lead	107
Manganese	100
Nickel	92.
Selenium	3.0
Vanadium	107
Zinc	89.

QA/QC Table 23. Results of Duplicate Chlorides and Bromides Analysis  
Concentrations in mg/l

Sample No.	Chlorides		RPD	Bromides		RPD
	Run 1	Run 2		Run 1	Run 2	
7341	22.	22.	0	ND	ND	--

QA/QC Table 24. Results of Matrix Spike  
for Chlorides and Bromides Analysis

Sample No.	% Recovery Chloride	% Recovery Bromides
7341	98.	110
7344	96.	---
7335	--	98.



**POOR LEGIBILITY**

**PORTIONS OF THIS DOCUMENT  
MAY BE UNREADABLE, DUE TO  
THE QUALITY OF THE  
ORIGINAL**

## CHAIN OF CUSTODY RECORD

**SAMPLER(S) SIGNATURE**

**PROJECT NO.**

[illegible]

RELINQUISHED BY: NAME

DATE/TIME: 2/2/84

**REPORTED BY NAME**

RELINQUISHED BY: NAME

DATE/TIME: 11/11/74 11:00 AM

RECOVERED BY NAME

ENDORSED BY: NAME

DATE/TIME: 01/22/2006 11:00:00 AM

**RECEIVED**

**AUTHORIZATION FOR DISPOSAL**

**DATE/TIME:** \_\_\_\_\_

**DEATHS**

280526

**ENVIRESPONSE, INC.**

## CHAIN-OF-CUSTODY RECORD

PROJECT NAME

GRASSNEKE

## **SAFETY INFORMATION**

**PROJECT NO.**

[illegible]

RELINQUISHED BY: NAME

RELINQUISHED BY: NAME

RELINQUISHED BY: NAME

**AUTHORIZATION FOR DISPOSAL**

8-0527



# ENVIRESPONSE, INC.

## CHAIN OF CUSTODY RECORD

PROJECT NAME

Snad Oil Site

SAMPLER(S) SIGNATURE

[Signature]

PROJECT NO.

370 67 140499

SAMPLE IDENTIFICATION	SAMPLING LOCATION	DATE SAMPLED	SAMPLE TYPE			COMB	GRAB	VOLUME TO BE COLLECTED	NO. OF CONTAINERS	TIME COLLECTION BEGAN	INITIAL	TIME COLLECTION COMPLETED	INITIAL	COMMENTS
			SOLID	AIR	OIL									
05714	B20	3/26/87	✓				✓	2x1L	2	0900	J	0915	J	PP, PESTICIDE/PCB
05714	B20	3/26/87	✓				✓	3x1/2L	3	0900	J	0915	J	VOA
05713	B27	3/25/87	✓				✓	2x1L	2	1430	J	1439	J	PP, PESTICIDE/PCB
05713	B27	3/25/87	✓				✓	3x1/2L	3	1430	J	1439	J	VOA
05712	KROFT SPRING	3/24/87	✓				✓	2x1L	2	1045	J	1100	J	PP, PESTICIDE/PCB
05712	KROFT SPRING	3/24/87	✓				✓	3x1/2L	3	1045	J	1100	J	VOA
05715	B9	3/26/87	✓				✓	2x1L	2	1100	J	1115	J	PP, PESTICIDES/PCB
05715	B9	3/26/87	✓				✓	3x1/2L	3	1100	J	1115	J	VOA

RELINQUISHED BY: NAME

[Signature]

DATE/TIME

3/24/87 1415

RECEIVED BY: NAME

RELINQUISHED BY: NAME

DATE/TIME

RECEIVED BY: NAME

RELINQUISHED BY: NAME

DATE/TIME

RECEIVED BY: NAME

AUTHORIZATION FOR DISPOSAL

DATE/TIME

DISPOSED BY:

DATE/TIME



THE

**新到各書**

# PROJECT NO.

[illegible]

**THE**

100

100-443887-100

**PHOTO**





# FIELD DATA SHEET

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

Location: GRASSMERE WELL#3

Collectors: CB PM

Lab Number (Consec.#s)  
No 7353

Date Collected  
Mo 019 Day 11 Yr 81

Time (24 hr)  
1530

SOIL		LAND	VEGETATION		GROUNDWATER	
Device Auger Core Split Spoon Cylinder Cup Spade	Soil Type Rock Gravel Sand Clay Silt Muck Loam Peat	Upland-Dry Lowland-Dry Floodplain Wetland Gully  Slope $> 15^\circ$ $< 15^\circ$	Old Field Wooded Farmland	Residential Industrial Commercial  Herbaceous _____ % Shrubs _____ % Trees _____ %  DBH <span style="border: 1px solid black; padding: 2px;">  </span> In.	Water Table Depth <span style="border: 1px solid black; padding: 2px;">  </span> Ft.	Sample Depth <span style="border: 1px solid black; padding: 2px;">  </span> Ft.
Depth <span style="border: 1px solid black; padding: 2px;">  </span> Ft. <span style="border: 1px solid black; padding: 2px;">  </span> In.	Color: _____			Color: _____ Odor: _____ Oil: _____ Device: <u>BAILER</u>		

SURFACE WATER				SAMPLE PREPARATION		
Color: _____ pH: _____	Temp _____	Device Kemmerer Petersen Surber Manual Net Seine Trawl Bucket	Surface Clean Oil Garbage Trash Bubbles Dead Fish Sewage Ind. Waste Float. Solids	Bottom % Ooze Sand Gravel Clay Rubble Rock Shell Organic	Container Glass Jar Plastic Jar Metal Acetate Core Paper Cap Teflon Cap Foil Cap  Storage Wet Ice Ambient Dry Ice	Cleaning Procedure Low → High Concentration Detergent Wash Water Rinse Acetone Rinse Hexane Rinse Other Solvent Rinse Specify: _____
STREAM Width <span style="border: 1px solid black; padding: 2px;">  </span> Ft.	Depth <span style="border: 1px solid black; padding: 2px;">  </span> Ft. or In.	Velocity <span style="border: 1px solid black; padding: 2px;">  </span> Ft/Sec	FLOW DIRECTION _____ Pools _____ % Riffles _____ %			

## TRANSECT INFORMATION

Letter	Station #

Compass Direction \_\_\_\_\_

Distance Between Stations

   to    is    Ft.

Remarks and Site Description





# FIELD DATA SHEET

2 8 0533

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

BLANK

Location: BLANK

Collectors: PM CB

Lab Number (Consec.#'s)  
NO 7346

Date Collected  
Mo 12 Day 11 Yr 86

Time (24 hr)  
0900

## SOIL

## LAND

## VEGETATION

## GROUNDWATER

### Device

Auger  
Core  
Split Spoon  
Cylinder Cup  
Spade

### Soil Type

Rock  
Gravel  
Sand  
Clay  
Silt  
Muck  
Loam  
Peat

### Depth

     Ft.  
or  
     In.

Color:     

Upland-Dry  
Lowland-Dry  
Floodplain  
Wetland  
Gully

Slope  $> 15^\circ$   
 $< 15^\circ$

Old Field  
Wooded  
Farmland  
Residential  
Industrial  
Commercial

Herbaceous      %  
Shrubs      %  
Trees      %

DBH      In.

Water Table Depth      Ft.

Sample Depth      Ft.

Color:     

Odor:     

Oil:     

Device:     

## SURFACE WATER

## SAMPLE PREPARATION

Color:      Temp       
Odor:      pH     

STREAM Width      Ft.

Depth      Ft.  
or  
In.

Velocity      Ft/Sec

### FLOW DIRECTION

Pools      % Riffles      %

### Device

Kemmerer  
Petersen  
Surber  
Manual  
Net  
Seine  
Trawl  
Bucket

### Surface

Clean  
Oil  
Garbage  
Trash  
Bubbles  
Dead Fish  
Sewage  
Ind. Waste  
Float. Solids

### Bottom %

Ooze  
Sand  
Gravel  
Clay  
Rubble  
Rock  
Shell  
Organic

### Container

Glass Jar  
Plastic Jar  
Metal  
Acetate Core  
Paper Cap  
Teflon Cap  
Foil Cap

### Storage

Wet Ice  
Ambient  
Dry Ice

### Cleaning Procedure

Low  $\rightarrow$  High Concentration  
Detergent Wash  
Water Rinse  
Acetone Rinse  
Hexane Rinse  
Other Solvent Rinse  
Specify:     

## TRANSECT INFORMATION

### Compass Direction

### Distance Between Stations

Letter	Station #
<u>    </u>	<u>    </u>

     to      is      Ft.

Remarks and Site Description

FIELD BLANK



## FIELD DATA SHEET

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

Location: Conduits from overpass. Runoff Sediment  
Collectors: G.P., P.L.L., C.W.

Lab Number (Consec.#'s)

NO 7345

Date Collected

Mo Day Yr  
019 112 816

Time (24 hr)

0046

SOIL		LAND	VEGETATION		GROUNDWATER	
Device	Soil Type	Upland-Dry Lowland-Dry Floodplain Wetland Gully	Old Field Wooded <u>Farmland</u>	Residential Industrial Commercial	Water Table Depth	
Auger	Rock					
Core	Gravel					
Split Spoon	Sand					
Cylinder Cup	Clay					
Spade	Silt					
Depth	Muck	Slope > 15° < 15°	Herbaceous <u>50</u> %		Sample Depth	
	Loam		Shrubs <u>30</u> %			
	Peat		Trees <u>20</u> %			
	Color: _____		DBH		Color: _____	
					Odor: _____	
					Oil: _____	
					Device: _____	

## SURFACE WATER

## SAMPLE PREPARATION

SURFACE WATER		Device		Surface	Bottom %	Container	Cleaning Procedure
Color: <u>clear</u>	Temp _____	Kemmerer	Clean	Ooze	Glass Jar <u>5</u>	Low → High Concentration	
pH: <u>none</u>	pH _____	Petersen	Oil	Sand	Plastic Jar <u>9</u>	Detergent Wash	
STREAM Width		Surber	Garbage	Gravel	Metal	Water Rinse	
Depth		Manual	Trash	Clay	Acetate Core	Acetone Rinse	
Velocity		Net	Bubbles	Rubble	Paper Cap	Hexane Rinse	
		Sieve	Dead Fish	Rock	Teflon Cap	Other Solvent Rinse	
		Trawl	Sewage	Shell	Foil Cap	Specify: _____	
		Bucket	Ind. Waste	Organic			
FLOW DIRECTION _____			Float. Solids				
Pools _____ % Riffles _____ %							

## TRANSECT INFORMATION

Compass Direction

Distance Between Stations

Letter	Station #

\_\_\_\_\_ to \_\_\_\_\_ is \_\_\_\_\_ Ft

Remarks and Site Description

our point  
Gravel  
Sediment  
Sump Area  
No low water

Duplicate



# FIELD DATA SHEET

2 8 0535

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

Location: Sand Site

Collectors: PLK, GP, CW

Lab Number (Consec.#'s)  
NO 7344

Date Collected  
Mo 019 Day 112 Yr 816

Time (24 hr)  
1049

SOIL		LAND	VEGETATION		GROUNDWATER	
Device	Soil Type	Upland-Dry Lowland-Dry Floodplain Wetland Gully	Old Field Wooded Farmland	Residential Industrial Commercial	Water Table Depth	<input type="text"/> <input type="text"/> <input type="text"/> <input type="text"/> Ft
Auger Core Split Spoon Cylinder Cup Spade	Rock Gravel Sand Clay Silt Muck Loam Peat Color: _____	Slope > 15° < 15°	Herbaceous _____ % Shrubs _____ % Trees _____ % DBH <input type="text"/> <input type="text"/> <input type="text"/> In.		Sample Depth	<input type="text"/> <input type="text"/> <input type="text"/> <input type="text"/> Ft
Depth <input type="text"/> <input type="text"/> <input type="text"/> <input type="text"/> Ft. or In.					Color: _____ Odor: _____ Oil: _____ Device: _____	

SURFACE WATER				SAMPLE PREPARATION		
Color: <u>Clear</u> Odor: _____ Temp _____ pH _____ TEAM Width <input type="text"/> <input type="text"/> <input type="text"/> <input type="text"/> Ft. Depth <input type="text"/> <input type="text"/> <input type="text"/> <input type="text"/> Ft. or In. Velocity <input type="text"/> <input type="text"/> <input type="text"/> <input type="text"/> Ft/Sec FLOW DIRECTION _____ Pools _____ % Riffles _____ %	Device Kemmerer Petersen Surber Manual Net Seine Trawl Bucket	Surface Clean Oil Garbage Trash Bubbles Dead Fish Sewage Ind. Waste Float. Solids	Bottom % Ooze Sand Gravel Clay Rubble Rock Shell Organic	Container Glass Jar _____ Plastic Jar _____ Metal _____ Acetate Core Paper Cap Teflon Cap Foil Cap Storage Wet Ice Ambient Dry Ice	Cleaning Procedure Low → High Concentration Detergent Wash Water Rinse Acetone Rinse Hexane Rinse Other Solvent Rinse Specify: _____	

## TRANSECT INFORMATION


Letter	Station #
<input type="text"/>	<input type="text"/>

Compass Direction \_\_\_\_\_

Distance Between Stations

to  is  Ft

Remarks and Site Description





# FIELD DATA SHEET

2 8 0536

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

Location: SAD WASTE OIL / CSX LAGOON

Collectors: WALSH/PRINCE

Lab Number (Consec.#'s)  
NO 7342

Date Collected  
Mo 09 Day 12 Yr 86

Time (24 hr)  
0921

SOIL		LAND	VEGETATION		GROUNDWATER	
Device Auger Core Split Spoon Cylinder Cup Spade Depth <div><div></div><div></div><div></div><div></div></div> Ft. or In.	Soil Type Rock Gravel Sand Clay Silt Muck Loam Peat Color: _____	Upland-Dry Lowland-Dry Floodplain Wetland Gully Slope > 15° < 15°	Old Field Wooded Farmland Herbaceous _____ % Shrubs _____ % Trees _____ % DBH <div><div></div><div></div><div></div></div> In.	Residential Industrial Commercial	Water Table Depth <div><div></div><div></div><div></div><div></div></div> Ft. Sample Depth <div><div></div><div></div><div></div><div></div></div> Ft. Color: _____ Odor: _____ Oil: _____ Device: _____	

SURFACE WATER				SAMPLE PREPARATION		
Color: _____ Odor: _____ Temp _____ pH _____ Stream Width <div><div></div><div></div><div></div><div></div></div> Ft. Depth <div><div></div><div></div><div></div><div></div></div> Ft. or In. Velocity <div><div></div><div></div><div></div><div></div></div> Ft/Sec FLOW DIRECTION _____ Pools _____ % Riffles _____ %	Device Kemmerer Petersen Surber Manual Net Seine Trawl Bucket	Surface Clean Oil Garbage Trash Bubbles Dead Fish Sewage Ind. Waste Float. Solids	Bottom % Ooze Sand Gravel Clay Rubble Rock Shell Organic	Container Glass Jar Plastic Jar Metal Acetate Core Paper Cap Teflon Cap Foil Cap Storage Wet Ice Ambient Dry Ice	Cleaning Procedure Low → High Concentration Detergent Wash Water Rinse Acetone Rinse Hexane Rinse Other Solvent Rinse Specify: _____	

## TRANSECT INFORMATION

Letter	Station #

Compass Direction

Distance Between Stations

to  is  Ft

Remarks and Site Description

*sediment releases oil when disturbed*  
*some sediment on top of 6" of sand to add bubbles down*  
*LAGOON*  
*1*  
*Concrete Lagoon*  
*2*  
*1.3 million gal when full*  
*Normally Empty pebbles liner pipe through liner*  
*LAGOON SYSTEM*  
*Spring 80*  
*AFL separator*  
*Vert. tub coalescing separator*  
*11 pipes through lagoon bottom*  
*SAMPLE of water under oil layer*



## FIELD DATA SHEET

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

Location: SAAD Waste Oil - CSX Railroad

Collectors: \_\_\_\_\_

Lab Number (Consec.#'s)  
No 7341

Date Collected  
Mo 09 Day 12 Yr 86

Time (24 hr)  
0800

SOIL		LAND	VEGETATION		GROUNDWATER	
Device Auger Core Split Spoon Cylinder Cup Spade	Soil Type Rock Gravel Sand Clay Silt Muck Loam Peat Color: _____	Upland-Dry Lowland-Dry Floodplain Wetland Gully  Slope $> 15^\circ$ $< 15^\circ$	Old Field Wooded Farmland	Residential Industrial Commercial  Herbaceous _____ % Shrubs _____ % Trees _____ %  DBH <u>    </u> in.	Water Table Depth <u>    </u> Ft.	Sample Depth <u>    </u> Ft.
Depth <u>    </u> Ft. or In.					Color: _____ Odor: _____ Oil: _____ Device: _____	

SURFACE WATER			SAMPLE PREPARATION			
Color: _____ Odor: _____	Temp _____ pH _____	Device Kemmerer Petersen Surber Manual Net Seine Trawl Bucket	Surface Clean Oil Garbage Trash Bubbles Dead Fish Sewage Ind. Waste Float. Solids	Bottom % Ooze Sand Gravel Clay Rubble Rock Shell Organic	Container Glass Jar Plastic Jar Metal Acetate Core Paper Cap Teflon Cap Foil Cap  Storage Wet Ice Ambient Dry Ice	Cleaning Procedure Low $\rightarrow$ High Concentration Detergent Wash Water Rinse Acetone Rinse Hexane Rinse Other Solvent Rinse Specify: _____
Width <u>    </u> Ft.	Depth <u>    </u> Ft. or In.	Velocity <u>    </u> Ft/Sec				
FLOW DIRECTION _____ Pools _____ % Riffles _____ %						

## TRANSECT INFORMATION

Letter	Station #

Compass Direction \_\_\_\_\_

Distance Between Stations

     to      is      Ft.

Remarks and Site Description

F. + Well SSLN #1

Depth on 9/11/86 TOC - Bottom 51.6'  
TOC - WL 15.0'  
Grnd - TOC 1.7'



## FIELD DATA SHEET

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

Location: GRASSMERE NATURE PARK

Collectors: WALSH/PRINCE

Lab Number (Consec. #'s)

No 7335

Date Collected

Mo 09 Day 11 Yr 86

Time (24 hr)

1833

## SOIL

## LAND

## VEGETATION

## GROUNDWATER

## Device

## Soil Type

Auger  
Core  
Split Spoon  
Cylinder Cup  
Spade

Rock  
Gravel  
Sand  
Clay  
Silt  
Muck  
Loam  
Peat

Color: \_\_\_\_\_

## Depth

                    Ft.  
or  
In.

Upland-Dry  
Lowland-Dry  
Floodplain  
Wetland  
Gully

Slope  $> 15^\circ$   
 $< 15^\circ$

Old Field  
Wooded  
Farmland  
Residential  
Industrial  
Commercial

Herbaceous \_\_\_\_\_ %  
Shrubs \_\_\_\_\_ %  
Trees \_\_\_\_\_ %

DBH                In.

Water Table Depth                     Ft.

Sample Depth                     Ft.

Color: \_\_\_\_\_

Odor: \_\_\_\_\_

Oil: \_\_\_\_\_

Device: \_\_\_\_\_

## SURFACE WATER

## SAMPLE PREPARATION

Color: \_\_\_\_\_ Temp \_\_\_\_\_  
Odor: \_\_\_\_\_ pH \_\_\_\_\_

Stream Width                          Ft.

Depth                          Ft.  
or  
In.

Velocity                          Ft/Sec

FLOW DIRECTION \_\_\_\_\_

Pools \_\_\_\_\_ % Riffles \_\_\_\_\_ %

## Device

Kemmerer  
Peterson  
Surber  
Manual  
Net  
Seine  
Trawl  
Bucket

## Surface

Clean  
Oil  
Garbage  
Trash  
Bubbles  
Dead Fish  
Sewage  
Ind. Waste  
Float. Solids

## Bottom %

Ooze  
Sand  
Gravel  
Clay  
Rubble  
Rock  
Shell  
Organic

## Container

Glass Jar  
Plastic Jar  
Metal  
Acetate Core  
Paper Cap  
Teflon Cap  
Foil Cap

## Storage

Wet Ice  
Ambient  
Dry Ice

## Cleaning Procedure

Low—High Concentration  
Detergent Wash  
Water Rinse  
Acetone Rinse  
Hexane Rinse  
Other Solvent Rinse  
Specify: \_\_\_\_\_

## TRANSECT INFORMATION

Letter	Station #
<u>    </u>	<u>    </u> <u>    </u> <u>    </u>

Compass Direction \_\_\_\_\_

Distance Between Stations

               to                is                     Ft.

Remarks and Site Description

Spring 2 - S of entry road in springbox #2  
Brick box 1 1/2 ft high, pipe inside box  
flow  $\approx$  9 gal/min



# FIELD DATA SHEET

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

2 8 0539

Location: SAAD CR. WELL

Collectors: PK GP

Lab Number (Consec.#'s)  
NO 7334

Date Collected  
Mo 09 Day 11 Yr 81

Time (24 hr)  
        

SOIL		LAND	VEGETATION		GROUNDWATER	
Device Auger Core Split Spoon Cylinder Cup Spade	Soil Type Rock Gravel Sand Clay Silt Muck Loam Peat Color: <u>  </u>	Upland-Dry Lowland-Dry Floodplain Wetland Gully  Slope $> 15^\circ$ $< 15^\circ$	Old Field Wooded Farmland  Herbaceous <u>  </u> % Shrubs <u>  </u> % Trees <u>  </u> % DBH <u>  </u> <u>  </u> <u>  </u> In.	Residential Industrial Commercial	Water Table Depth <u>  </u> <u>  </u> <u>  </u> <u>  </u> Ft. Sample Depth <u>  </u> <u>  </u> <u>  </u> <u>  </u> Ft. Color: <u>  </u> Odor: <u>  </u> Oil: <u>  </u> Device: <u>BAILER</u>	

SURFACE WATER				SAMPLE PREPARATION		
Color: <u>  </u> Odor: <u>  </u> Temp <u>  </u> pH <u>  </u> REAM Width <u>  </u> <u>  </u> <u>  </u> <u>  </u> Ft. Depth <u>  </u> <u>  </u> <u>  </u> <u>  </u> Ft. or In. Velocity <u>  </u> <u>  </u> <u>  </u> <u>  </u> FV/Sec FLOW DIRECTION <u>  </u> Pools <u>  </u> % Riffles <u>  </u> %	Device Kemmerer Petersen Surber Manual Net Seine Trawl Bucket	Surface Clean Oil Garbage Trash Bubbles Dead Fish Sewage Ind. Waste Float. Solids	Bottom % Ooze Sand Gravel Clay Rubble Rock Shell Organic	Container Glass Jar Plastic Jar Metal Acetate Core Paper Cap Teflon Cap Foil Cap Storage Wet Ice Ambient Dry Ice	Cleaning Procedure Low $\rightarrow$ High Concentration Detergent Wash Water Rinse Acetone Rinse Hexane Rinse Other Solvent Rinse Specify: <u>  </u>	

## TRANSECT INFORMATION

Letter	Station #

Compass Direction   

Distance Between Stations

         to          is             Ft.

Remarks and Site Description

oil and water phase



# FIELD DATA SHEET

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

2 8 0540

Location: CROFT SPRING

Collectors: PK GP CW

Lab Number (Consec.#'s)

No 7333

Date Collected

Mo 01 Day 11 Yr 81

Time (24 hr)

## SOIL

Device	Soil Type
Auger	Rock
Core	Gravel
Split Spoon	Sand
Cylinder Cup	Clay
Spade	Silt
Depth	Muck
<u>  </u> <u>  </u> <u>  </u> <u>  </u>	Loam
Ft. or In.	Peat
	Color: <u>  </u>

## LAND

Upland-Dry  
Lowland-Dry  
Floodplain  
Wetland  
Gully

Slope  $> 15^\circ$   
 $< 15^\circ$

## VEGETATION

Old Field  
Wooded  
Farmland  
Residential  
Industrial  
Commercial

Herbaceous    %  
Shrubs    %  
Trees    %

DBH          In.

## GROUNDWATER

Water Table Depth             Ft.

Sample Depth             Ft.

Color:     
Odor:     
Oil:     
Device:   

## SURFACE WATER

Color:    Temp     
Odor:    pH   

STREAM Width             Ft.

Depth             Ft. or In.

Velocity             Ft/Sec

FLOW DIRECTION   

Pools    % Riffles    %

Device	Surface	Bottom %
Kemmerer	Clean	Ooze
Petersen	Oil	Sand
Surber	Garbage	Gravel
Manual	Trash	Clay
Net	Bubbles	Rubble
Seine	Dead Fish	Rock
Trawl	Sewage	Shell
Bucket	Ind. Waste	Organic
	Floated Solids	

## SAMPLE PREPARATION

Container	Cleaning Procedure
Glass Jar	Low $\rightarrow$ High Concentration
Plastic Jar	Detergent Wash
Metal	Water Rinse
Acetate Core	Acetone Rinse
Paper Cap	Hexane Rinse
Teflon Cap	Other Solvent Rinse
Foil Cap	Specify: <u>  </u>
Storage	
Wet Ice	
Ambient	
Dry Ice	

## TRANSECT INFORMATION

Letter	Station #
<u>  </u>	<u>  </u> <u>  </u> <u>  </u>

Compass Direction   

Distance Between Stations

         to          is             Ft.

Remarks and Site Description





## FIELD DATA SHEET

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

Location:

WECC # 2

Collectors:

PJM PK CB

Lab Number (Consec.#'s)

NO 7332

Date Collected

Mo A Day 11 Yr 86

Time (24 hr)

## SOIL

Device	Soil Type
Auger	Rock
Core	Gravel
Split Spoon	Sand
Cylinder Cup	Clay
Spade	Silt
Depth	Muck
	Loam
	Peat
	Color:

## LAND

Upland-Dry  
Lowland-Dry  
Floodplain  
Wetland  
Gully

Slope  $\geq 15^\circ$   
 $< 15^\circ$

## VEGETATION

Old Field  
Wooded  
Farmland

Residential  
Industrial  
Commercial

Herbaceous \_\_\_\_\_ %  
Shrubs \_\_\_\_\_ %  
Trees \_\_\_\_\_ %

DBH

\_\_\_\_\_ in.

## GROUNDWATER

Water Table Depth

285

Ft.

Sample Depth

Ft.

Color: \_\_\_\_\_

Odor: \_\_\_\_\_

Oil: \_\_\_\_\_

Device: Boiler

## SURFACE WATER

Color: \_\_\_\_\_ Temp \_\_\_\_\_  
pH \_\_\_\_\_

STREAM Width \_\_\_\_\_ Ft.

Depth \_\_\_\_\_ Ft. or In.

Velocity \_\_\_\_\_ Ft/Sec

FLOW DIRECTION \_\_\_\_\_

Pools \_\_\_\_\_ % Riffles \_\_\_\_\_ %

## Device

Kemmerer  
Petersen  
Surber  
Manual  
Net  
Seine  
Trawl  
Bucket

## Surface

Clean  
Oil  
Garbage  
Trash  
Bubbles  
Dead Fish  
Sewage  
Ind. Waste  
Float. Solids

## Bottom %

Ooze  
Sand  
Gravel  
Clay  
Rubble  
Rock  
Shell  
Organic

## Container

Glass Jar  
Plastic Jar  
Metal  
Acetate Core  
Paper Cap  
Teflon Cap  
Foil Cap

## Storage

Wet Ice  
Ambient  
Dry Ice

## Cleaning Procedure

Low → High Concentration  
Detergent Wash  
Water Rinse  
Acetone Rinse  
Hexane Rinse  
Other Solvent Rinse  
Specify:

## TRANSECT INFORMATION

Letter	Station #

Compass Direction

Distance Between Stations

\_\_\_\_\_ to \_\_\_\_\_ is \_\_\_\_\_ Ft.

Remarks and Site Description

PP ANALYSIS



## FIELD DATA SHEET

Environmental Response Team, Environmental Protection Agency  
Woodbridge Ave., Edison, N.J. 08837  
(201) 321-6660

Location: WELL #1

Collectors: C. BURCHETTE, P. KARLIZINSKI, P. McNALLY

Lab Number (Consec.#'s)

No 7331

Date Collected

Mo 01 Day 11 Yr 81

Time (24 hr)

0800

## SOIL

## LAND

## VEGETATION

## GROUNDWATER

<b>Device</b> Auger Core Split Spoon Cylinder Cup Spade  <b>Depth</b> <input type="text"/> <input type="text"/> <input type="text"/> <input type="text"/> Ft. or <input type="text"/> <input type="text"/> <input type="text"/> <input type="text"/> In.	<b>Soil Type</b> Rock Gravel Sand Clay Silt Muck Loam Peat Color: _____	<b>Upland-Dry</b> <b>Lowland-Dry</b> <b>Floodplain</b> <b>Wetland</b> <b>Gully</b>  Slope $> 15^\circ$ $< 15^\circ$	<b>Old Field</b> <b>Wooded</b> <b>Farmland</b> <b>Residential</b> <b>Industrial</b> <b>Commercial</b>  Herbaceous _____ % Shrubs _____ % Trees _____ % DBH <input type="text"/> <input type="text"/> <input type="text"/> In.	<b>Water Table Depth</b> <u>228.4</u> Ft.  <b>Sample Depth</b> <input type="text"/> <input type="text"/> <input type="text"/> <input type="text"/> Ft.  Color: _____ Odor: _____ Oil: _____ Device: <u>BAILER</u>
--	--	--	---	--

## SURFACE WATER

## SAMPLE PREPARATION

Color: _____ Temp _____ Odor: _____ pH _____  <b>STREAM</b> Width <input type="text"/> <input type="text"/> <input type="text"/> <input type="text"/> Ft. Depth <input type="text"/> <input type="text"/> <input type="text"/> <input type="text"/> Ft. or In. Velocity <input type="text"/> <input type="text"/> <input type="text"/> <input type="text"/> Ft/Sec FLOW DIRECTION _____ Pools _____ % Riffles _____ %	<b>Device</b> Kemmerer Petersen Surber Manual Net Seine Trawl Bucket	<b>Surface</b> Clean Oil Garbage Trash Bubbles Dead Fish Sewage Ind. Waste Float. Solids	<b>Bottom %</b> Ooze Sand Gravel Clay Rubble Rock Shell Organic	<b>Container</b> Glass Jar Plastic Jar Metal Acetate Core Paper Cap Teflon Cap Foil Cap  <b>Storage</b> Wet Ice Ambient Dry Ice	<b>Cleaning Procedure</b> Low $\rightarrow$ High Concentration Detergent Wash Water Rinse Acetone Rinse Hexane Rinse Other Solvent Rinse Specify: _____
--	--	---	---	---	--

## TRANSECT INFORMATION

Compass Direction

Distance Between Stations

Letter	Station #
<input type="text"/>	<input type="text"/>

to    is     Ft

Remarks and Site Description

P.P. VOA ANALYSIS

- WELL BAILED

- WOULD NOT RECHARGE

# ENVIRESPONSE, INC.

## CHAIN OF CUSTODY RECORD

SHEET NO. 1 OF 1

PROJECT NAME GRASS MERE

SAMPLER(S) SIGNATURE Paul McVally

PROJECT NO. \_\_\_\_\_

SAMPLE IDENTIFICATION	SAMPLING LOCATION	DATE SAMPLED	SAMPLE TYPE				COMB	GRAB	VOLUME TO BE COLLECTED	NO. OF CONTAINERS	TIME COLLECTION BEGAN	INITIAL	TIME COLLECTION COMPLETED	INITIAL	COMMENTS
			SOLID	LIQ	AIR	OIL									
7341	SSLN #1 RR	9-12	✓					✓	1L	1	0800	PM	1700	PM	PP METALS
7341	"	7-12	✓					✓	250ml	1	0800	PM	1700	PM	AL, FE, MN
7342	Lagoon	9-12	✓					✓	1L	1	0800	PM	1700	PM	PP METALS
7342	"	9-12	✓					✓	250ml	1	0800	PM	1700	PM	AL, FE, MN
7344	Highway Drain	9-12	✓						1L	1	0800	PM	1700	PM	PP METALS
7344	"	9-12	✓						250ml	1	0800	PM	1700	PM	AL, FE, MN
7345	Site Drain	9-12	✓						1L	1	0800	PM	1700	PM	CP METALS
7345	"	9-12	✓						250ml	1	0800	PM	1700	PM	AL, FE, MN

RELINQUISHED BY: NAME \_\_\_\_\_ DATE/TIME \_\_\_\_\_  
 RELINQUISHED BY: NAME \_\_\_\_\_ DATE/TIME \_\_\_\_\_  
 RELINQUISHED BY: NAME \_\_\_\_\_ DATE/TIME \_\_\_\_\_  
 AUTHORIZATION FOR DISPOSAL \_\_\_\_\_ DATE/TIME \_\_\_\_\_

RECEIVED BY: NAME \_\_\_\_\_ DATE/TIME \_\_\_\_\_  
 RECEIVED BY: NAME \_\_\_\_\_ DATE/TIME \_\_\_\_\_  
 RECEIVED BY: NAME \_\_\_\_\_ DATE/TIME \_\_\_\_\_  
 DISPOSED BY: \_\_\_\_\_ DATE/TIME \_\_\_\_\_

280543

APPENDIX D

MONITORING WELL INSTALLATION DETAILS

# FIELD WELL COMPLETION FORM

JOB NAME: Sand Waste Oil

JOB NUMBER: \_\_\_\_\_ PROJECT MANAGER: Karmazinski

LOGGED BY: McWally EDITED BY: Karmazinski

WELL NAME: MW-11 DATE: 3/25/87

DRILLING COMPANY: Geo Tek

EQUIPMENT: ☒ 6 1/4 INCH HOLLOW STEM AUGER DRILLER: \_\_\_\_\_  
☐ \_\_\_\_\_ INCH ROTARY WASH HOURS DRILLED: \_\_\_\_\_

GALLONS OF WATER USED DURING DRILLING: \_\_\_\_\_ GALLONS

METHOD OF DECONTAMINATION PRIOR TO DRILLING: Pressurized Steam

DEVELOPMENT

METHOD OF DEVELOPMENT: Surface Pumping

DEVELOPMENT BEGAN DATE: 3/25/87 TIME: 1100

YIELD:	GPM	TIME:	FROM	TO	DATE:
YIELD:	GPM	TIME:	FROM	TO	DATE:
YIELD:	GPM	TIME:	FROM	TO	DATE:
YIELD:	GPM	TIME:	FROM	TO	DATE:

TOTAL WATER REMOVED DURING DEVELOPMENT: \_\_\_\_\_ GALLONS

DESCRIPTION OF TURBIDITY AT END OF DEVELOPMENT: ☐ CLEAR ☐ SLIGHTLY CLOUDY  
☒ MOD. TURBID ☐ VERY MUDDY

ODOR OF WATER: Organic

WATER DISCHARGED TO: ☒ GROUND SURFACE ☐ TANK TRUCK  
☐ STORM SEWERS ☐ STORAGE TANK  
☐ DRUMS ☐ OTHER \_\_\_\_\_

DEPTH TO WATER AFTER DEVELOPMENT: 8.49' Below GS FEET

MATERIALS USED

4 SACKS OF Gravel 5.4 lbs SAND

3 SACKS OF Portland CEMENT

\_\_\_\_\_ GALLONS OF GROUT USED

\_\_\_\_\_ SACKS OF POWDERED BENTONITE

20 POUNDS OF BENTONITE PELLETS

\_\_\_\_\_ FEET OF \_\_\_\_\_ INCH PVC BLANK CASING

12 FEET OF 4 INCH PVC SLOTTED SCREEN


\_\_\_\_\_ YARD<sup>3</sup> CEMENT-SAND (REDI-MIX) ORDERED

\_\_\_\_\_ YARD<sup>3</sup> CEMENT-SAND (REDI-MIX) USED

CONCRETE PUMPER USED? ☒ NO ☐ YES

NAME \_\_\_\_\_

WELL COVER USED: ☒ LOCKING STEEL COVER  
☐ CHRISTY BOX  
☐ OTHER \_\_\_\_\_



NOT TO SCALE

ADDITIONAL INFORMATION: \_\_\_\_\_

# FIELD WELL COMPLETION FORM

JOB NAME: Saad Waste Oil

JOB NUMBER: \_\_\_\_\_ PROJECT MANAGER: Karmazinski

LOGGED BY: McWally EDITED BY: Karmazinski

WELL NAME: MW-14 DATE: 3/26/87

DRILLING COMPANY: Geo-Tek

EQUIPMENT: ☒ 6 1/4 INCH HOLLOW STEM AUGER DRILLER: \_\_\_\_\_  
☐ \_\_\_\_\_ INCH ROTARY WASH HOURS DRILLED: \_\_\_\_\_

GALLONS OF WATER USED DURING DRILLING: \_\_\_\_\_ GALLONS \_\_\_\_\_

METHOD OF DECONTAMINATION PRIOR TO DRILLING: Pressurized Steam

## DEVELOPMENT

METHOD OF DEVELOPMENT: Surface Pumping

DEVELOPMENT BEGAN DATE: 3/26/87 TIME: 1500

YIELD:	GPM	TIME: FROM	TO	DATE:
YIELD:	GPM	TIME: FROM	TO	DATE:
YIELD:	GPM	TIME: FROM	TO	DATE:
YIELD:	GPM	TIME: FROM	TO	DATE:

TOTAL WATER REMOVED DURING DEVELOPMENT: \_\_\_\_\_ GALLONS \_\_\_\_\_

DESCRIPTION OF TURBIDITY AT END OF DEVELOPMENT: ☐ CLEAR ☐ SLIGHTLY CLOUDY  
☒ MOD. TURBID ☐ VERY MUDDY

ODOR OF WATER: Sanic

WATER DISCHARGED TO: ☒ GROUND SURFACE ☐ TANK TRUCK  
☐ STORM SEWERS ☐ STORAGE TANK  
☐ DRUMS ☐ OTHER \_\_\_\_\_

DEPTH TO WATER AFTER DEVELOPMENT: 2.31' Below GS FEET

## MATERIALS USED

5 SACKS OF Gravel, Silica SAND

2 SACKS OF Silica CEMENT

\_\_\_\_\_ GALLONS OF GROUT USED

\_\_\_\_\_ SACKS OF POWDERED BENTONITE

20 POUNDS OF BENTONITE PELLETS

227 FEET OF \_\_\_\_\_ INCH PVC BLANK CASING

18 FEET OF 4 INCH PVC SLOTTED SCREEN


\_\_\_\_\_ YARD<sup>3</sup> CEMENT-SAND (REDI-MIX) ORDERED

\_\_\_\_\_ YARD<sup>3</sup> CEMENT-SAND (REDI-MIX) USED

CONCRETE PUMPER USED? ☒ NO ☐ YES

NAME \_\_\_\_\_

WELL COVER USED: ☒ LOCKING STEEL COVER  
☐ CHRISTY BOX  
☐ OTHER \_\_\_\_\_



NOT TO SCALE

ADDITIONAL INFORMATION: \_\_\_\_\_

\_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

**FIELD WELL COMPLETION FORM**

JOB NAME: Saad Waste O, I

JOB NUMBER: \_\_\_\_\_ PROJECT MANAGER: Karmazinski

LOGGED BY: McNelly EDITED BY: Karmazinski

WELL NAME: MW-18 DATE: 3/24/87

DRILLING COMPANY: GeoTek

EQUIPMENT: ☒ 6 1/4 INCH HOLLOW STEM AUGER DRILLER: \_\_\_\_\_  
☐ \_\_\_\_\_ INCH ROTARY WASH HOURS DRILLED: \_\_\_\_\_

GALLONS OF WATER USED DURING DRILLING: \_\_\_\_\_ GALLONS

METHOD OF DECONTAMINATION PRIOR TO DRILLING: Pressurized Steam

**DEVELOPMENT**

METHOD OF DEVELOPMENT: Surface Pumping

DEVELOPMENT BEGAN DATE: 3/24/87 TIME: 1400

YIELD:	GPM	TIME: FROM	TO	DATE:
YIELD:	GPM	TIME: FROM	TO	DATE:
YIELD:	GPM	TIME: FROM	TO	DATE:
YIELD:	GPM	TIME: FROM	TO	DATE:

TOTAL WATER REMOVED DURING DEVELOPMENT: \_\_\_\_\_ GALLONS

DESCRIPTION OF TURBIDITY AT END OF DEVELOPMENT: ☐ CLEAR ☐ SLIGHTLY CLOUDY  
☒ MOD. TURBID ☐ VERY MUDDY

ODOR OF WATER: Organic

WATER DISCHARGED TO: ☒ GROUND SURFACE ☐ TANK TRUCK  
☐ STORM SEWERS ☐ STORAGE TANK  
☐ DRUMS ☐ OTHER \_\_\_\_\_

DEPTH TO WATER AFTER DEVELOPMENT: 8.03' Below GS FEET

**MATERIALS USED**

4 SACKS OF Grout, Silica SAND

3 SACKS OF Portland CEMENT

\_\_\_\_\_ GALLONS OF GROUT USED

\_\_\_\_\_ SACKS OF POWDERED BENTONITE

20 POUNDS OF BENTONITE PELLETS

4.73 FEET OF 2" INCH PVC BLANK CASING

5 FEET OF 2" INCH PVC SLOTTED SCREEN



\_\_\_\_\_ YARD<sup>3</sup> CEMENT-SAND (REDI-MIX) ORDERED

\_\_\_\_\_ YARD<sup>3</sup> CEMENT-SAND (REDI-MIX) USED

CONCRETE PUMPER USED? ☒ NO ☐ YES

NAME \_\_\_\_\_

WELL COVER USED: ☒ LOCKING STEEL COVER  
☐ CHRISTY BOX  
☐ OTHER \_\_\_\_\_



NOT TO SCALE

ADDITIONAL INFORMATION: \_\_\_\_\_

\_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

**APPENDIX E**

**SINGLE WELL PUMPING TEST**




28 0549  
 Ave Q 6.25 GPM

# Single Well Pumping Test - B-6

Actual I #	Δ on Pumps (ft)	Time + Size Pumping started (ft)	Drawdown (ft)
9:14 Test Begin	7.38'	0	
9:16	6.5 GPM	5	0.02
9:19	7.40'	7	0.03
9:21	7.41'	10	0.05
9:24	6.0 GPM	12	0.05
9:26	7.43'	19	0.05
9:33	6 GPM	26	0.05
9:40	7.43'	38	0.05
9:46	6.5 GPM	43	0.05
9:52	7.43'	48	0.05
9:57	7.43'	58	0.05
10:02	6.25 GPM	59	
10:12	7.43'		
10:13	Pump off		

\* Measured from top of temporary PVC hose installed in PVC Screen



AD  
= 0.058'

28 0500

# B-C Single Well Pumping Test

2 8

0551

$$T = \frac{264 \text{ Q}}{\Delta\Delta}$$

where

$T$  = Transmissivity  
 $Q$  = Pumping Rate

$\Delta\Delta$  = Drawdown per log Cycle

$$= \frac{264 (6.25 \text{ GPM})}{0.058'}$$

$$= 28,448 \text{ GPD/ft}$$

$$K = \frac{T}{S}$$

Where:

$K$  = Hydraulic Conductivity  
 $T$  = Transmissivity

$S$  = Saturated Thickness of Aquifer

$$K = \frac{28,448}{16'}$$

$$= 1,778 \text{ ft/day}$$

$$= 6.272 \times 10^{-1} \text{ cm/sec}$$

$$\frac{86,400}{}$$

$$= \frac{125 \text{ GPM}}{\text{ft}^3/\text{ft}^3}$$

$$= \frac{6.25 \text{ (GPM)}}{0.05 \text{ ft}}$$

$$\text{Specific Capacity} = \frac{\text{discharge}}{Q}$$

APPENDIX F

PRIOR GROUNDWATER ANALYSIS

NUS FIT Report, Sampling Investigation Report  
Saad Site, Nashville, Tennessee, September 9, 1983

**Table I  
Saad Site  
Nashville, Tennessee**

**SAMPLE CODES, DESCRIPTIONS AND LOCATIONS**

<u>CODE</u>	<u>DESCRIPTION</u>	<u>LOCATION</u>
<b><u>PHASE 1:</u></b>		
SS-PW-1W	Water	Newman's Private Well
SS-PW-2W	Water	Lankford's Private Well
SS-FB-W	Water	Behind Franklin Brick
SS-LN-DL-W	Water	Secondary Drainage Lagoon Radnor Railroad Yard
SS-LN-DL-S	Sediment	Secondary Drainage Lagoon Radnor Railroad Yard
SS-LN-OS-W-	Water	Oil Separator Radnor Railroad Yard
SS-LN-OS-S	Sediment	Oil Separator Radnor Railroad Yard
SS-CON-1S	Soil	18" below surface behind Saad Oil Company
SS-CON-2S	Soil	6' below surface behind Saad Oil Company
SS-S-6.1-W	Water	Ground seepage near big spring on Croft farm
SS-S-6.1-S	Sediment	Ground seepage near big spring on Croft farm
SS-S-2-W	Water	Side spring near spring S-2 on Croft farm
SS-S-2-S	Sediment	Side spring near spring S-2 on Croft farm
SS-S-3.1-W	Water	Second spring on Croft farm
SS-S-3.1-S	Sediment	Second spring on Croft farm
SS-SP4-5-W	Water	Side stream near spring on Croft farm
SS-SS-SP4-5S	Sediment	Side stream near spring on Croft farm

TABLE 1 (continued)

CODE	DESCRIPTION	LOCATION
SS-T-2-W	Water	Industrial creek north of Croft farm*
SS-T-2-S	Sediment	Industrial creek north of Croft farm*
SS-BC-W	Water	Below confluence of Croft spring and industrial creek*
SS-BC-S	Sediment	Below confluence of Croft spring and industrial creek*
SS-S-7-W	Water	Major spring on Croft farm (Croft spring)
SS-S-7-S	Sediment	Major spring on Croft farm (Croft spring)
SS-CF-SP*	Water	Major spring on Croft farm (Croft spring)
<b>PHASE II:</b>		
SS-CS-1	Composite Soil	Intersection of Vulcan & McNalley Drive, north of railroad track
SS-CS-2	Composite Soil	Intersection of Vulcan & McNalley Drive, south of railroad track
SS-CS-3	Composite Soil	Low point east of Trousdale Blvd. at SW corner of Kabinart Corporation
SS-CS-3A	Composite Soil	Drainage ditch west of Trousdale Blvd. across from SS-CS-3
SS-CS-4	Composite Soil	Sink hole across Trousdale Blvd. from Saad site
SS-CS-5S	Sediment	Low point behind fenced area across from Saad Oil Company
SS-CS-5W	Water	Low point behind fenced area across from Saad Oil Company


TABLE I (continued)


<u>CODE</u>	<u>DESCRIPTION</u>	<u>LOCATION</u>
SS-CS-6	Composite Soil	Drainage ditch on Croft Farm at corner of railroad track Trousdale Road
SS-CS-7	Composite Soil	Drainage ditch on eastern side of Trousdale Road at culvert mouth
SS-CS-8W	Water	Ditch west of Trousdale Road south of Saad site
SS-CS-8S	Sediment	Ditch west of Trousdale Road south of Saad site
PHASE III (Figure 4)		
SS-WT-1	Water	Tank truck used by driller
SS-CF-MW2	Water	Monitoring well No. 2 on Croft Farm
SS-CF-MW3	Water	Monitoring well No. 3 on Croft Farm
SS-CF-MW4	Water	Monitoring well No. 4 on Croft Farm
SS-CF-MW5	Water	Monitoring well No. 5 on Croft Farm
SS-LN-MW6	Water	Monitoring well on L&N property
SS-SS-MW7	Water	Monitoring well on Saad property

\* Sample actually taken during Phase III but is included with the other samples collected from the spring in Phase I.



0557 20





**NUS**  
CORPORATION  
A Halliburton Company  
810 CLOVER ROAD  
GAITHERSBURG, MARYLAND 20878  
(301) 255-6000

**FIGURE 3**  
**PHASE 2**  
**SAMPLE LOCATION**

**Table II**  
**Saad Site - Phase I**  
**Water Samples**  
**Inorganic Analysis**  
**(in ug/l)**

Element	SS- PW-1W	SS- PW-2W	SS- FB-W	SS- LN-DL/W	SS- LN-OS/W	SS- CF-SP	SS- S-7/W	SS- S-6.1/W	SS- S-2/W	SS- S-3.1/W	SS- SP4-5/W	SS- T-2/W	SS- BC/W
Barium	-	-	580	21	-	-	-	121	14	-	-	-	-
Cadmium*	-	-	-	-	-	3	-	-	-	-	-	-	-
Copper*	5	17	22	38	-	-	-	-	-	-	-	-	-
Lead*	-	-	-	-	-	22	-	-	-	-	-	-	-
Strontium	341	144	530	113	278	-	160	104	140	85	91	171	163
Titanium	3	10	230	13	-	-	-	278	21	-	10	-	10
Vanadium	-	-	33	-	-	-	-	13	-	-	-	-	-
Yttrium	-	-	17	-	-	-	-	11	-	-	-	-	-
Zinc*	22	267	95	78	-	-	-	70	-	-	-	-	10
Aluminum	130	400	39,000	500	100	-	160	11,000	580	-	500	200	200
Manganese	10	46	1,400	77	2,200	3,200	2,400	1,400	920	-	-	72	170
Calcium	54,000	70,000	250,000	36,000	96,000	-	90,000	102,000	84,000	61,000	72,000	99,000	92,000
Magnesium	10,000	6,600	26,000	5,400	9,700	-	6,500	6,600	6,200	4,900	5,000	6,600	6,200
Iron	900	300	22,000	900	700	5,300	26,000	12,000	1,000	-	200	100	200
Sodium	4,500	9,000	19,000	12,000	31,000	-	11,000	12,000	9,000	4,000	10,000	10,000	9,000
Cyanide*	<2	<2	20	<2	10	-	<2	<2	<2	<2	<2	<2	<2

- Material was analyzed for but not detected

Table III  
Sand Site - Phase I  
Water Samples  
Purgeable Organic Analysis  
(in ug/l)

Compound	SS- PW-1W	SS- PW-2W	SS- PB-W(2)	SS- LN-DL/W	SS- LN-OS/W	SS- CF-SP	SS- S-7/W	SS- S-6.1/W(3)	SS- S-2/W	SS- S-3.1/W	SS- SP4/5/W(1)	SS- T-2/W	SS- BC/W
Chloroethane*	-	-	5.3	-	-	-	-	-	-	-	-	-	-
1,1-Dichloroethane*	-	-	5.1	-	16	-	2 J	22	-	-	-	2 J	2 J
Trans-1,2-Dichloroethene	64	-	8.5	-	-	-	-	3 J	-	-	-	0.9 J	-
Chloroform*	-	-	-	20	3 J	-	0.5 J	-	-	0.8 J	0.5 J	0.6 J	0.5 J
1,1,1-Trichloroethane*	-	-	-	-	50	-	-	3 J	-	-	-	5 J	3 J
Bromodichloromethane	-	-	-	0.8 J	-	-	-	-	-	-	-	-	-
Trichloroethene	-	-	0.5 J	-	-	-	-	0.6 J	-	-	-	1 J	0.7 J
Benzene*	-	-	4 J	-	-	-	-	-	-	-	NA	-	-
Tetrachloroethene	-	0.6 J	-	-	-	-	-	-	-	-	0.9 J	12	9
Toluene*	-	-	230 J	-	-	-	-	-	-	-	NA	-	-
Chlorobenzene*	-	-	-	-	-	-	2 J	-	-	-	NA	-	-
Ethyl Benzene*	-	-	9.2 J	-	-	-	-	-	-	-	NA	-	-
M-Xylene	-	-	32 J	-	-	NA	-	-	-	-	NA	-	-
OxP-Xylene(mixed)	-	-	40 J	-	-	NA	-	-	-	-	NA	-	-
2-methyl-2- methylpropane	-	5 JN	-	-	-	-	-	-	-	-	-	-	-

Table III (continued)  
Saad Site - Phase I  
Water Samples  
Purgeable Organic Analysis  
(in ug/l)

Compound	SS- PW-1W	SS- PW-2W	SS- FB-W(2)	SS- LN-DL/W	SS- LN-OS/W	SS- CF-SP	SS- S-7/W	SS- S-6.1/W(3)	SS- S-2/W	SS- S-3.1/W	SS- SP4/5/W(1)	SS- T-2/W	SS- BC/W
total unidentified alkylhydrocarbons	-	-	20 J	-	-	-	-	-	-	-	-	-	-
methyl isobutyl ketone	-	-	30 JN	-	-	-	-	-	-	-	-	-	-
Vinyl Chloride*	-	-	4 J	-	-	-	-	-	-	-	-	-	-

- (1) For station SP4-5/W, acid preserved sample was lost during analysis.  
 (2) No acid preserved sample.  
 (3) Holding time exceeded.  
 J Estimated value.  
 N Presumptive evidence of presence of material.  
 NA compound not analyzed for.  
 \* Priority pollutant.

Table IV  
Saad Site - Phase I  
Water Samples  
Extractable Organic Analysis  
(in ug/l)

Compound	PW-1/W	PW-2/W	FB-W	LN-DL/W	LN-OS/W	CF-SP(1)	S-7/W	S-6.1/W	S-2/W	S-3.1/W	SP4/5/W	T-2/W	BC/W
Acenaphthene*	-	-	1.0 J	-	-	-	-	-	-	-	-	-	-
Flouranthene*	-	-	1.0 J	-	-	-	-	-	-	-	-	-	-
Pyrene*	-	-	1.0 J	-	-	-	-	-	-	-	-	-	-
Chrysene*	-	-	-	5 J	-	-	-	-	-	-	-	-	-
Benzo(6H)Perylene*	-	-	-	14 J	-	-	-	-	1.0 J	-	-	-	-
2,4-Dimethylphenol*	-	-	3.8 J	-	-	-	-	-	-	-	-	-	-
Pentachlorophenol*	-	-	-	84 J	-	-	-	-	1.0 J	-	-	-	-
Naphthaleneamine (3 isomers)	-	-	25 JN	-	-	-	-	-	-	-	-	-	-
C <sub>3</sub> Alkylbenzenesulfo- Namide	-	-	10 JN	-	-	-	-	-	1.0 J	-	-	-	-
Phosphoric acid, tributyl ether	-	-	10 JN	-	-	-	-	-	-	-	-	-	-
C <sub>5</sub> Alkylbenzenesulfo- namide	-	-	10 JN	-	-	-	-	-	1.0 J	-	-	-	-
Hexadecanoic Acid	-	-	10 JN	-	-	-	10 JN	-	-	10 JN	-	-	-
Methylphenal	-	-	10 JN	-	-	-	-	-	1.0 J	-	-	-	-

Table IV (continued)  
Saad Site - Phase I  
Water Samples  
Extractable Organic Analysis  
(in ug/l)

Compound	PW-1/W	PW-2/W	PB-W	LN-DL/W	LN-OS/W	CF-SP(1)	S-7/W	S-6.1/W	S-2/W	S-3.1/W	SP4/5/W	T-2/W	BC/W
Methyldibenzothiophene	-	-	-	-	20 JN	-	-	-	-	-	-	-	-
Methylphenanthrene	-	-	-	-	10 JN	-	-	-	-	-	-	-	-
C <sub>7</sub> alkylphenanthrene (4 isomers)	-	-	-	-	40 JN	-	-	-	-	-	-	-	-
C <sub>7</sub> Alkylphenanthrene (4 isomers)	-	-	-	-	10 JN	-	-	-	-	-	-	-	-
Methylpyrene	-	-	-	-	10 JN	-	-	-	-	-	-	-	-
Bromoethylmethylpropyl-	-	-	-	-	-	-	10 JN	-	-	-	-	-	-
Dimethylbenzenesulfonamide	-	-	-	-	-	-	-	-	10 JN	-	-	-	-
Petroleum Type Product	-	-	-	-	NQ	-	-	-	-	-	-	-	-
Unidentified Compounds(2)	-	-	2	-	-	-	-	-	-	1	1	-	-

- Material was analyzed for but not detected.

J Estimated value.

N Presumptive evidence of resence of material.

NQ Material not quantified.

(2) For station CF-SP, quantity for phenals is suspect based on QC data.

(2) Recorded in number of compounds detected not ug/l.

\* Prioioty pollutant.

Table IV (continued)  
 Saad Site - Phase I  
 Water Samples  
 Extractable Organic Analysis  
 (in ug/l)

Compound	PW-1/W	PW-2/W	FB/W	LN-DL/W	LN-OS/W	CF-SP(1)	S-7/W	S-6.1/W	S-2/W	S-3.1/W	SP4/5/W	T-2/W	BC/W
C <sub>3</sub> Alkyl-naphthalene (2 isomers)	-	-	-	50 JN	-	-	-	-	-	-	-	-	-
Dibenzothiophene	-	-	-	50 JN	-	-	-	-	-	-	-	-	-
Methyldibenzothiophene (2 isomers)	-	-	-	50 JN	-	-	-	-	-	-	-	-	-
C <sub>2</sub> Alkyl-naphthothiophene (2 isomers)	-	-	-	50 JN	-	-	-	-	-	-	-	-	-
C <sub>2</sub> Alkylphenanthrene	-	-	-	50 JN	-	-	-	-	1.0 J	-	-	-	-
Tetrahydromethylnaphthalene (2 isomers)	-	-	-	-	15 JN	-	-	-	-	-	-	-	-
C <sub>2</sub> Alkyl-naphthalene (2 isomers)	-	-	-	-	10 JN	-	-	-	1.0 J	-	-	-	-
Octahydrohexamethyl- lindene	-	-	-	-	21 JN	-	-	-	-	-	-	-	-
C <sub>3</sub> Alkyl-naphthalene (7 isomers)	-	-	-	-	50 JN	-	-	-	1.0 J	-	-	-	-
C <sub>4</sub> Alkyl-naphthalene (5 isomers)	-	-	-	-	150 JN	-	-	-	-	-	-	-	-
C <sub>2</sub> Alkylbiphenyl	-	-	-	-	10 JN	-	-	-	1.0 J	-	-	-	-



Table V  
 Sand Site - Phase I  
 Soil/Sediment Samples  
 Inorganic Analysis  
 (in ug/kg)(1)

Element	SS- LN-D4S	SS- LN-OS/S	SS- CON-1S	SS- CON-2S	SS- S-7/S	SS- S-6.1/S	SS- S-2/S	SS- S-3.1/S	SS- SP4-5/S	SS- T-2/S	SS- BC/S	SS- CF-SP
Silver*	-	-	8,400	-	-	-	-	-	-	-	-	1,700
Arsenic*	-	-	-	-	-	-	-	-	-	-	-	1,500
Barium	56,000	100,000	250,000	240,000	250,000	220,000	330,000	190,000	90,000	130,000	130,000	35,000
Cadmium*	1,000	-	31,000	-	-	-	-	-	-	-	-	1,000
Cobalt	-	-	-	-	-	-	NA	NA	-	NA	NA	5,500
Chromium*	10,000	25,000	180,000	34,000	30,000	20,000	26,000	18,000	15,000	11,000	15,000	8,800
Copper*	24,000	69,000	170,000	26,000	17,000	7,600	5,000	6,000	4,400	5,000	13,000	-
Nickel*	4,600	10,000	96,000	20,000	-	12,000	12,000	9,000	8,000	7,000	6,500	8,900
Lead*	26,000	82,000	410,000	100,000	-	21,000	16,000	15,000	9,000	46,000	140,000	2,200
Tin	-	-	40,000	-	-	-	-	-	-	-	-	-

Table V (continued)  
Saad Site - Phase I  
Soil/Sediment Samples  
Inorganic Analysis  
(in ug/kg)<sup>(1)</sup>

Element	SS- LN-D4/S	SS- LN-05/S	SS- CON-1/S	SS- CON-2/S	SS- S-7/S	SS- S-6.1/S	SS- S-2/S	SS- S-3.1/S	SS- SP4-5/S	SS- T-2/S	SS- BC/S	SS- CF-SP
Strontium	62,000	290,000	140,000	230,000	370,000	150,000	280,000	310,000	100,000	-	330,000	NA
Tellurium	-	-	-	-	-	-	-	-	-	-	-	-
Titanium	64,000	140,000	74,000	120,000	180,000	390,000	260,000	130,000	140,000	-	120,000	NA
Zinc*	70,000	69,000	860,000	150,000	31,000	42,000	30,000	59,000	22,000	22,000	58,000	12,000
Mercury*	NAI	-	NA	NA	190	120	220	220	250	-	-	-
Thallium*	-	-	-	-	-	-	-	-	-	110,000	-	-
Aluminum	3,500,000	9,400,000	9,800,000	19,000,000	19,000,000	19,000,000	20,000,000	14,000,000	15,000,000	9,900,000	12,000,000	2,000,000
Manganese	170,000	840,000	680,000	1,200,000	5,500,000	640,000	5,100,000	7,200,000	780,000	2,000,000	1,800,000	5,600,000

Table V (continued)  
 Sand Site - Phase I  
 Soil/Sediment Samples  
 Inorganic Analysis  
 (in ug/kg)(1)

Element	SS- LN-D4S	SS- LN-OS/S	SS- CON-1S	SS- CON-2S	SS- S-7/S	SS- S-6.1/S	SS- S-2/S	SS- S-3.1/S	SS- SP4-5/S	SS- T-2/S	SS- BC/S	SS- CF-SP
Iron	8,400,000	22,000,000	18,000,000	25,000,000	88,000,000	18,000,000	32,000,000	18,000,000	14,000,000	17,000,000	2,200,000	10,000,000
Sodium	230,000	550,000	680,000	450,000	1,100,000	300,000	490,000	880,000	370,000	490,000	590,000	NA
Cyanide*	200	200	-	-	200	200	200	200	200	200	200	-

- Material was analyzed for but not detected.

NA Element not analyzed for.

J Estimated value.

NAI Interferences

\* Priority

Actual value is known to be less than value given.

(1) Dry Weight

Table VI  
Saad Site - Phase I  
Soil/Sediment Samples  
Purgeable Organic Analysis  
(in ug/kg)(3)

Compound	SS- LN-DL/S	SS- LN-OS/S	SS- CON-S	SS- CON-ZS	SS- S-7/S	SS- S-6.1/S	SS- S-2/S	SS- S-3.1/S	SS- SP4-S	SS- T-2/S	SS- BC/S	SS- CF-SP
1,1-Dichloroethane*	290	33	-	-	-	-	-	-	-	-	-	-
1,1,1-Trichloroethane*	450	43	3,000	-	-	-	-	-	-	-	-	-
Trichloroethene	43	-	65,000	2,000	-	-	-	-	-	-	-	-
Tetrachloroethene	-	-	14,000	-	-	-	-	-	33	33	43	-
Toluene*	78	-	270,000	16,000	-	-	-	-	-	-	-	-
Ethyl Benzene*	130	-	-	-	-	-	-	-	-	-	-	-
M-Xylene	310	-	170,000	4,000	-	-	-	-	-	-	-	NA
O & P-Xylene (mixed)	260	-	120,000	4,000	-	-	-	-	-	-	-	-

Table VI (continued)  
 Saad Site - Phase I  
 Soil/Sediment Samples  
 Purgeable Organic Analysis  
 (in ug/kg)(3)

Compound	SS- LN-DL/S	SS- LN-OS/S	SS- CON-1/S	SS- CON-2/S	SS- S-7/S	SS- S-6.1/S	SS- S-2/S	SS- S-3.1/S	SS- SP4-5/S	SS- T-2/S	SS- BC/S	SS- CF-SP
Isopropanol	103N	-	-	-	-	-	-	-	-	-	-	-
Methylethyl Ketone	5003N	-	-	-	-	-	-	-	-	-	-	-
Methyl Isopropyl Ketone	303N	-	-	-	-	-	-	-	-	-	-	-
Methyl Butyl Ketone	303N	-	-	-	-	-	-	-	-	-	-	-
Methyl Isobutyl Ketone	3003N	-	-	-	-	-	-	-	-	-	-	-
Total Unidentified Alkyl Hydrocarbons	6,8003	1,0003	1,700,0003	180,0003	1,1003	-	-	-	-	-	-	-
Unidentified Terpene	-	303	-	-	503	-	-	-	-	-	-	-
Tricyclodecane	-	-	-	-	-	-	-	-	-	-	-	-

Table VI (continued)  
 Saad Site - Phase I  
 Soil/Sediment Samples  
 Purgeable Organic Analysis  
 (in ug/kg)(3)

Compound	SS- LN-DL/S	SS- LN-OS/S	SS- CON-7S	SS- CON-2S	SS- S-7/S	SS- S-6.1/S	SS- S-2/S	SS- S-3.1/S	SS- SP4-5S	SS- T-2/S	SS- BC/S	SS- CP-SP
Trimethylcyclohexane	-	-	-	-	-	-	-	-	-	-	-	-
Unidentified Compounds	-	-	-	-	-	-	-	-	-	-	-	-
Methylene Chloride	-	-	250,000	-	-	-	-	-	-	-	-	-
Trans-1,2-Dichloroethene	-	-	13,000	12,000	-	-	-	-	-	-	-	-
Isooctanol	-	-	180,000JN	18,000JN	-	-	-	-	-	-	-	-
C9Alcohol (isomer unknown)	-	-	37,000J	14,000J	-	-	-	-	-	-	-	-

Table VI (continued)  
Saad Site - Phase I  
Soil/Sediment Samples  
Purgeable Organic Analysis  
(in ug/kg)<sup>(3)</sup>

Compound	SS- LN-DL/S	SS- LN-OS/S	SS- CON-1/S	SS- CON-2/S	SS- S-7/S	SS- S-6.1/S	SS- S-2/S	SS- S-3.1/S	SS- SP4-S/S	SS- T-2/S	SS- BC/S	SS- CF-SP
Decanol	-	-	220,000JN	22,000JN	-	-	-	-	-	-	-	-

\* Priority pollutants.

- Material was analyzed for but not detected.

J Estimated value.

N Presumptive evidence of presence of material

NA Compound not analyzed for.

(1) Unidentified compounds recorded as number of compounds detected, ug/kg.

(2) The data is suspect based on quality control information.

(3) Dry weight.

Table VII  
Saad Site - Phase I  
Soil/Sediment Samples  
Extractable Organic Analysis  
(in ug/kg)(1)

Compound	SS- LN-DL/S	SS- LN-06/S	SS- CON-1/S	SS- CON-2/S	SS- S-7/S	SS- S-6.1/S	SS- S-3.1/S	SS- SP4/S	SS- T-2/S	SS- BC/S	SS- CF-SP
Naphthalene*	5,400J	2,000J	-	-	-	-	-	-	-	-	-
Acenaphthene*	4,600J	-	-	-	-	-	-	-	1,400J	-	-
Flourene*	12,000J	4,500J	-	-	-	-	-	-	1,400J	-	-
Phenanthrene*	36,000J	18,000J	-	-	-	-	-	-	2,500J	-	-
Anthracene	-	2,000J	-	-	-	-	-	-	1,400J	-	-
Flouranthene*	4,600J	3,400J	-	-	-	-	-	-	1,300J	-	-
Pyrene*	7,500J	9,000J	-	-	-	-	-	-	3,900J	-	-
Benzo(A)Anthracene*	-	2,000J	-	-	-	-	-	-	1,400J	-	-



Table VII (continued)  
Saad Site - Phase I  
Soil/Sediment Samples  
Extractable Organic Analysis  
(in ug/kg)(1)

Compound	SS- LN-DL/S	SS- LN-OS/S	SS- CON-1/S	SS- CON-2/S	SS- S-7/S	SS- S-6.1/S	SS- S-3.1/S	SS- SP4/S	SS- T-2/S	SS- BC/S	SS- CF-SP
Chrysene*	4,600J	2,000J	-	-	-	-	-	-	1,400J	-	-
Benzo(B)Flouranthene	-	2,000J	-	-	-	-	-	-	1,400J	-	-
Benzo(K)Flouranthene*	-	2,000J	-	-	-	-	-	-	1,400J	-	-
Benzo-A-Pyrene*	-	-	-	-	-	-	-	-	1,400J	-	-
Benzo(GHI)Perylene*	-	-	-	-	-	-	-	-	2,500J	-	-
Pentachlorophenol*	-	-	-	-	-	2,700J	520J	-	-	-	-
C <sub>2</sub> Alkylstyrene	46,000JN	-	-	-	-	-	-	-	-	-	-
C <sub>3</sub> Alkylstyrene (3 isomers)	46,000JN	-	-	-	-	-	-	-	-	-	-

Table VII (continued)  
 Saad Site - Phase I  
 Soil/Sediment Samples  
 Extractable Organic Analysis  
 (in ug/kg)(1)

Compound	SS- LN-DL/S	SS- LN-O6/S	SS- CON-1/S	SS- CON-ZS	SS- S-7/S	SS- S-6.1/S	SS- S-3.1/S	SS- SP4/SS	SS- T-2/S	SS- BC/S	SS- CF-SP
Methylnaphthalene (2 isomers)	50,000JN	-	-	-	-	-	-	-	-	-	-
C <sub>2</sub> Alkyl-naphthalene (5 isomers)	110,000JN	-	-	-	-	-	-	-	-	-	-
C <sub>3</sub> Alkyl-naphthalene (7 isomers)	120,000JN	70,000JN	-	-	-	-	-	-	-	-	-
C <sub>4</sub> Alkyl-naphthalene (4 isomers)	80,000JN	-	-	-	-	-	-	-	-	-	-
Dimethyltetrahydronaphthalene (2 isomers)	46,000JN	-	-	-	-	-	-	-	-	-	-
Methylbiphenyl (2 isomers)	46,000JN	-	-	-	-	-	-	-	-	-	-

Table VII (continued)  
 Saad Site - Phase I  
 Soil/Sediment Samples  
 Extractable Organic Analysis  
 (in ug/kg)<sup>(1)</sup>

Compound	SS- LN-DL/S	SS- LN-OS/S	SS- CON-1S	SS- CON-2S	SS- S-7/S	SS- S-6.1/S	SS- S-3.1/S	SS- SP4/S	SS- T-2/S	SS- BC/S	SS- CF-SP
C <sub>2</sub> Alkylfluorene (4 isomers)	50,000JN	-	-	-	-	-	-	-	-	-	-
Dibenzothiophene	60,000JN	-	-	-	-	-	-	-	-	-	-
Methylphenanthrene (3 isomers)	70,000JN	-	-	-	-	-	-	-	-	-	-
C <sub>2</sub> alkylphenanthrene (5 isomers)	50,000JN	26,000JN	-	-	-	-	-	-	-	-	-
C <sub>3</sub> Alkylphenanthrene	46,000JN	-	-	-	-	-	-	-	-	-	-
Dimethylnaphthothiophene	50,000JN	-	-	-	39,000JN	-	-	-	-	-	-
C <sub>4</sub> Alkylbenzene	-	20,000JN	-	-	-	-	-	-	-	-	-

Table VII (continued)  
 Saad Site - Phase I  
 Soil/Sediment Samples  
 Extractable Organic Analysis  
 (in ug/kg)(1)

Compound	SS- LN-DL/S	SS- LN-OS/S	SS- CON-1/S	SS- CON-2/S	SS- S-7/S	SS- S-6.1/S	SS- S-3.1/S	SS- SP4/S	SS- T-2/S	SS- BC/S	SS- CF-SP
C <sub>5</sub> Alkylbenzene (3 isomers)	-	20,000JN	-	-	-	-	-	-	-	-	-
Methyldecahydronaphthalene	-	20,000JN	-	-	-	-	-	-	-	-	-
C <sub>3</sub> Alkylstyrene (2 isomers)	-	20,000JN	-	-	-	-	-	-	-	-	-
C <sub>4</sub> Alkylstyrene (4 isomers)	-	26,000JN	-	-	-	-	-	-	-	-	-
Methylnaphthalene	-	20,000JN	-	-	-	-	-	-	-	-	-
C <sub>2</sub> Alkyl naphthalene (3 isomers)	-	60,000JN	-	-	-	-	-	-	-	-	-

Table VII (continued)  
 Saad Site - Phase I  
 Soil/Sediment Samples  
 Extractable Organic Analysis  
 (In ug/kg)(1)

Compound	SS- LN-DL/S	SS- LN-OS/S	SS- CON-1S	SS- CON-2S	SS- S-7/S	SS- S-6.1/S	SS- S-3.1/S	SS- SP4/S	SS- T-2/S	SS- BC/S	SS- CF-SP
C <sub>4</sub> Alkyl naphthalene (7 isomers)	-	70,000JN	-	-	-	-	-	-	-	-	-
C <sub>2</sub> Alkylbiphenyl (2 isomers)	-	26,000JN	-	-	-	-	-	-	-	-	-
Methyldibenzofuran	-	20,000JN	-	-	-	-	-	-	-	-	-
Methylflourene	-	26,000JN	-	-	-	-	-	-	-	-	-
C <sub>2</sub> Alkylflourene	-	20,000JN	-	-	-	-	-	-	-	-	-
Methylphenanthrene (2 isomers)	-	20,000JN	-	-	-	-	-	-	-	-	-

Table VII (continued)  
Saad Site - Phase I  
Soil/Sediment Samples  
Extractable Organic Analysis  
(in ug/kg)(1)

Compound	SS- LN-DL/S	SS- LN-OS/S	SS- CON-1/S	SS- CON-2/S	SS- S-7/S	SS- S-6.1/S	SS- S-3.1/S	SS- SP4/S	SS- T-2/S	SS- BC/S	SS- CF-SP
C <sub>3</sub> Alkylphenanthrene (5 isomers)	-	26,000JN	-	-	-	-	-	-	-	-	-
Methylnaphthethiophene	-	20,000JN	-	-	-	-	-	-	-	-	-
Methylflouranthene (2 isomers)	-	20,000JN	-	-	-	-	-	-	-	-	-
Methyl(cyclohexylmethyl) Cyclohexane	-	-	-	-	59,000JN	-	-	-	-	-	-
Hexamethyloctahydroindene	-	-	-	-	59,000JN	-	-	-	-	-	-
C <sub>3</sub> Alkylnaphthalene	-	-	-	-	59,000JN	-	-	-	-	-	-
C <sub>4</sub> Alkylnaphthalene (3 isomers)	-	-	-	-	59,000JN	-	-	-	-	-	-

Table VII (continued)  
Saad Site - Phase I  
Soil/Sediment Samples  
Extractable Organic Analysis  
(in ug/kg)(1)

Compound	SS- LN-DL/S	SS- LN-OS/S	SS- CON-1S	SS- CON-2S	SS- S-7/S	SS- S-6.1/S	SS- S-3.1/S	SS- SP4/S	SS- T-2/S	SS- BC/S	SS- CF-SP
Hexadecenoic Acid	-	-	-	-	-	6,000JN	-	-	-	-	-
Heptadecanoic Acid	-	-	-	-	-	5,000JN	-	-	-	-	-
Hexadecanoic Acid, Methyl Ester	-	-	-	-	-	5,000JN	-	-	-	-	-
Petroleum Product	NQ	NQ	NQ	NQ	NQ	NQ	-	-	NQ	NQ	N

\* Priority pollutant.

- Material was analyzed for but not detected.

NA Not analyzed for.

J Estimated value.

N Presumptive evidence of presence of material.

NQ Not quantified.

(1) Dry weight.

**Table VIII**  
**Saad Site - Phase I**  
**Soil/Sediment Samples**  
**Pesticides/PCB's and other chlorinated compounds**  
**(in ug/kg)(2)**

Compounds	LN-DL/S	LN-OS/S	CON-1S	CON-2S	S-7/S	S-6.1/S	S-2/S	S-3.1/S	SP4-5/S	T-2/S	BC/S	CF-SP(1)
Gamma-chlordane	-	-	-	-	-	-	-	-	-	62	48	-

**DRAFT**

- Material was analyzed for but not detected.

(1) For station CF-SP, all data suspect based on QC data.

(2) Data reported on dry weight basis.



Table IX  
Saad Site - Phase II  
Water Samples  
Inorganic Analysis  
(in ug/l)

Element	SS-CS-5W	SS-CS-8W
Cadmium*	10	6
Lead*	8	10
Selenium*	9	5
Zinc*	26	32
Aluminum	760	910
Manganese	150	110
Iron	1100	1110

\* Priority pollutant.

**TABLE X**  
**Saad Site - Phase II**  
**Water Samples**  
**Purgeable Organics Analysis**  
**(in ug/l)**

**Compound**

**SS-CS-5W**

**SS-CS-8W**

**Acetone**

**NQ**

**--**

**- Material was analyzed for but not detected.**  
**NQ - Not quantified**

**DRAFT**

**TABLE XI**  
**Saad Site - Phase II**  
**Water Samples**  
**Extractable Organic Analysis**  
**(in ug/l)**

**Compound**

**SS-CS-5W**

**SS-CS-8W**

Prometon

NQ

- Material was analyzed for but not detected.  
NQ - Not quantified

DRAFT

**Table XII**  
**Saad Site - Phase II**  
**Soil/Sediment Samples**  
**Inorganic Analysis<sup>(1)</sup>**  
**(in ug/kg)**

Element	SS-CS-1	SS-CS-2	SS-CS-3	SS-CS-3A	SS-CS-4	SS-CS-5S	SS-CS-6	SS-CS-7	SS-CS-8S
Aluminum	2,500,000	3,000,000	1,600,000	1,300,000	2,000,000	930,000	2,100,000	1,800,000	2,900,000
Manganese	280,000	230,000	220,000	160,000	240,000	260,000	130,000	240,000	230,000
Iron	1,400,000	860,000	770,000	610,000	480,000	1,200,000	420,000	500,000	1,700,000
Cyanide*	-	-	-	-	3,400	1,000	-	-	-

\* Priority pollutant

- Material was analyzed for but not detected.

(1) Data reported on a wet weight basis.

Table XII  
Saad Site - Phase II  
Soil/Sediment Samples  
Inorganic Analysis<sup>(1)</sup>  
(in ug/kg)

Element	SS-CS-1	SS-CS-2	SS-CS-3	SS-CS-3A	SS-CS-4	SS-CS-5S	SS-CS-6	SS-CS-7	SS-CS-8S
Silver *	-	-	-	2,700	-	-	-	-	-
Barium	35,000	33,000	46,000	-	48,000	120,000	22,000	30,000	25,000
Cadmium*	900	200	3,900	1,700	1,300	1,100	500	1,000	1,100
Cobalt	-	-	-	9,100	-	-	-	-	-
Chromium*	3,300	2,400	5,100	4,700	2,500	3,700	2,600	3,300	6,500
Copper*	7,200	-	10,000	7,300	9,400	24,000	-	-	9,600
Nickel*	-	-	7,500	10,000	-	6,700	-	-	5,200
Lead*	11,000	-	110,000	56,000	210,000	51,000	-	38,000	17,000
Selenium*	2,700	4,200	2,900	3,800	3,200	1,900	2,000	3,200	3,100
Zinc*	13,000	12,000	160,000	160,000	110,000	58,000	4,100	18,000	41,000

**Table XIII**  
**Saad Site - Phase II**  
**Soil/Sediment Samples**  
**Purgeable Organic Analysis**  
**(in ug/kg)(1)**

Compound	SS-CS-1	SS-CS-2	SS-CS-3	SS-CS-3A	SS-CS-4	SS-CS-5	SS-CS-6	SS-CS-7	SS-CS-8S
Methylene Chloride*	-	-	-	88	34	-	-	-	-
1,1,1-Trichloroethane*	-	-	-	-	1.5 J	-	-	-	-
Trichlorotrifluoroethane	-	3,300 JN	-	-	-	-	3.7 JN	5.1 JN	-
Trimethylpentane	-	2,500 JN	-	-	-	-	-	-	-
Fluorotrichloromethane	-	-	3.6	-	4.4	-	3,400	5.3	-
Hexane	-	-	-	-	-	-	2.6 JN	-	-
Acetone	-	-	-	-	-	-	-	-	19 J
2-hexanone	-	-	-	-	-	-	-	-	-

- Material was analyzed for but not detected.

J Estimated value.

N Presumptive evidence of presence of material.

\* Priority pollutant.

(1) Data reported on wet weight basis.

Table XIV (continued)  
 Sand Site - Phase II  
 Soil/Sediment Samples  
 Extractable Organic Analysis  
 (ug/kg)(3)

Compound	SS-CS-1(1)	SS-CS-2(1)	SS-CS-3(2)	SS-CS-3A(2)	SS-CS-4	SS-CS-5S(1)	SS-CS-6(1)	SS-CS-7(1)	SS-CS-8S
Indeno(1,2,3-CD)Pyrene*	-	800 J	-	-	-	-	-	-	-
Dibenzo(A,H)Anthracene*	-	800 J	-	-	-	-	-	-	-
Benzo(6H)Perylene*	-	800 J	-	-	-	-	-	-	-
Hydroxymethylpentanone	550 JN	-	-	400 JN	-	-	-	0.32 JN	-
Tetradecanoic Acid	-	-	-	1300 JN	-	-	-	-	-
Pentadecanoic Acid	-	-	-	600 JN	-	-	-	-	-
Hexadecanoic Acid	-	-	-	4100 JN	-	-	-	-	-
Octadecanoic Acid	-	-	-	800 JN	-	-	-	-	-
Hexane	-	-	-	-	-	1800 JN	-	-	-
Petroleum Product	-	-	-	-	-	N	-	-	-

**Table XV**  
**Saad Site - Phase III**  
**Water Samples**  
**Inorganic Analysis**  
**(in ug/l)**

Element	SS- WT-1	SS- CF-MW2	SS- CF-MW3	SS- CF-MW4	SS- CF-MW5	SS- LN-MW6	SS- SS-MW7
Arsenic*	-	-	-	-	-	-	35
Cadmium*	400	4	4	-	5	5	6
Chromium*	18	-	-	-	16	-	32
Nickel*	-	-	-	-	-	66	65
Lead*	9	18	47	20	15	24	41
Selenium*	11	-	-	-	-	-	-
Zinc*	49	54	58	53	54	51	46
Aluminum	530	430	5,200	100	-	-	7,800
Manganese	44	250	5,000	6,500	730	780	21,000
Iron	740	670	11,000	12,000	7,200	1,600	50,000

\* Priority pollutant.

- Material was analyzed for but not detected



**Table XVI**  
**Saad Site - Phase III**  
**Water Samples**  
**Purgeable Organic Analysis**  
**(in ug/l)**

Compound	SS-(1) WT-1	SS- CF-MW2	SS- CF-MW3	SS- CF-MW4	SS-(1) CF-MW5	SS-(1) LN-MW6	SS- SS-MW7
Vinyl Chloride*	-	-	-	-	-	-	6,600
Chloroethane*	-	-	-	61	-	15	240
Methylene Chloride*	-	-	-	-	-	-	19,000
1,1 - Dichloroethene	-	-	-	-	-	-	690
1,1 - Dichloroethane*	-	-	-	67	-	21	1,100
Trans-1,2-Dichloroethene	-	-	-	10 J	-	-	95,000
Chloroform*	74	-	-	-	-	-	11
1,2-Dichloroethane*	-	-	-	-	-	-	31
1,1,1-Trichloroethane*	-	-	-	-	-	69	15,000
Bromodichloromethane	10	-	-	-	-	-	-
Trichloroethene	-	-	-	-	-	240	69,000
Benzene*	-	-	-	-	-	10 J	67
Tetrachloroethene	-	-	-	-	-	-	49,000
Toluene*	-	-	-	-	-	10 J	3,900
Chlorobenzene*	-	-	-	-	-	-	87
Ethyl Benzene*	-	-	-	-	-	-	-

280589

Table XVI (continued)  
Saad Site - Phase III  
Water Samples  
Purgeable Organic Analysis  
(in ug/l)

Compound	SS-(1) WT-1	SS- CF-MW2	SS- CF-MW3	SS- CF-MW4	SS-(1) CF-MW5	SS-(1) LN-MW6	SS- SS-MW7
Acetone	NQ	-	-	NQ	-	NQ	NQ
Methylcyclohexane	-	NQ	-	NQ	-	NQ	NQ
Dichloroflouromethane	-	-	-	NQ	-	-	-
Cyclohexane	-	-	-	NQ	-	-	-
Dimethylheptadienyne	-	-	-	-	-	-	NQ
Hexanone	-	-	-	-	-	-	NQ
Propylheptanol	-	-	-	-	-	-	NQ
Methylheptane	-	-	-	-	-	-	NQ
Trichloroflouromethane	-	-	-	-	-	-	10 J
Unidentified Compounds(2)	-	-	-	1	-	1	2

- Material was analyzed for but not detected.

\* Priority pollutant.

J Estimated value.

NQ Not quantified

(1) Quantity is suspect based on QC data.

(2) Reported in number of compounds detected, not ug/l.

**Table XVII**  
**Saad Site - Phase III**  
**Water Samples**  
**Extractable Organic Analysis**  
**(in ug/l)**

Compound	SS- WT-1	SS- CF-MW2	SS-(1) CF-MW3	SS-(1) CF-MW4	SS- CF-MW5	SS- LN-MW6	SS- SS-MW7
Phenol*	-	-	-	-	-	-	960
2,4-Dimethylphenol*	-	-	-	-	-	-	33
4-Chloro-3-Methylphenol	-	-	-	-	-	-	25 J
Trimethylphenol	-	-	-	-	-	-	NQ
Methylethylphenol	-	-	-	-	-	-	NQ
Phosphonic Acid, Tributyl Ester	-	-	-	-	-	-	NQ
Unidentified Compounds (2)	-	-	9	-	6	-	9

- Material was analyzed for but not detected.

\* Priority pollutant.

NQ Not quantified.

J Estimated value.

(1) Quantity for phenols is suspect based on QC data.

(2) Reported in number of compounds detected, not in ug/l.

Table XIX  
Saad Oil Company  
Nashville, TN  
Field Data

Station	pH (SU)	Temperature C °	Conductivity (umhos)
SS-CW-8W(1)	7.80	28	-
SS-CS-5W (1)	9.47	35	-
SS-S-7-W	5.04	17.5	-
SS-S-3.1-W	5.47	16.6	-
SS-S-6.1-W	4.77	16.2	-
SS-SP4-5-W	5.40	16.1	-
SS-S-2-W	6.36	17.8	-
SS-T-2-W	6.23	17.3	-
SS-BC-W	7.11	17.3	-
SS-PW-1W	7.07	18.8	560
SS-PW-2W	6.51	19.1	450
SS-LN-DL-W	7.52	29.8	-
SS-LN-DS-W	6.81	27.6	-
SS-FB-W	5.5	25.9	-
SS-WT-1	7.45	23.0	-
SS-CF-MW2	7.54	20.0	-
SS-CF-MW3	6.37	23.0	-
SS-CF-MW4	NA	NA	-
SS-CF-MW5	6.95	18.0	-
SS-LN-MW6	6.35	21.0	-
SS-SS-MW7	6.18	19.0	-

NA - Not available

- Measurement not taken.

Table XVIII  
Saad Site - Phase III  
Nashville, Tennessee  
Water Samples  
Diesel Fuel Analysis  
(in mg/l)(1)

	SS- CF-MW2	SS- CF-MW3	SS- CF-MW4	SS- CF-MW5	SS- LN-MW6	SS- SS-MW7	SS- CF-SP
Diesel Fuel	5u	15u	15u	15u	5u	55(2)	5u

u - material was analyzed for but not detected, number is minimum detection limit.

(1) Gas Chromatographic Method

(2) Oil and Grease by gravimetric analysis - results were 65 mg/L

APPENDIX G

DAILY CHRONOLOGY OF FIELD ACTIVITIES

**TABLE 4**  
**DAILY CHRONOLOGY OF FIELD ACTIVITIES**

<u>DATE</u>	<u>ACTIVITY</u>
March 17, Tuesday	Health & Safety Meeting Begin Tank Sampling
March 18, Wednesday	Finish Tank Sampling Borehole 4 Borehole 14 Borehole 15 Borehole 16
March 19, Thursday	Borehole 1 Borehole 2 Borehole 3 Borehole 17 Borehole 18
March 20, Friday	Borehole 5 Borehole 6 Borehole 19 Borehole 20 Survey
March 21, Saturday	Borehole 7 Borehole 8 Borehole 9 Borehole 10 Borehole 12 Survey
March 22, Sunday	Borehole 11 Borehole 21 Survey
March 23, Monday	Collect Water Samples Redrill B-17, B-19, B-21
March 24, Tuesday	Borehole 13 Collect Water Sample Install Monitoring Well at B-18
March 25, Wednesday	Collect Water Sample Install Monitoring Well at B-11 Skimmer Test B-11
March 26, Thursday	Finish Survey Install Monitoring Well at B-14 Finish Water Sample Collection Redrill B-7
March 27, Friday	Site Clean-up